

Oil Mill Creek Municipal Drain Report

For The City of Port Colborne



February 27, 2025

Project No: EWB-199998

Copyright © 2025, all rights reserved

February 27, 2025

Attention: Alana Vander Veen
City of Port Colborne
1 Killaly St W
Port Colborne, ON L3K 6H1
Alana.VanderVeen@portcolborne.ca

Dear Ms. Vander Veen:

This letter amends the scope of the proposed work to reflect the changes requested by Council after the first meeting to consider the report as presented on September 3rd, 2024.


The proposed works for the Centennial Park wetland; drawings, specifications and costs are removed from the Report's proposed scope of work. The descriptions within the Report remain as the City seeks an alternative finance method for the wetland. The amended proposed works do not include any works associated with the constructed runoff storage feature. All other proposed works identified in the Report remain with no other modifications or changes.

The engineering fee is reduced by \$21,742., roughly 21% of the design fee that was associated with work on the wetland. The reduction of effort included; drawings, design, modelling and assessment. The City's CAD fee is reduced by 6.4%, a total of \$5,850.

The 3 wetland drawings in the original Oil Mill Creek Drain Report, v101 dated June 20, 2024 are removed from this report, which is now identified as version 102 and dated February 27, 2025. This reduces the cost of the proposed works by \$124,515., the estimated cost of constructing the wetland. All other estimated construction costs have remained the same.

A new assessment table has been provided in the report. The assessment calculations shown in Appendix B are updated based on the changes described.

Yours truly,



Paul C. Marsh, P.Eng.
Principal Engineer
EWA Engineering Inc.

**City of Port Colborne
Oil Mill Creek Drain Report**


Revision and Version Tracking

Title: Oil Mill Creek Drain Report
Submission Date: February 27, 2025

Version #	Issued As:	Prepared by	QA/QC	Editor	Date:
102	Scope Ammended Report	P.Marsh		P.Marsh	Feb 27, 2025
101	Final Report Adjusted	P.Marsh	A. Vander Veen	P.Marsh	June 20, 2024 April 29, 2024
100	Final Report	P. Marsh	Grammarly	P. Marsh	Dec. 4, 2023
90	Draft Report for Comment	P. Marsh	A. Vander Veen	P. Marsh	Sept. 12, 2023
50					

FileName: 199998-OMC_DrainReport_v102.docx

Seal Page:



© 2025 EWA Engineering Inc.

The conclusions, analysis and interpretations are based on the data and information available and in the condition and accuracy provided. EWA Engineering assumes no responsibility for data provided by others and has not reviewed nor verified the data's reliability, accuracy or representation.

The information contained in this document is solely for the use of the Client identified on the cover sheet for the purpose for which it has been prepared, and EWA Engineering Inc. recognizes nor accepts the duty to or accepts any responsibility to any third party who may rely upon this document.

This document may not be used for any purpose other than that provided in the contract between the Owner/Client and the Engineer, nor may any section or element of this document be removed, reproduced, electronically stored or transmitted in any form.

Table of Contents

1	Executive Summary.....	1
2	Introduction.....	3
2.1	Objective	4
3	Background.....	5
3.1	Drain History and Past Reports.....	5
3.2	Oil Mill Creek Drain Watershed.....	5
4	Design Considerations	8
4.1	Design Scope	8
4.2	Watershed Characterization and Use	10
4.3	Oil Mill Creek Outlet	11
4.3.1	Gate and Outlet Capacity Assessment	12
4.4	OMC West Branch.....	13
4.5	Bell Acres	14
5	Drain Works Recommendations	15
5.1	Design Criteria.....	15
5.2	Description of the Works.....	15
5.2.1	Municipal and Private Crossings	16
5.2.2	Drain Grade Improvements	18
5.2.2.1	West Branch Grade Line Improvements	18
5.2.2.2	E1 Branch Grade Line Improvements	19
5.2.2.3	Bell Acres Outlet SWM Controls.....	20
5.2.3	Drain Integrated Watershed Improvements.....	20
5.2.4	Utility Conflicts & Coordination.....	24
5.2.5	Plans, Profiles & Specifications	24
5.2.6	Outlet Improvements	24
5.3	Construction and Constructability.....	25
5.3.1	Vegetation Removal	25
5.3.2	Spoil Material	26
5.3.2.1	Contaminated Spoils.....	26
5.3.3	Revegetation.....	27
5.3.4	Private Drain Connections	27
5.4	Future Maintenance and Repair Provisions.....	27
5.5	Construction Summary.....	30
6	Drainage Works Financing	34
6.1	Eligible Cost of Works.....	34
6.1.1	Admin & Engineering Costs	34
6.2	Capital Construction Cost.....	35
6.3	Maintenance Costs	35
6.4	Principles of Assessment.....	35
6.4.1	Allowances:.....	40
6.4.2	Riparian versus Watershed Benefit.....	41
6.4.3	General Instructions to Property Owners, Road Authorities and Public Utilities	42
6.4.4	Grants.....	43
6.5	Cost, Allowance and Assessment Schedules.....	43
7	Oil Mill Creek Drain Report Conclusions	52

Appendix A: Drainage Design Drawings; Plans, Profiles	
Appendix B: Cost Estimates & Assessment Schedules	
Appendix C: Supplementary Information & Documents	
Appendix D: Specifications	
Appendix E: Assessment Map Atlas	

Table of Contents (continued)

Figures

Figure 1 Oil Mill Creek Drain	3
Figure 2 Oil Mill Creek Drain	7
Figure 3 Lake Erie monthly mean water levels, m to IGLD 1985.....	11
Figure 4 OMC Outlet.....	12
Figure 5 OMC Outlet Flap Gate.....	13
Figure 6 Bell Acres Roadside Swale.....	15
Figure 7 West Branch Proposed Grade Improvements.....	19
Figure 8 E1 Branch Design Grade Improvement	20
Figure 9 Centennial Park Culverts Proposed Riffles and Pool.....	21
Figure 10 Centennial Park Proposed Wetland.....	22
Figure 11 Proposed Wetland Inlet/Outlet Weir.....	22
Figure 12 Oil Mill Creek Grade Lines to Proposed Wetland	23
Figure 13 Centennial Park Proposed Wetland Hydrograph Results	23
Figure 14 Outlet Gate Passive Flow Changes	25

Tables

Table 1 Culvert Improvements	17
Table 2 Oil Mill Creek Drain Construction Summary.....	30
Table 3 West Branch Drain Construction Summary.....	30
Table 4 Oil Mill Creek Drain Maintenance Construction Summary	31
Table 5 E1, E2 and E3 Branch Drain Construction Summary	32
Table 6 Oil Mill Creek Estimated Cost of Construction	35
Table 7 Section 24 Special Assessments.....	38
Table 8 Oil Mill Creek Drain Assessment Summary.....	44

1 Executive Summary

On July 23, 2018, the City of Port Colborne approved the appointment of a Drainage Engineer, Paul Marsh, P.Eng. from EWA Engineering Inc., in accordance with the Drainage Act, Chapter D.17 of the Revised Statutes of Ontario, Section 74 & 78 to prepare an Engineer's Report for the Oil Mill Creek Drain within the City of Port Colborne.

Oil Mill Creek (OMC) Drain has experienced the following issues:

- The outlet has a low grade line to a steel flap gate controlled outfall positioned at the water's edge. The outlet is flow constrained with an effective limit on the flow to Lake Erie. The flap gate is manually operated using a hand crank operated winch mounted on top of the outlet structure.
- The upper portion of the watershed has an average slope of 0.15%, with one segment at 0.46% compared to the segment just in front of the outlet pipe intake at 0.04%. This results in a relatively quick runoff to the middle of the OMC Drain and then relatively slow through the outfall.
- Past excavations and the presence of rock outcrop compromise the West Branch positive drain grade.
- The Bell Acres subdivision has a reported problem with the existing roadside swale drainage system.

These and other drainage problems were investigated, and the following is a summary list of the proposed improvements in this report.

- A. Improvements in the operation of the outfall flap gate.
- B. Updated grade line drawings.
- C. Lowered grade line for E1 for the Bell Acres subdivision.
- D. Proposed rock removal of the existing grade hump on the West Branch to create a positive grade flow path to the West Branch Drain outlet at 0+475 OMC Drain.
- E. Construction of a wetland within Centennial Park to act as a stormwater runoff storage facility to reduce the flooding impact of the OMC Drain.

In addition to these specific programmed improvements, there are additional culvert replacements, repairs, and maintenance works based on the new grade lines.

The project cost is estimated to be \$611,601.33.

The project estimate is divided into main and branch drain costs.

• Construction Management Estimated Costs	\$41,000.00
Section 78 - Proposed Improvements for Construction	
• OMC Outlet Improvements	\$27,637.50
• Oil Mill Creek Improvements 0+360 to 0+480 Centennial Wetland	\$124,515.40
• West Branch Improvements - 968m	\$69,025.00
• E1 Branch Drain Sta 0+515 to 0+880	\$11,975.00
• E1 Branch Drain Sta 0+880 to Sta 1+277	\$6,455.00
Section 74 - Maintenance Works for Construction	
• E3 Branch	\$10,145.00
• E2 Branch	\$13,300.00
• Oil Mill Creek Drain - Upper Watershed	\$39,325.00

For a total construction cost of \$343,377.90.

The proposed OMC outlet and the OMC Centennial Wetland are improvements assessed to upstream landowners as Section 23 liability on a property area and land use basis. The same assessment, Section 23 liability is used for the West Branch grade line improvements that remove rock to grade.

The maintenance works, Section 74, are assessed on a Section 23 liability basis, and the culvert replacements are based on Section 24 special benefits, with 50% of the cost assigned to the benefitting landowner and 50% of the cost assessed to the watershed except for culverts at or near the outlet. The exception to the 50/50 approach is the existing concrete culvert, O-CS-08, which is to be re-laid to the design grade. The cost for this is assessed 100% to the municipal road.

There are Section 26 assessments for utilities responsible for specific infrastructure within the drainage works.

This report and the proposed improvements are based on instructions from the City of Port Colborne and in consultation with the local landowners. The cost of these improvements is shared with property owners using calculations for allowances and assessments consistent with the Drainage Act of Ontario.

2 Introduction

The City of Port Colborne retained Paul Marsh, P.Eng of EWA Engineers Inc., to prepare a Drainage Report under the Drainage Act R.S.O. 1990 for the Oil Mill Creek Drain.

The following Figure identifies the existing drain channels.




Figure 1 Oil Mill Creek Drain

This report includes a description of all work, associated plans, cost estimates, and assessment schedules for the proposed work on the existing Oil Mill Creek Drain and the proposed Branch Drains. The report has been prepared in accordance with the requirements of the Drainage Act, Chapter D.17 of the Revised Statutes of Ontario, Sections 4 and 78.

The Oil Mill Creek Drain Engineer's Report is prepared as follows:

- Baseline Drainage Report: provides an assessment of current drainage problems and identifies the extent of the drainage area to be serviced by the municipal drain. Baseline report includes a history of drainage and presents historical information such as grade lines.
- The Oil Mill Creek Watershed Assessment Report provides an assessment of existing capacity through hydrologic and hydraulic modelling, which identifies the options for resolving problems and recommends a preferred option to improve drainage.

The final Engineer's Report comprises the two previous reports, supporting documentation, final drainage cost estimates, and an assessment schedule or table.

The proposed improvement work for the Oil Mill Creek Drain is prepared as a Section 78 (1.1) of the Drainage Act. The works are described as maintenance except changes to grade lines, which are deemed required but do not require a Section 78 or 4 application of the Act.

2.1 Objective

The Oil Mill Creek Drain already exists and has for many years. The objective is maintaining the existing drains in a State of Good Repair (SOGR). Changes in land use practices have impacted the drains, and the shift from farming with row crops to significant numbers of rural residential lots affects the drains' function and purpose. The drains have been impacted by vegetation growth within the drain banks. This report addresses the growth through cleaning and clearing. This report provides a re-grading of the drain and branch drains in recognition of flow improvements.

No previously completed drainage works are included in this report.

The following were the original identified drainage services to be covered in the final report.

1. The existing outlet is working but will be reviewed for operational improvements, including a review of the existing 'j' shaped break wall structure.
2. The existing outlet includes a pump configuration with a maintenance hole for the wet well and an existing pipe for discharge. Investigate the cost vs benefit to re-instate the pump and consider a new pump station configuration.
3. The existing park located on the main branch of the drain is to be reviewed in the context of the park's relationship with the Drain. Specifically, it includes a stormwater management feature such as a pond or wetland along with a re-alignment of the existing swales to make improvements by increasing the available flow volumes for more significant precipitation events.

4. Ensure that the catchment boundaries between adjacent drains are consistent.
5. Investigate additional service capabilities to the Richard Avenue, Tammy Avenue and Tracey Terrace area called Bell Acres.
6. Review existing service to Merkel Rd., June Rd. and Firelane 4.
7. Review the structural (current condition) and capacity of culverts.
8. There was a past drawing to introduce a second outlet for the West Branch down Pinecrest Rd. However, this work does not appear to have progressed to a report. Review the cost benefit of a second outlet on Pinecrest Rd.
9. Investigate the benefits vs costs of a second outlet at or near 2685 Vimy Ridge Rd. This location would be protected from storms as it is on the back side of the point.

3 Background

3.1 Drain History and Past Reports

The earliest record of works related to the Oil Mill Creek Drain is 1888 with a report to extend the Drain and outlet improvement, a Report prepared by Geo. Ross. Up to the most recent report prepared in 1999, by K.Smart. This report included a Court of Revision and a Drainage Tribunal. The Tribunal's findings were reassessments. See file 2000onafrat30.pdf, which is included in the Baseline Report.

3.2 Oil Mill Creek Drain Watershed

The Oil Mill Creek Drain serves an area of 255.7 hectares based on the defined drain boundary. The main branch of the drain is 2,008m in length from the drain origin, defined as the south side of the Friendship Trail to the outlet into Lake Erie.

The watershed boundary is south of Highway 3 with a high point midway between Pinecrest Rd and Cedar Bay Rd, which is 182m. The outlet at the lake varies with the change in Lake Levels, but the recorded average lake level is 174.15 IGLD.

- Watershed average fall (slope) is given as 0.27% or 2.7m per 1000m
- Drain average fall (slope) is given as 0.13% or 1.3m per 1000m

This slope characterizes the Oil Mill Creek drain as a low slope or slow watershed.

The lower portion of the drain is highly influenced by Lake Erie's water elevation with a littoral sand beach influenced outlet that has a specially constructed outlet including a J-shaped break wall.

The Oil Mill Creek drain can be segregated into several distinct geographic areas as follows:

- E1 Branch
- E2 and E3 Branches
- West Branch
- Oil Mill Creek Drain

These five zones are described in more detail as follows.

Oil Mill Creek E1 Branch

E1 is 1277m long and with an overall grade of 0.23%. It's been over dug from the original RVA profile in several places.

Oil Mill Creek E2 & E3 Branches

E2 was lowered from its original intended profile mostly at the outlet as expected, creating a considerable grade back to Merkel Rd (original grade RVA 0.44% is now 0.54%). The 325m Drain has an overall grade of 0.54%, making it the steepest portion of the Oil Mill Creek drain segments.

E3 is 223m long with an overall grade of 0.22%, corresponding to 2.2m over 1000m of fall. The survey recorded significant ponded or still water with a culvert submerged.

Oil Mill Creek West Branch

The West Branch has a shallow grade profile over its 1265m of length, making it one of the poorer functioning portions of the Oil Mill Creek. The overall grade is 0.05% or 0.5m per 1000m.

Oil Mill Creek Drain

By design, the Oil Mill Creek Drain has a very low grade in the first 600m of the drain, roughly to the point of confluence with the West Branch outlet. From the point adjacent to Pinecrest Road, there is an improved grade line to the Friendship Trail.



4 Design Considerations

The Oil Mill Creek Watershed analysis is based on Hydrologic and Hydraulic analysis to predict runoff flow requirements and match channel capacity. Water monitoring and gauge measurements have not been practiced in the past; thus, calibration or validation of the computer-based model results is limited to historical anecdotal comparisons.

Included under a separate copy is the Report Titled “Oil Mill Creek Drain Watershed, Hydrology and Hydraulics Report.”

4.1 Design Scope

Review existing drains for improved maintenance where required and identify working zones and access as needed.

OMC Outlet improvements Sect. 78

- 1 Investigate design improvements to the surge/seiche control gate structure. Identify 3 options for consideration. Provide a Cost vs Benefit analysis of each and provide the final design for the preferred option.
- 2 Assess Opportunities to restore pumping. Develop preliminary design. Assess costs. Two Options to be considered:
 - #1 Restore existing but replace the discharge pipe.
 - #2 use existing wet well but replace discharge and suction pipelines. Suction line to draw from steel pipe built in 2000.
- 3 Provide improvements to the trash rack at the outlet entrance. This work was removed as the trash rack was identified as being adequate at this time.

Oil Mill Creek Main Branch as Sect. 74

Culvert improvements and Grade control 0+350 to 0+900 and to the End of the Drain (EOD) at 1+300.

West Branch STA 0+000 to 1+188 Sect 78

Survey investigation and past plan review

- Plan review indicates the use of clay as a means to level the grade line at the upstream portion of the existing Drain. Today, this past work appears compromised and no longer a functional positive grade. The rock hump causes a degraded positive slope within the West Branch outlet.

Bell Branch – Proposed STA 0+000 to 1+150

Trapezoidal channel south of the Friendship Trail

- Survey investigation and discussion with Mr. Vander Vart indicated the presence of rock along the proposed drainage pathway. The extent of rock present and the proposed grade line makes this pathway too

expensive as an option. However, using the existing connection to E1 and changing the E1 Grade line can deliver similar benefits.

Improved outlet conditions for Richard Ave, Tracey Terrace, and Tammy Ave. Three outlet connections to the existing channel are to be designed using the existing E1 Branch as the outlet.

Provide improved Grade Line to lower outlet elevation Sect 78

E1 Branch STA 0+000 to 1+278

- Review and improve grade line where possible.

E2 Branch STA 0+000 to 0+329 Sect 78

- New design grade line and improved connections to existing and proposed drainage on Merkel Rd, June Rd and Firelane 4.

E3 Branch STA 0+000 to 0+239 Sect 78

- New design grade line and culvert improvement

Merkel Branch – Possible by Petition Sect. 4

- The design review identified some options for service but determined them not to be cost-effective or otherwise difficult to implement.

Centennial Park Wetland integrated with E1 as an overflow interceptor. Sect. 78

- Incorporate existing parklands into a wetland detention basin, providing peak flow detention.

E2 overflow outlet to the proposed Centennial Wetland.

4.2 Watershed Characterization and Use

The Oil Mill Creek Drain Watershed is characterized through land use as a design consideration in the following ways:

1. Upper watershed has a barrier to overland flow south from the former CNR tracks, now the Friendship Trail. All lands north of the Friendship Trail are collected to a crossing located on the east side of Pinecrest Rd from north to south across the Friendship Trail.
2. The Oil Mill Creek is located on the edge of Pinecrest Rd with an overall grade of 0.23% and one 185m segment at 0.46%. Lands west of Pinecrest Rd are predominately row crop farms and connect through a municipal road culvert across Pinecrest Rd at station 0+905.
3. Branch E1 serves lands east of Pinecrest Rd over to Cedar Bay Rd, including the Bell Acres subdivision. With a fair grade line with south westerly orientation and rock outcrop influences in alignment, there is a mix of urban residential with row crop farmland in the upper portion and outlets to the OMC Drain through a designated wetland at station 0+705.
4. West Branch is predominately lakeshore influenced lands with a very low slope municipal drain providing service to urban properties with some row crops or farmland in the northwest portion of the catchment. The drain is influenced by a rock outcrop through the middle of the drain. The West Branch also outlets through a designated wetland.
5. E2 and E3 Branches serve urban properties west and east of Cedar Bay Rd at the south end of the catchment. Two existing outlets connect to the OMC Drain at station 0+303 for E3 and 0+322 for E2.
6. The OMC Drain outlets through a historical stream connection through the existing dune and lakeshore environment, which was converted into a concrete pipe conveyance with pumping in the 1960s and extended north of Vimy Ridge Rd in 1999 to connect to the existing box culvert crossing and providing a closed conduit over 122m of outlet. Upstream areas include urban properties and Centennial Park.

These are general descriptions of the watershed areas, and for more details, see the included maps and drawings in Appendix A.

Lake Erie Levels

In geologic time, Lake Erie levels have varied depending on glaciation and the various flow sills that have existed in and out of the Great Lakes basin. These sills have changed in elevation as landforms rebounded from the effects of glaciation. In the modern period, Lake Erie levels are dominated by flows out of Lake Huron and out of Lake Erie into the Niagara River and Welland Canal system.

The Government of Canada Fisheries & Oceans Hydrographic Service provides the following historic Lake levels based on 100+ years of monitoring data and

statistics. The values are quoted in monthly mean water levels reference to IGLD 1985.

Yearly Average

174.17

Minimum Monthly

173.18

Maximum Monthly

175.04




Figure 3 Lake Erie monthly mean water levels, m to IGLD 1985

The Lake Erie level influences Oil Mill Creek, and the lake continuously affects outlet flows. There are two effects from the lake;

- Flows to outlet. Once the lake level is below the outlet pipe invert, outflow is unimpeded, but once the water surface is above the pipe invert, then the rate of flow out can still be positive but is not free flowing.
- Storm surges cause flows to run backwards up the pipe.

These effects are influenced and controlled by the outlet gate position.

4.3 Oil Mill Creek Outlet

The outlet has been composed of a piped portion for quite a long time. The piping still being used is estimated to be from the 1960s and initially commenced at the south limit of the existing properties along the outlet, conveying runoff to the lake through pipes and an outlet structure.



Figure 4 OMC Outlet

The original pumping was in place to benefit the upstream areas within the Oil Mill Creek watershed. The pump hasn't been in use for a significant amount of time, and the extension of the closed conduit portion extends past the former suction point of the pumping system another 74m upstream.

The existing steel pipe, shown in Figure 5, has significant rust, but pipe integrity is not assessed, and thus, it is not known if the discharge piping could still be used. No flap or other backflow prevention device exists on the pipe discharge outlet.

4.3.1 Gate and Outlet Capacity Assessment

The existing outlet gate is composed of three primary parts;

- A trapezoidal concrete outlet consisting of wing walls and headwall with a flat roof as cover.
- A swing grate made of steel that covers and protects the outlet.
- A top hinged steel flap gate that closes against a concrete outlet headwall to prevent high lake water surface levels from pushing flow backward.



Figure 5 OMC Outlet Flap Gate

The gate is heavy, approximately 400 kg, and open or closed using a winch with a handle mounted on the top of the concrete outlet. It is possible for the flow to push the gate open where the pressure of the flow against the gate is greater than the weight of the gate. If the winch pulls the gate open, it does not prevent the lake from flowing backwards up the drain through the outlet. The flow is only controlled if the gate is lowered into position such that it forms a seal against the concrete headwall.

4.4 OMC West Branch

The West Branch of Oil Mill Creek Drain is historically constructed with a low grade outlet at Station 0+475 Oil Mill Creek Drain. The middle of the West Branch was identified in the RVA report as having a rock outcrop, and there was work performed to lower a portion of the rock outcrop and backfilled the upstream portion with a clay liner, (see drawing in Baseline Report).

This appears to have been compromised by subsequent maintenance works or other work.

Culvert inspections identified some non-compliance capacities and structural conditions addressed by this report.

The Hydrology and Hydraulics report identified that the Branch E1 and OMC Drain upper portion, above station 0+905, have significant grade lines such that the runoff is significantly faster than the runoff from the West Branch. The Stormwater model reports the West Branch running backwards in some conditions for a short time as the peak flow from E1 and OMC arrives at the West Branch confluence before the West Branch peak.

This report introduces a new West Branch Grade Line as a Section 78 Drain Improvement. The proposed design grade line requires rock removal and culvert replacement to new design grade inverts. One culvert is to be reused and laid on the proposed grade line.

4.5 Bell Acres

The existing roadside swales and channels were investigated by surveying the existing Bell Acres subdivision. Drawings with plans and profiles to show existing grades to the outlet were composed. This showed that several humps and over-deep sections exist within the roadside swales, as well as culverts installed at incorrect elevations; however, these minor defects do not impact the overall capacity of the existing roadside drainage system. Culvert sizes to determine capacity were not analyzed. The existing rock outcrop significantly influences the design of the existing stormwater swale system.

The existing drainage along roadways within the Bell Acres subdivision will remain roadside swales. The roadway swales outlet to ditch channels that outlet to E1 Branch. These channels will not be converted to Municipal Drains as the municipality has access for maintenance activities.

A new path to the outlet following the west side of property ARN 238600 / Vander Vart was investigated to provide an improved outlet condition. The initial survey was promising, with an improved grade line to OMC, but a second survey of subsurface rock identified significant challenges with the proposed alignment. This option was stopped in favour of continuing with the E1 Branch.

The E1 Branch grade line was compromised slightly by installing twin PE culverts, E1-CS-03, at station 0+566, just above the existing grade line. E1 Branch is improved by lowering the upper portion of the grade line while maintaining the existing lower reach within the designated wetland at the same grade line.



Figure 6 Bell Acres Roadside Swale

5 Drain Works Recommendations

5.1 Design Criteria

Channel size is confirmed to be based on a 1 in 5 year return period storm, which is expressed as a design storm as follows:

- 5-year design storm with a total rainfall amount of 68.90mm using an SCS Type II 24-hour storm distribution.
- 100-year design storm with a total rainfall amount of 121.1mm using an SCS Type II 24-hour storm distribution.

The 100-year design storm is accepted as the Probable Maximum Precipitation (PMP) event for consideration of impacts.

5.2 Description of the Works

The following presents a program of proposed improvement works for the Oil Mill Creek Drain. As a program, some works are staged at various times and may not proceed in a step-by-step manner but on an as and when available basis that best meets environmental and regulatory requirements.

5.2.1 Municipal and Private Crossings

The culverts are identified for replacement for structural or capacity requirements.

O-CS-05 Friendship Trail crossing is the municipally owned culvert being replaced. All other culverts are private access crossing culverts.

The following table identifies the proposed culvert works for drain improvements.

Table 1 Culvert Improvements

Name ID	Crossing	INSP Status	Q 5yr / Q _a	P/Fail	Diam	Material	Work Description	L, m
Oil Mill Creek Drain Culverts for Improvement								
O-CS-05	FRIENDSHIP TRAIL		.93/.58	Fail	500	CSP	Replace with PE 2W 600	11.6
O-CS-12	#851 PINECREST RD. DRIVEWAY			P	600	PE	PE 600	9
O-CS-11	#851 PINECREST RD. DRIVEWAY				600	PE	PE 600	6
O-CS-10	#813 PINECREST RD. DRIVEWAY	Replaced 2023	.		900	PE	Replaced by Roads	8
O-CS-09	#745 PINECREST RD. DRIVEWAY		(.94/.90)	P	750	PE	PE 750	12
O-CS-08	#663 PINECREST RD. DRIVEWAY	PIPE REPAIR REPLACE	.94/.63	Fail	950	Concrete	Reconstruct / Relay with bedding and Joint seal.	8.6
O-CS-06	CENTENNIAL PARK CROSSING		1.9/1.9	P		CSPA Poly-coated	Twin CSPA 1600x1200	6
O-CS-03	#2876 VIMY RIDGE RD. DRIVEWAY		1.9/1.9	P		CSP	1400	
E1 Branch Culverts for Improvement								
E1-CS-01	#663 PINECREST RD. DRIVEWAY		1.52/.73	Fail	700	CSP	CSP 700	5
E1-CS-03	Private Access		1.15/.69	Fail	600	Twin PE	Re-lay on Design Grade line using existing culverts	9
E1-CS-04	CEDAR BAY RD		.22/.22	P	600	CSP	CSP 600	9
E3 Branch Culverts for Improvement								
E3-CS-01	Private Access		.27/.22	Fail	450	CSP	Replace with HDPE 2W 525	6
E3-CS-03	CEDAR BAY RD.		.27/.27	P	450	PE	PE 450	12
West Branch Culverts for Improvement								
WB-CS-04	VIMY RIDGE RD.		.7/.69	P		CSPE 900x600		12.2
WB-CS-05	#2595 VIMY RD. DRIVEWAY	REPLACE	.7/.58	Fail		CSPE 800x600	Replace with CSPA 900x660	6
WB-CS-06	#2555 VIMY RD. DRIVEWAY		.7/.7	P		CSPE 800x600		6
WB-CS-07	PRIVATE DRIVEWAY		.7/.7			CSPA 1400x800		12
WB-CS-08	PINECREST RD.		.7/.7	P		CSPE 800x550		6
WB-CS-09	462 PINECREST RD. DRIVEWAY	REPLACE	.7/.7	Fail		CSP 450	Replace with CSP Arch 800x580	10
WB-CS-10	462 PINECREST RD. DRIVEWAY		.24/.24	P		CSP 600		10
WB-CS-11	446 PINECREST RD. DRIVEWAY	REPLACE	.16/.11	Fail		CSP 450	Replace with CSP Arch 680x500	14.3
WB-CS-12	426 PINECREST RD. DRIVEWAY	REPLACE	.16/.16	P		CSP Arch 900x550	Re-lay on new design grade with existing culvert	
WB-CS-14	2366 FIRELANE 2	REPLACE	.16/.11	Fail		CSP 450	Replace with PE 600	4.4
WB-CS-15	2334 FIRELANE 2	REPLACE	.16/.12	Fail	300	PE	Replace with PE 600	6
WB-CS-17	316 FIRELANE 2	REPLACE	.13/.11	Fail	350	CSP	Replace with PE 450	6

The following describes the recommended improvements for private and municipal drain crossing structures.

West Branch Drain

- Re-lay private access with existing pipe WB-CS-12 on the proposed design grade line.
- Replace 6 private access culverts with the recommended sized culvert at the proposed design grade line.

E1 Branch Drain

- Re-lay private access twin PE pipes E1-CS-03 on the proposed design grade line.

E2 Branch Drain has no culverts for improvement.

E3 Branch Drain

- Existing private culvert, E3-CS-01, in paddock to be replaced with 525mm PE with bedding to support to haunches.

OMC Drain

- Reconstruct O-CS-08 with existing concrete pipe. Re-lay with bedding, grout seal bell/spigot joint connection and backfill with Granular A gravel to design grade line.
- Replace Municipal crossing O-CS-05 at Friendship Trail for capacity requirements

5.2.2 Drain Grade Improvements

There are the distinct grade line improvements identified in the design drawing profiles. They are:

- West Branch starting at 0+647 to 1+170
- E1 Branch starting at 0+515 to EOD at 1+277 (West side of Cedar Bay Rd)

5.2.2.1 West Branch Grade Line Improvements

From the Baseline Report Drawings, the West Branch was identified as having a hump in the existing grade line at the alignment change from Pinecrest Rd to Firelane 2. Specifically at station 0+850 to 0+900 there is a rock hump that prevents the outlet of flows from the upper portion of the Drain along Firelane 2.

The proposed design grade line lowers the grade line by a small amount from station 0+647 to the End of the Drain (EOD).




Figure 7 West Branch Proposed Grade Improvements

The proposed grade change results in changes to the existing culverts. Every effort to use existing culverts has been made. . The benefit is shown in Figure 7 as compared to the existing grade line. This summary chart does not show all the survey details, which are visible in the drawing OM.P5 included in Appendix A.

The improved grade line results in a very slight improvement in drain flow due to improved velocities. However, lowering the grade line through rock is not required to achieve the full design drain bottom and only to achieve the grade at the centreline of the drain. The intent is not to increase existing capacity, although that will be improved slightly, to improve positive grade to outlet to reduce standing water in the upper portion of the drain.

Riparian landowners can anticipate that flooding of the West Branch will still occur as the overall grade to the outlet is still a slow or low-grade drain. Reduced standing water post peak flows should be evident after construction.

5.2.2.2 E1 Branch Grade Line Improvements

The existing drainage concerns within the Bell Acres subdivision are assessed for the existing positive drain to outlet uses the elevations from the survey investigation and site inspection.




Figure 8 E1 Branch Design Grade Improvement

This grade line chart shows the existing over deep section of the E1 Branch with an ascribed design grade line used where no change in the existing grade line will occur. The over deep section will remain and not have maintenance for the lower reach to reestablish a grade line to outlet based on downstream flows.

The design grade line crosses over the existing grade survey line at station 0+515 and shows a lower, improved grade line for 762m to Cedar Bay Rd. This lower grade line allows for the existing channel serving the subdivision to be lower by a similar amount, 150mm to 275mm, and this will improve outlet conditions for the existing roadside swales through the subdivision. Drawing OM.P3 shows the E1 Branch improvement using a yellow fill for existing soil to be removed and spread adjacent to the drain.

The lowering of E1 allows for the improvement of the three swales serving the Bell Acres subdivision and the western edge swale connecting to E1 Branch.

5.2.2.3 Bell Acres Outlet SWM Controls

The improvements to the Bell Acres Subdivision swales with improved grade lines will result in marginally faster and higher peak flows passing downstream. The hydraulic analysis identifies a low-flow culvert with an embankment, including an overflow swale, to decrease the peak flow's downstream effect. This results in water backing in the existing swales during storms but draining away better using the improved grade lines. This work is outside the scope of the Oil Mill Creek Drain Report.

Technical analysis of the flow control method is described in detail in the Oil Mill Creek Watershed Report.

5.2.3 Drain Integrated Watershed Improvements

The existing OMC Drain watershed has components that do not meet the expected design standard of sustaining flows from the 1:5 year design storm,

68.9mm over 24 hours, and these are areas within the Centennial Park where the drain is compromised on an existing grade line to the existing piped outlet.

The proposed improvement for integrated watershed has two features:

- Pool and riffle channel construction above and below the existing culvert on the OMC crossing for the Centennial Park access lane.
- Constructed Wetland within Centennial Park consisting of 6000 m³ of detention storage volume available during peak flows and a 1,000 m³ permanent pool for wetland naturalization.

OMC Pool and Riffle

The functional design intends to restore some positive grade line to outlet in response to the past over digging of the grade line through Centennial Park.




Figure 9 Centennial Park Culverts Proposed Riffles and Pool

Centennial Wetland

The City of Port Colborne identified the opportunity for including a wetland on City owned land to reduce the extent of flooding. This option was identified along with an option to construct a second outlet through the park to the lake. Both options were investigated, and the wetland option was considered the preferred option as the environmental and social impacts were significantly less than construction of a new outlet to the lake through the park.

The wetland works as a stormwater detention facility where the stormwater peak flow is stored in the wetland and then slowly released. This capability is usually implemented with an inflow channel, and an outflow channel with flow control. However, this option was not possible with the existing space in the park. Instead, there is a single channel in, which is also the channel out, and the inflow/outflow structure works on both flows into the wetland and flows out of the wetland.




Figure 10 Centennial Park Proposed Wetland

The inlet/outlet weir has a two stage water control with a low flow notch weir and a higher flow rectangular weir.




Figure 11 Proposed Wetland Inlet/Outlet Weir

The wetland takes the peak runoff from the upper watershed, OMC and E1 contributing flows, and provides a channel and volume for that runoff to go instead of backing into the West Branch and/or overflowing the OMC channel banks in the park. The role of the wetland can be visualized through the following chart of the main Oil Mill Creek watershed grade lines.




Figure 12 Oil Mill Creek Grade Lines to Proposed Wetland

The three contributing areas upstream from the proposed wetland; West Branch, E1 Branch and OMC Main Drain are each roughly 1000m in length, but the West Branch has much less slope over that same distance as E1 or OMC. The Centennial Park Wetland inlet/outlet channel (green line in Figure 13) is designed using a channel slope that is less than the West Branch with the objective that runoff will preferentially fill the wetland before filling the West Branch. The reality is that both will occur, but the existence of the wetland reduces the impact on the West Branch and the downstream runoff.

The Centennial Park Wetland was assessed using the PC-SWM model implemented for the Watershed Hydrology and Hydraulics Report.




Figure 13 Centennial Park Proposed Wetland Hydrograph Results

Figure 13 illustrates the modelling results with the Wetland through the two shaded areas showing the hydrograph upstream and downstream of the Wetland channel. The upside-down hydrograph shows the flows entering the wetland (shown as backward to the direction of the channel in the model).

The rising peak hydrograph, O-07, represents the flow into the West Branch, Wetland and OMC outlet confluence. The modified peak, O-04, represents the flow downstream in OMC after the wetland and West Branch confluence. The peak flow is reduced, but the duration of the receding portion of the hydrograph is longer and slower. The reduction of peak flow from 2.2 m³/s to 1.4 m³/s is due to the success of the wetland and partially from challenges with peak flow through the outlet.

5.2.4 Utility Conflicts & Coordination

Not all utility locations and conflicts are known during design. Where a conflict has been identified a program cost has been allocated for the protection of the utility by the contractor during construction. Moving the utility for the drain hasn't been identified as a requirement during design.

5.2.5 Plans, Profiles & Specifications

The proposed Oil Mill Creek Drain works are described in the attached Plans, Profile Drawings, Specific Design Drawings, and Standard Detail Drawings, which are attached as Appendix A.

Project Specifications are attached in Appendix E.

5.2.6 Outlet Improvements

The following are planned improvements to the outlet and are recommended for consideration as an improvement under Section 78.

1. Relocating the winch from the top of the outlet structure to a position further up the beach, hopefully with less risk to the operator during storms. Alternatively, the winch could be converted to electric power to operate open and close.
2. Install passive flap gate ports on the existing heavy steel gate to accommodate flow switching to outflow in the OMC Drain.




Figure 14 Outlet Gate Passive Flow Changes

The passive flap gate openings are intended to provide outlet flows even when the gate remains lowered. The gate is not really closed or open; it is either in the raised position or in the lowered position. When lowered, wave action or Lake Erie seiche conditions push against the gate, which seals against the outlet and prevents flows from passing upstream.

When the storm recedes, and the OMC flow is outflow instead of inflow, it will push the gate open, provided the force of the flow, or head, is higher than the weight of the gate. Unfortunately, the gate is heavy, and outflow depends on an operator returning to the OMC outlet site and lifting the gate using the hand crank winch. The weight of the gate reduces the passive outflow to only large events and restricts outflow by a significant degree.

Adding two 300mm openings in the lower two central panels of the gate with the installation of two Recycled Vulcanized Rubber covers or flaps allows for flows to pass through the gate even while the gate is lowered. The flexible mat flap has stainless steel angle iron pieces added to it, ensuring that it closes against the steel tightly and prevents backflow. This allows the flow to exit even if the steel flap gate is closed, and the resistance to outflow is the minimal flap gate weight.

For a 0.6m depth behind the steel flap gate, the orifice flow is calculated as 0.13 cms for each flapgate, achieving 0.26 cms for the two passive outlets.

5.3 Construction and Constructability

The following describes the specific requirements for drain construction.

5.3.1 Vegetation Removal

Vegetation, specifically trees are to be cut down outside of any bird nesting periods. The remaining stumps are to remain in place unless they obstruct flow or

they are Ash trees with re-growth from the lower truck already established. The stump will be ground down to match the existing channel section in those cases.

Tree removal within the Top of Bank to Top of Bank is to be 100 percent; however, tree removal within the work zone is at the discretion of the contractor and drainage superintendent while making every effort to preserve trees where possible. Where trees are removed in the work zone, they qualify for the tree replacement program as per the tree qualifying criteria.

5.3.2 Spoil Material

All spoils and spoil handling practices will comply with applicable legislation, including O. Reg. 406/19: ON-SITE AND EXCESS SOIL MANAGEMENT filed December 4, 2019, under the Environmental Protection Act, R.S.O. 1990, c. E.19

Where specified, excavated spoil material shall be disposed of and levelled a minimum of 2.5 m from the top of bank to ensure that sediment does not re-enter the drain. Spoil placed next to the drain shall be spread to permit access across the berm area and shall be placed to a maximum height of 0.6m. Spoil excavated along existing travelled road allowances and on private property, where requested, shall be disposed of by the Contractor off site. The benefiting property owner shall bear the cost of spoil trucked from the property.

Spoil shall be disposed of as noted in the description of the proposed work. Generally, the spoil will be disposed of adjacent to the drain unless otherwise specified. Should any property owner require that all or a portion of the spoil be trucked away from their property, the cost of trucking spoil shall be assessed totally to the property owner requesting same and will not form part of the total cost of the drainage system. The cost of trucking away spoil from any future maintenance work will be assessed directly to the property owner requesting the same. Debris from vegetation removal will be removed from the property or disposed of by agreement of the property owner.

For the reaches of drains within travelled municipal road allowances, the spoil will be trucked away during the initial construction and any future maintenance work where there is no opportunity to dispose of the material on site.

Access channels shall be provided through the levelled spoil material at every location where existing drainage outlets are visible and/or identified during construction by the Drainage Superintendent. The invert of the access channels shall be consistent with the drain cross-section at that location.

Spoil excavated from the drain shall be levelled in a manner suitable for cultivating crops where crops were previously cultivated. Where the drain is adjacent to a grassed area maintained by the owner, the spoil shall be levelled and re-seeded with grass so that the area is restored to a like or better condition than prior to construction.

5.3.2.1 Contaminated Spoils

Where soils are known to be contaminated but have been assessed to pose no human health risk, on site spreading adjacent to the drain will be the practice and acknowledge that the soils are not to be 'moved' off the property.

Where soils are to be removed from the property, a sample will be collected and analyzed for contamination prior to the commencement of removal. Where that sample is shown to be contaminated and disposal of the soil will require disposal at a registered facility in compliance with O.Reg 406/19, the owner will be responsible for the costs to dispose of the contaminated soil from their property.

Once a contaminated sample is returned, the owner will be given the opportunity to retain the soil on site instead of trucking for disposal.

5.3.3 Revegetation

The drain banks should be seeded as quickly as possible after excavating the existing and proposed channels, and the spoil should be seeded on the day of levelling. Seeding should occur in a manner that optimizes seed germination and establishment of vegetation before mid-October and after late April.

Seed mixture used shall be applied at a rate of 40 kg/ha in the following proportions:

Creeping red fescue	20 kg	50%
Perennial ryegrass	8 kg	20%
Birdsfoot trefoil	12 kg	30%
Total	40 kg/ha	100%

5.3.4 Private Drain Connections

Where private connections are made to the Municipal Drain, the connections are to be compliant with the City of Port Colborne's standards connection designs.

This includes the following connection types:

- Open channel connection – minimal allowance for grade and freeboard.
- Surface water flows – rip rap rock requirements for reducing or amending sites of potential or evident erosion.
- Tile drain connections – use PE pipe to connect to a receiving channel.
- Berm and Orifice Flow Control - connections designed to control runoff to specified flow rates.

Private connections are not part of the drain but are owned, and the landowner is responsible for construction and maintenance. Where the Drainage Superintendent or Engineer identifies a deficiency, the landowner is to make good the connection. Deficiencies can be an eroded connection, a blocked connection or a poor connection, and the landowner can accept having work done by the City on their behalf to make good the connection based on a 50/50 cost sharing basis. Where the City identifies a deficiency and the repairs are not made by the landowner by the next cycle of drain maintenance, the City can make the required repairs, and 100% of the cost will be assessed to the landowner.

5.4 Future Maintenance and Repair Provisions

The Drainage Act, Chapter D.17, Sections 74 through 84 governs future maintenance, improvement and repair to any Drainage Works constructed under a By-Law passed under this Act or any predecessor of this Act.

Upon completion of the Oil Mill Creek Drain works described in this Report, the City of Port Colborne will be responsible for future maintenance of the drain with the cost assessed to the upstream lands and roads using the Assessment Schedule in Appendix B and pro-rating the assessment based on the actual cost using the Outlet Liability Assessment – Section 23. Special Assessment shall not apply to maintenance work except where maintenance works are related to culvert/bridge replacement or upgrades.

The following are the identified maintenance sections anticipated to meet the City target of performing maintenance on a drain once every 10 years with a site specific assessment on a 5 year schedule.

- OMC Drain
 - Outlet; including gate and closed conduit to Vimy Ridge Rd 0+119 to 0+000
A Regular Annual visual inspection.
Catchbasin inspection (2), and
a 10 year video inspection and/or Confined Space Entry (CSE) walk-through.
 - Middle 0+000 to 0+905
Where the existing bottom is deeper than the design grade line, no further excavation, bank obstruction removal only.
The riffle and pool addition will restore the grade line with no grade maintenance required. During this time, brushing and bank restoration are recommended on a 10-year cycle or as required by visual inspection on a 5-year cycle.
 - Upper OMC Drain, 0+905 to 1+944 EOD
Perform regular 5 year inspection cycle and maintenance as determined by survey inspection.
- E2 & E3 Branch Drains scheduled maintenance from inspection over length from outlet to EOD
 - E2: 0+000
 - E2: to 0+350 lower reach over excavated and realigned of new outlet monitor at 10 year interval.
 - E3: 0+000 to 0+222 grade reconstruction through paddock monitored at 5-year intervals.
- West Branch
 - West Branch, 0+000 to 0+208 North of Vimy Ridge Rd, minimal maintenance expected from existing over depth to grade line. Spot maintenance where required.
 - WB, 0+208 to 0+647,
regular 5 year inspection cycle and maintenance as determined by survey inspection.
 - WB, 0+647 to 1+188 EOD regular 5 year inspection cycle after rock removal to confirm grade line. Maintenance forecast for light work based on rock to grade line.
- E1 Branch Drain scheduled maintenance reflects proposed works.
 - E1: 0+000 to 0+515 lower than the proposed grade line, monitor only.

- E1: 0+515 to 1+277 inspect on 5-year interval. Maintenance only to grade line with survey validation.

These recommended maintenance and inspection cycles are to be adjusted as evidenced by physical conditions within each Drain and Branch Drain.

5.5 Construction Summary

The following table lists construction activities by property, starting from the outlet and proceeding upstream.

Section 78 – Proposed Improvements

Table 2 Oil Mill Creek Drain Construction Summary

Property / Owner	Drain Side	From STA	To STA	Length	Working Side	Work Description
Oil Mill Creek Drain Outlet Improvements						
271104000231501 / SOUDER, CATHERINE R	Both	0-088.7	0-119.3	30.617	Both	Improvements to the existing outlet: Flap Gate Changes and relocate winch.

Table 3 West Branch Drain Construction Summary

Property / Owner	Drain Side	From STA	To STA	Length	Working Side	Work Description
West Branch Drain						
271104000242101 / PORT COLBORNE CITY		0+000	0+098.5	98.5	East	
271104000241900 / FIDDY, CHARLES JOHN; FIDDY, LILLIAN NICOLE		0+098.5	0+129.1	30.6	East	
271104000242101 / PORT COLBORNE CITY		0+129.1	0+207.6	78.5	East	
Vimy Ridge Road		0+207.6	0+317.3	109.7	West	Replace Culvert WB-CS-05 2595 Vimy Rd. with CSPA 900x660
271104000243200 / FIGUEIRA, MARIO		0+317.3	0+367.0	43.6	West	
271104000243600 / MCADAM, RICHARD WILSON		0+367.0	0+458.7	97.8	West	
Pinecrest Road		0+458.7	0+750.0	291.3	West	Replace Culvert WB-CS-09 462 Pinecrest Rd with CSPA 800x580 excavate to design grade line starting at 0+647
271104000302610 / METCALF, IVANA KOMLIJENOVIC; METCALF, THOMAS ASA		0+750.0	0+780.0	30	South	Replace Culvert WB-CS-11 446 Pinecrest Rd with CSPA 680x500 Excavate to design grade line
271104000302100 / BEGG, TERRY-LYNN		0+780.0	0+854.8	74.8	South	Relay Culvert WB-CS-12 426 Pinecrest Rd. at excavated lower design grade line. Rock removal to project riffles and pool.
271104000301700 / KRIEGER, LESLEY EILEEN		0+854.8	0+889.2	34.4	South	Excavate to design grade line, rock removal to project riffles and pool.
271104000301600 / MORRISON, HALEY MARILYN; MINOR, DUNCAN LINCOLN		0+889.2	0+907.5	34.4	South	Excavate to design grade line, rock removal to project riffles and pool.
271104000301500 / HOLODAY, SUSAN-PIETRAS; HOLODAY, RICHARD		0+907.5	0+957.7	50.2	South	Replace Culvert WB-CS-14 2366 Firelane 2 with PE600 2W. Excavate to design grade line and rock removal to project riffles.
271104000301400 / JASEK, COLLEEN R; JASEK, JOHN M		0+957.7	0+991.6	33.9	South	Replace Culvert WB-CS-15 2334 Firelane 2 with PE600 2W. Excavate to design grade line and rock removal to project riffles.
271104000301300 / GROOM, JOSHUA NATHAN; GROOM, KRISTAL LYNN		0+991.6	1+025.5	33.9	South	Replace Culvert WB-CS-17 316 Firelane 2 with PE450 2W. Excavate to design

						grade line and rock removal to project riffles.
271104000300900 / REPEC, JENNIFER		1+025.5	1+188	162.5	South	Excavate to design grade line and rock removal to project riffles.

Proposed Centennial Wetland Branch Drain

271104000242101 / PORT COLBORNE CITY	Both	0+000	0+173.5	173.5	East	Construction reverse channel to weir to control fill/outlet of runoff stormwater to detention wetland. Excavate detention wetland and stockpile spoils onsite.
--------------------------------------	------	-------	---------	-------	------	---

Section 74 – Maintenance Works

Table 4 Oil Mill Creek Drain Maintenance Construction Summary

Property / Owner	Drain Side	From STA	To STA	Length	Working Side	Work Description
Oil Mill Creek Drain						
271104000232900 / PARR, MARTIN JOHN; PARR, LINDSEY MARIE	Both	0-069.1	0-088.7	19.572	Both	
271104000233100 / PRUYN, FRANCIS MATHEUS ROBERT; PRUYN, HENRIETTE	Both	0-038.8	0-069.1	30.253	Both	reveal and maintain existing PE CB
271104000232900 / PARR, MARTIN JOHN; PARR, LINDSEY MARIE	Both	0-019.6	0-038.8	19.226	Both	
271104000233100 / PRUYN, FRANCIS MATHEUS ROBERT; PRUYN, HENRIETTE	Both	0-016.1	0-019.6	3.457	Both	reveal and maintain existing PE CB
Vimy Ridge Road		0+003.8	0-016.1	16.113	Both	Pipe inspections on an 8 to 10 year cycle. Last inspection was completed in 2016
271104000230000 / SCHULTZ, WINKLEY JANE; SCHULTZ, DOUGLAS ALLEN	Both	0+003.8	0+014.8	11	South side	
271104000230100 / ALEXANDER, KATHRYN RUTH	Both	0+014.8	0+033.5	18.7	South side	
271104000230200 / DE OCAMPO, MARTINIANO; DE OCAMPO, AMELIA	Both	0+033.5	0+049.3	15.8	South side	
271104000230300 / ZIEMIANSKI, DEREK; HOCHREITER, MELISSA MAY	Both	0+049.3	0+065.3	16	South side	
271104000230400 / VAN ESCH, STEVEN CARMEN; VAN ESCH, KAITLIN MICHELLE	Both	0+065.3	0+080.6	15.3	South side	
271104000230500 / GAME, RYAN DOUGLAS; GAME, RENEE MARIE	Both	0+080.6	0+096.3	15.7	South side	
271104000230600 / MCCOMBE, LAURIE; DEROSE, LEONARDO	Both	0+096.3	0+111.9	15.6	South side	
271104000230700 / DEROSE, LEONARDO; MCCOMBE, LAURIE	Both	0+111.9	0+127.3	15.4	South side	

271104000242101 / PORT COLBORNE CITY	Both	0+127.3	0+902.6	775.3	Both	Construct a plunge pool on the downstream side of the existing twin culverts. Construct riffles using West Branch rock spoils. Construct Wetland with branch drain outlet at OMC station 0+424
Pinecrest Road		0+902.6	1+292.6	1026.9	West	At 663 Pinecrest Rd Relay 950mm on proposed grade line with 50mm embedment, 150mm compacted granular base to SPD 95% , concrete grout the joint to seal.
271104000499900 / PORT COLBORNE CITY	Both	1+292.6	1+306.6	14	Both	Replace existing CSP 500 with 750PE 320 kPa to design grade with 25mm embedded.

Table 5 E1, E2 and E3 Branch Drain Construction Summary

Property / Owner	Drain Side	From STA	To STA	Length	Working Side	Work Description
E1 Branch						
271104000242101 / PORT COLBORNE CITY	Both	0+000	0+104.5	104.5	East	
271104000240900 / LAUR CAROL JAYNE ESTATE; LAUR, JOHN THOMAS; LAUR, MICHAEL JOHN	Both	0+104.5	0+846.9	742.4	East / South / East	Excavate to design grade line starting at 0+515 with spoil spread adjacent to the drain. Relay E1-CS-03 twin PE 600mm culverts to design grade line
271104000240710 / KALYNUIK, CATHY ANN; KALYNUIK, JAMES VAN	Both	0+846.9	0+874.6	27.7	East	Excavate to design grade line with spoil spread adjacent to the drain.
271104000238600 / VANDER VAART, LEONARDUS J; VANDER VAART, MARGARET ANN	Both	0+874.6	1+074.2	199.6	South	Excavate to design grade line with spoil spread adjacent to the drain.
271104000238700 / SZABO, MONICA ANN; GRAY, ROGER WAYNE	Both	1+074.2	1+273.5	199.3	South	Excavate to design grade line with spoil spread adjacent to the drain.
Cedar Bay Rd	Both	1+273.5	1+277.0	3.5		
E2 Branch						
271104000242101 / PORT COLBORNE CITY	Left	0+000	0+277.5	277.5	West	re-align 35m of the existing channel with improved flow connection to Oil Mill Creek Drain
271104000238600 / VANDER VAART, LEONARDUS J; VANDER VAART, MARGARET ANN	Left	0+277.5	0+348	70.5	West	Excavate to design grade line starting at station 0+225 to EOD 0+350 with spoil spread adjacent to the drain.
271104000233300 / MARTINEAU, WILFRED ROMEO; MARTINEAU, ROXANNE STEPHANIE	Right	0+020.1	0+089.7	69.6		
271104000234100 / SCHNEIDER, WENDY LORRAINE; STOUT, CHRISTOPHER JOHN	Right	0+089.7	0+130	40.3		
Firelane 4	Right	0+130	0+150.1	20.1		
271104000234200 / 788833 ONTARIO LIMITED; O'CONNOR, ELIZABETH	Right	0+150.1	0+190.3	40.2		
271104000235600 / ALEK, CHRISTOPHER PAUL; ALEK, WENDY LEE	Right	0+190.3	0+230.5	40.2		

June Rd	Right	0+230.5	0+250.6	20.1		
271104000235700 / KNIGHT- WOODWARD, BARBARA	Right	0+250.6	0+291	40.4		
271104000237300 / KELLY, ROBERT JAMES; KELLY, MARY ANN	Right	0+291	0+331	40		
271104000237610 / BEAM, JONATHAN IRVIN	Right	0+331	0+351.1	20.1		
271104000237400 / PORT COLBORNE CITY	Right	0+351.1	0+351.6	0.5		

E3 Branch

271104000242101 / PORT COLBORNE CITY	Both	0+000	0+004	4	Both	realign to E2 revised outlet.
271104000233300 / MARTINEAU, WILFRED ROMEO; MARTINEAU, ROXANNE STEPHANIE	Both	0+004	0+127.3	123.3	South	replace the existing culvert with a new, construct a cobblestone low flow channel with an overflow channel to a new outlet
271104000233200 / PETRUS, MICHAEL LESLIE; PETRUS, BRADLY MICHAEL	Both	0+127.3	0+204.5	77.2	South	
Cedar Bay Rd	Both	0+204.5	0+222	17.5		

6 Drainage Works Financing

6.1 Eligible Cost of Works

The Drainage Act stipulates what is or isn't eligible as a cost of construction or cost of the proposed works. Many reports are prepared on the basis that a single aspect of construction will be undertaken; however, for the Oil Mill Creek Drain, there may be one period of construction or several depending on the construction progress selected by the City of Port Colborne. The implementation of the proposed works is not detailed in this report. It is implemented by the City of Port Colborne to make the most effective use of existing resources and ensure the most cost-effective construction effort is achieved on behalf of the assessed landowners.

As required by the Drainage Act, Chapter D.17, Section 59(1), the Council may call a meeting if the contract price exceeds 133 percent of the estimated construction costs. These costs are estimated and shown in Table 6 Oil Mill Creek Estimated Cost of Construction

6.1.1 Admin & Engineering Costs

Administration costs identified with the Oil Mill Creek Drain are two items:

- City project-related interest charges, and
- GST tax charged to the project at the municipal rate.

A survey was completed of the Drain at a cost of \$15,394.50

The fees for EWA Engineering Inc. are assessed to the project as \$103,535.52 and will be assessed to the cost of the works. There were two Change Orders to complete the work authorized, and assessed as part of the cost of producing the report.

CAD effort expended by the City is presented as \$73,424.

A budget for engineering services during construction is set at \$1,500.

The total Engineering costs for the Oil Mill Creek Drain included in the Assessment Tables is \$193,854.02

The administration portion of the assessable fees is \$74,369.41 for a total assessed Engineering and Administration cost of **\$268,223.43**.

6.2 Capital Construction Cost

The estimated construction cost of the project is shown in the following table.

Table 6 Oil Mill Creek Estimated Cost of Construction

Construction Management Estimated Costs		\$ 41,000.00	
Section 78 - Proposed Improvements for Construction			
	OMC Outlet Improvements	\$ 27,637.50	
	Oil Mill Creek Improvements - 0+360 to 0+480	\$ 124,515.40	
	West Branch Improvements - 1188m	\$ 69,025.00	
	Interval E1 Branch Drain Sta 0+515 to 0+880	\$ 11,975.00	
	Interval E1 Branch Drain Sta 0+880 to Sta 1+277 - 400m	\$ 6,455.00	
Section 74 - Maintenance Works for Construction			
	E2 Branch	\$ 13,300.00	
	E3 Branch	\$ 10,145.00	
	Oil Mill Creek Drain - Upper Watershed	\$ 39,325.00	
Sub-Total Estimated Cost of Construction			\$343,377.90

6.3 Maintenance Costs

Included in the estimated cost of construction are allocations for costs related to drain maintenance works, including vegetation removal and re-grading, that are included in the construction cost as Section 78/74 works.

Adjustments from the previous grade lines are identified as works to be completed as Schedule 74 maintenance. These are not a redesign of a grade line in most cases as much as they are recognizing the grade line using metric and new datums.

6.4 Principles of Assessment

The following are general and specific principles used to assess costs for the Oil Mill Creek Drain according to the Regulations formed under the Drainage Act using our understanding of the Act and seeking the most fair methods to share costs to ratepayers within the Oil Mill Creek Drain Watershed.

1. Assessments are a method to calculate a contributing property's share of drainage works, hereafter referred to as a Drain.
2. Each Drain is defined by a fixed point of commencement that traverses to a fixed Outlet, which may be a receiver or another Drain.
3. A property contributes to drainage work if any portion of the property directly or indirectly contributes to a runoff flow to the Drain.

4. A Drain is any constructed or existing natural method of conveyance or stormwater management function that moves or controls water from one collection point to a discharge point, an Outlet.
5. The use of a property, whether farming, residential, or vacant, does not define the benefit of the Drain. The benefit of a drain is realized equally among all properties with runoff to the Drain.
6. An excess or additional benefit is realized for any property or group of properties for which a higher standard of drainage service is required for the specific use of a property for which a higher value is realized.

As an example, where a market garden farm requires additional pumping for either irrigation or reducing the water surface in the drain, then the additional costs for that are borne by the benefitting lands.

7. Similarly, where a property or group of properties is provided with a lower standard of drainage service or where such property or properties provides a stormwater management function within the drainage works of the Drain, the value of the lower service or function is determined at a rate commensurate with the benefit to the drain.

As an example, where a property converts a portion of their lands (or the entire property) to a wetland or other stormwater management feature that reduces the peak flow of the runoff, thereby reducing or enhancing the capacity of the Drain to improve drainage and reduce flooding, then a commensurate benefit is realized to the volume of water removed from the runoff hydrograph.

Where the volume of detained runoff is small relative to the capacity of the drain, this contribution is deemed to be negligible. Where the volume detained is below 1% of the total runoff volume for the Drain, there is no real benefit realized for an individual Stormwater Management Feature.

8. The capacity of the Drain is determined based on a hydrologic model forecast of precipitation based runoff. Therefore, each property realizes a drain benefit based on the proportion of predicted runoff for their property. Predicted runoff is a product of the following attributes, which are determined for each property:
 - a. Area contributing to runoff;
 - b. Land use as it relates to runoff;
 - c. Land topography;
 - d. Proportion of hard surfaces vs soft surfaces as they relate to infiltration; and
 - e. Stormwater management features specially built to reduce the rate of runoff.
9. A benefit is realized for a property that causes a physical change in the Drain works to serve a particular use or surface water benefit to the property. An example is a culvert, which provides access to a property across a drain.
10. A benefit/assessment is realized for Municipal, Regional or Provincial lands held as Rights of Way that cause or require additional infrastructure, effort or costs related to the Drain. (Section 26)

11. Where a cost to the drain is realized through effort during construction or otherwise for the protection of flora, fauna or quantity or quality of stormwater runoff, this cost is born proportionally amongst all watershed contributing owners at the same rate as established for Drain benefit.

12. For the Oil Mill Creek Drainage works being considered, a Drain already exists, and the proposed assessment is to recognize a service or benefit that already exists and is being confirmed to exist through the creation of the report and assessment schedule.

13. For utilities that require additional work, changes in design, or protection during construction, those costs are borne by the owner of the utility.

A modern infrastructure concept missing from the Drainage Act, or not explicitly directed regarding assessment, is the service level of the drain. For an urban area, explicit service levels are documented through municipal design standards and expectations, often codified into operation manuals that establish the expected service levels. While there are aspects of this in the Drainage Act, service levels and the possibility that they may vary from property to property or region within a Drain area are not explicitly discussed. The concept is that for a basic service level for a farm, the requirement is for flooding not to be sustained such that plants are drowned. However, there is no direct link between depth to damage such as what is accepted in an urban area. Rural residential properties as compared with farm properties where the farm service level is to have the flooding removed within 24 to 36 hours while the residential service level expectation is to have no flooding within the property limits that might enter a building below grade and cause damage. Flooding depth is to be kept below all sill levels.

This difference in service level expectation, for example, are market garden farm operations when present in a drain seeking flood elevation control using mechanical pumping systems.

While efforts within the drain design and assessment have been made to address water quality as well as quantity, there are limits within the Drainage Act to address water quality as a direct benefit from drainage.

Benefit (Section 22)

This Assessment is based on the creation of land value through the creation of a new or additional drainage system. In the Oil Mill Creek Drains, the drain already exists and has for some time (more than 100 years).

Outlet Liability (Section 23)

This is the primary basis for the assessment of the maintenance and drain works. Assessment is based on each individual property's contributing runoff. This is determined by the area flowing to the drain and runoff factor C. The runoff factor C is the Rational Method for predicting peak runoff and does not predict the runoff volume (note special benefit used for site-specific SWM facilities).

The C factor for assessing property runoff is selected based on the property zoning. Where a property is not currently farmed but is zoned for farming, then a C factor is selected based on the potential use of the property. C factors are not

adjusted for variations in Residential properties. Residential properties with or without buildings are assigned the same C factor. Thus, the C factor is not a current prediction of runoff for an individual property but a Factor to assess the potential runoff based on the property's potential use in the present and in the future.

The following drain features are part of the whole system and are paid for through the outlet assessment:

- Channel Clearing and Re-grading
- Sediment Basins
- Where a channel is re-aligned to improve the drain function and not caused by a property's use, the cost of the channel re-alignment is assessed as an outlet liability assessment.

Special Benefit (Section 24)

The following are assessed costs considered as special benefits:

- Culverts,
- Fordings,
- Closed Conduit conveyance (piped flow)
- Erosion protection works,
- Channel re-alignment for property improvement.

The cost of a culvert is assessed against the property owner based on a 50/50 split in the cost assessed against the drain watershed. Unless the culvert is near the outlet and the cost is shared on an area proportional basis.

Table 7 Section 24 Special Assessments

Roll No	Owner	Proposed work	Owner Portion	Assessed Benefit
E1 Branch				
271104000240900	LAUR CAROL JAYNE ESTATE; LAUR, JOHN THOMAS; LAUR, MICHAEL JOHN	Existing twin PE culverts to be relaid to grade. All costs shared 50/50 with owner.	50%	\$4,263.23
E2 Branch				
271104000242101	PORT COLBORNE CITY	Re-align outlet construct new confluence with existing spoil to fill in the previous channel. Restoration includes seeding on natural materials fibermat.	100%	\$13,642.35
E3 Branch				
271104000233300	MARTINEAU, WILFRED ROMEO; MARTINEAU, ROXANNE STEPHANIE	replace culvert and improve inlet/outlet conditions E3-CS-01: 6m-HDPE 450mm REMOVE AND REPLACE CULVERT WITH 525mm D PE CULVERT 6m WITH 100mm B GRAVEL BEDDING AND TO THE PIPE HAUNCHES	20%	\$850.00
West Branch				
271104000301300	GROOM, JOSHUA NATHAN; GROOM, KRISTAL LYNN	WB-CS-17 - 2316 Firelane 2 Replace with 6m @ 0.11% PE 450	50%	\$3,255.56

271104000301400	JASEK, COLLEEN R; JASEK, JOHN M	WB-CS-15 - 2334 Firelane 2 Replace with 6m @ 0.11% PE 600	50%	\$3,348.58
271104000301500	HOLODAY, SUSAN-PIETRAS; HOLODAY, RICHARD	WB-CS-14 - 2366 Firelane 2 Replace with 4m @ 0.11% PE 600	50%	\$3,178.05
271104000302100	BEGG, TERRY-LYNN	WB-CS-12 - 426 Pinecrest Rd lower existing 3m - CSP Arch 550x900 culvert	50%	\$2,325.40
271104000302610	METCALF, IVANA KOMLIJENOVIC; METCALF, THOMAS ASA	WB-CS-11 - 446 Pinecrest Rd Replace with 15m@0.11% CSP 900 with 0.050 embedded	50%	\$5,115.88
271104000302700	1000071167 ONTARIO INC	WB-CS-09 - 462 Pinecrest Rd Replace with 10m@0.11% CSP 900 with 0.050 embedded	50%	\$4,185.72
271104000242700	MACCABE, NATALIE ANN BETHANY; APOLCER, JEREMY MATHEW	WB-CS-05 - 2595 Vimy Ridge Rd Replace with 6m@ 0.11% CSPA 889x610 with 0.050 emb	50%	\$3,604.37
OMC Upper				
271104000499900	PORT COLBORNE CITY	REPLACE O-CS-05 EXISTING 500mm WITH 600 PE 320 kPa Replace TO DESIGN GRADE WITH 25mm EMBEDDED INVERTS, 12m @ 0.2% US INV = 177.235 DS INV = 177.210	100%	\$10,580.57

In addition to assessed costs considered for special benefits, there is also recognition through the use of the Special Benefit for stormwater management facilities within the watershed that reduce the peak flow used to determine the outlet assessment. These facilities that may already exist in the watershed are recognized as having a benefit in reducing peak flow by determining the available volume is greater than the 24 hour peak flow volume predicted for the 1:2-year design storm.

- Site Specific Stormwater Management (SWM) Facilities
 - Wetlands,
 - Ponds, (natural and stormwater)
- Natural occurring features
 - Kettle lakes, and
 - Bog lands.

Special Assessment (Section 26)

There are special assessments, as recognized under the Act, for public (not private) roads and utilities that have or require additional costs to the drainage system.

In addition to the projected assessments for Right of Way lands as determined by the outlet assessment, any other costs for road crossings or protection of utilities during construction are assessed to the road owner or utility owner. In the case of Oil Mill Creek Drains, all of the existing drain culverts and road crossings are to

be maintained as is, and additional costs are not planned or identified. If replacement is required in the future, drain crossing culverts for roads are replaced 100% at the road authority's cost.

Also included are costs related to impacted utilities such as Enbridge. These costs can be additional effort during construction to protect or meet site supervision requirements by the utility. This may also include costs to move infrastructure if required by site conditions.

6.4.1 Allowances:

1. Where a Drain assessment schedule already exists, and a prior maintenance and assessment schedule is known to exist, then a Schedule 29 allowance is accepted and recognized through a past report and schedule unless it can be shown otherwise.
2. Where a Drain is re-aligned to a new path, then a Section 29 allowance for land taken is recognized. This can be amended by the restoration of any lands to the same owner by the same re-alignment. Thus, a net allowance can be realized where that is shown to be the case.
3. Where previously no Drain was recognized but already existed as a flow path, then a Section 31 allowance can be realized along with a one-time creation of a current and future easement for Drain maintenance activities as a Section 29 allowance. This is specifically for the creation of Branch Drains.
4. All property valuations are based on the same basic valuation per the Schedule of Costs.
5. Any tree or feature placed within a drainage works right of access for maintenance is not eligible for compensation.

Section 29 Allowance

(One time payment for land taken)

Where a Drain already exists and has had maintenance in the past, a work zone is assumed to exist, and a one-time payment for the work zone easement has been made. No further payment for a work zone or easement is deemed to be required based on the pre-existing work zone, regardless of whether that is known to exist or shown to exist in an explicit reference in a previous Engineer's report.

Where a Drain re-alignment is proposed, then a Section 29 allowance is determined. The determination is based on a 10m work zone running parallel to one side of the drain commencing at the Top of Bank. The Drainage Engineer determines the side from which work is done and shown on the Plans for Construction. The value is based on a single value of land figure as shown in the Schedule of Costs, and because the access is intermittent with the owner retaining ownership and access / use of the land for farming or otherwise, a factor in the assessment value of land is applied. Since the work zone is likely to be occupied on a 20-year maintenance cycle, a 1/20 factor is to be applied.

Where a buffer is established that restricts the use of the land adjacent to the drain, then a full payment for land taken based on the value established is made.

Section 30 Allowance

(Payment for damages during construction)

Awarded where work on the drain, such as maintenance, that damages crops which can not be restored. This does not apply to grass or any other ornamental feature restored to a similar condition as existed pre-construction. All damage calculations are based on agricultural crop losses.

For any trees removed for construction with a greater diameter than 150mm at breast height (DBH), compensation in the form of saplings is offered. Where a tree is removed, 2 saplings of a variety native to the area are offered for planting outside the work zone as compensation, and no award for compensation is made.

Section 31 Allowance

(Incorporate a Private Drain)

This type of allowance is to credit the construction effort of a private drain as it relates to the private drain being incorporated into a municipal Drain.

The value of the private drain depends on the condition and contribution to the function of the Drain. The cost to construct a similar channel would be based on the Schedule of Prices for valuation purposes. The cost to maintain it would be subtracted.

Section 32 Allowance

(Insufficient Outlet)

This compensates affected owners for whom lands are not sufficiently drained by the service level provided by the Drain or where lands are discharged into instead of having a sufficient outlet.

No allowance is made for Section 32 in the OMC watershed.

Section 33 Allowance

(Loss of Access)

Where a re-aligned Drain crosses the property and cuts off access, an allowance can be granted. This is offered as compensation where the landowner accepts the loss of access as the lessor of the cost to construct a culvert, bridge or fording to provide access. It can also be used to recognize a wetland where drainage is deferred in favour of the wetland's use of storage of runoff within the Watershed.

No occurrences of this within the Oil Mill Creek watershed are newly recognized within this report. There may be previous occurrences which are assumed to have been recognized in previous reports.

6.4.2 Riparian versus Watershed Benefit

The Drainage Act contains several key concepts, of which two are directly relevant to determining assessments:

- Injuring liability, Section 23 (1), and Outlet liability, Section 23 (2).

- Special Benefit Assessment, Section 24.

Where there is no extenuating circumstance to the direct flow of the channel, the whole benefit of the Bank Restoration and Improvement Program is that 100% of the cost is assessed to the adjacent landowner as a Special Benefit.

Where there is an extenuating circumstance to the flow of the channel, such as a bend, or other alignment adjustment, a tree or other object that obstructs flow and causes a change in velocity against a bank, then the cost of the Bank Restoration and Improvement Program is split with a portion allocated to the upstream watershed and a portion assigned to the benefiting adjacent landowner(s) as a Special Benefit. The ratio of an upstream area determines the portion compared as a percentage of the entire watershed area.

The Engineer's determination of the external influences of flow impacts requires the application of a bank protection measure. Bank protection measures rely on the acceptance and at the request of the adjacent landowner and are not applied without the landowner's acceptance. It is the choice of the Engineer to select the appropriate measure for the Drain.

6.4.3 General Instructions to Property Owners, Road Authorities and Public Utilities

The principles of the Drainage Act are:

- Drainage is a collective good that benefits all landowners. However, drainage does not have to benefit all landowners equally.
- All landowners cooperatively fund the drainage works proposed. There is no direct financial government role in the drainage works other than administrative.
- Landowners are assessed a financial share of the cost for the drainage works based on their respective drainage benefit.
- All drainage costs are borne by landowners, including allowances.
- Drainage is provided based on an identified service level for a specified size of storm. The standard storm, 1 in 5-year frequency, for basic open channel design is 68.9mm over 24 hours. A storm of a larger size or intensity may cause flooding. The tile placed at the bottom of an open channel is provided for drainage, not conveyance capacity.

For more details, refer to the OMC Watershed Hydrology and Hydraulics Report.

A best effort has been made to compose a fair and reasonable assessment of costs to each portion of the contributing lands.

6.4.4 Grants

Owners of qualifying agricultural land are presently eligible for a grant from the Ontario Ministry of Agriculture, Food and Rural Affairs of up to one-third of the cost of their assessment. This grant would be applied for by the City of Port Colborne and applied to the property owners' assessment at the time of final billing. The Assessment Schedule indicates lands that, based on information provided by the municipality, qualify for the agricultural land use rebate. The final determination of eligibility is the decision of the Ontario Ministry of Agriculture, Food and Rural Affairs. To be eligible for a grant, the property owner must have a Farm Property Class Tax Rate.

For additional information on the Agricultural Drainage Infrastructure Program, refer to the OMAFRA website at www.omafra.gov.on.ca.

6.5 Cost, Allowance and Assessment Schedules

The Assessment Tables are included in Appendix B. The following sections provide a summary report of those calculations.

Construction costs are allocated using the Interval ratio along with the Administration and Engineering Costs.

The cost of a new culvert to replace the Friendship Trail crossing east of Pinecrest Rd is allocated to the City of Port Colborne along with approach channel improvements and associated swale re-grading as a Private Drain Connection responsibility in recognition of the Friendship Trail as a barrier to the natural drainage. There is an assessment of cost during the construction of the culvert to the Niagara Regional Broadband Network for the cable that currently passes underneath the existing culvert. The cost is related to the protection and/or lowering of the cable to facilitate the construction of a new culvert.

Additional to these costs will be Administration and Engineering Costs related to the design.

Oil Mill Creek Municipal Drain
City of Port Colborne
Regional Municipality of Niagara

Assessment Summary

Farm As 'F'	Owner	Legal_Txt	Roll No	ARN ABBREV	Area Ha	Area in Drain Ha	Sect. 23	Sect. 24	Total Assessed	Allowances	Net
F	City of Port Colborne - Lands Assessed										
	AZZOPARDI, THERESA FRANCES	CON 1 PT LOT 12	271104000226100	226100	3.8339	0.8620	\$1,791.97		\$1,791.97	\$0.00	\$1,791.97
	BRYAN, MILDRED AGNES	CON 1 PT LOT 12 RP 59R12293 PART 2	271104000226200	226200	3.6457	0.4970	\$1,033.42		\$1,033.42	\$0.00	\$1,033.42
	SNEEK, GREGORY ALAN; SNEEK, ARIANE KATRINA	CON 1 PT LOT 12 RP 59R12293 PART 1	271104000226210	226210	0.4046	0.4020	\$835.00		\$835.00	\$0.00	\$835.00
	BULGER, CAROL ANN	CON 1 PT LOT 12	271104000226300	226300	3.8977	0.8720	\$1,813.09		\$1,813.09	\$0.00	\$1,813.09
	RIZZI GIOVANNI ESTATE; RIZZI, MENA	CON 1 PT LOT 12	271104000226301	226301	10.0639	0.5330	\$861.68		\$861.68	\$0.00	\$861.68
	SCHUIT, JOHN; DUMA, PAMELA SUSAN	HUMERSTONE CON 1 PT LOT 12	271104000226400	226400	9.4729	3.1000	\$4,650.87		\$4,650.87	\$0.00	\$4,650.87
	DUMA, PAMELA SUSAN; SCHUIT, JOHN	HUMERSTONE CON 1 PT LOT 12 RP 59R15490 PART 3	271104000226402	226402	0.9997	1.0000	\$1,482.17		\$1,482.17	\$0.00	\$1,482.17
	KLAUCK, WESLEY; KLAUCK, LISA	HUMERSTONE CON 1 PT LOT 12 RP 59R15490 PART 2	271104000226403	226403	0.9997	0.8030	\$1,159.97		\$1,159.97	\$0.00	\$1,159.97
	TAVANO, ANTONIO FELICE	HUMERSTONE CON 1 PT LOT 12 RP 59R15490 PART 1	271104000226404	226404	0.9997	0.3220	\$441.00		\$441.00	\$0.00	\$441.00
	BOSLEY, MARY ANN; BOSLEY, ROBERT J	HUMBERSTONE CON 1 PT LOT 12 RP 59R7346 PT PART 1	271104000226417	226417	6.4219	3.3000	\$3,693.81		\$3,693.81	\$0.00	\$3,693.81
	BABIRAD, RACHAEL LYNN	CON 1 PT LOT 12 PLAN 59R-6139 PART 1	271104000226418	226418	0.4044	0.4040	\$827.57		\$827.57	\$0.00	\$827.57
	BABIRAD, RACHAEL LYNN	CON 1 PT LOT 12 RP59R-6139 PART 2	271104000226419	226419	0.4044	0.4040	\$1,000.95		\$1,000.95	\$0.00	\$1,000.95
	FORDY, MARY ANN; FORDY, BRUCE GLEN	CON 1 PT LOT 12 RP59R-6139 PART 3	271104000226420	226420	0.4045	0.3950	\$992.10		\$992.10	\$0.00	\$992.10
	MINOR, MARK FRANKLIN; CHRISTIE MINOR, AMBER NOELLE	HUMBERSTONE CON 1 PT LOT 12 RP 59R16386 PART 1	271104000226422	226422	1.0009	0.7390	\$1,114.68		\$1,114.68	\$0.00	\$1,114.68
	MINOR, ANNE CATHERINE; MINOR, MORGAN PAUL	HUMBERSTONE CON 1 PT LOT 12 RP 59R16386 PART 2	271104000226423	226423	1.0010	0.7480	\$1,127.34		\$1,127.34	\$0.00	\$1,127.34
	THOMSON, WAYNE ROBERT; BROWN, NANCY ANN	PLAN 24 PT LOT 1 NP783	271104000226500	226500	0.1635	0.0210	\$26.23		\$26.23	\$0.00	\$26.23
	HRABOWSKY, YVONNA VLADISLAVA	PLAN 24 S PT LOT 1 NP783	271104000226800	226800	0.1705	0.0210	\$26.30		\$26.30	\$0.00	\$26.30
	MCWHINNIE, ELLEN	PLAN 24 LOT 27 PT LOT 26 NP 783 RP59R 8197 PART 1	271104000229000	229000	0.1579	0.0170	\$21.17		\$21.17	\$0.00	\$21.17
	MAFFEI, CHERYL; MAFFEI, TERRY	PLAN 24 LOT 28 LOT 29 NP783	271104000229100	229100	0.2125	0.0310	\$38.77		\$38.77	\$0.00	\$38.77
	KAVANAGH, RUTH	PLAN 24 LOT 30 NP783	271104000229200	229200	0.1076	0.0060	\$0.00		\$0.00	\$0.00	\$0.00
	VESPER, DEBORAH SUZZANE	PLAN 36 LOT 1 NP795	271104000229500	229500	0.0690	0.0690	\$173.39		\$173.39	\$0.00	\$173.39
	VESPER, DEBORAH	PLAN 36 LOT 2 NP795	271104000229600	229600	0.0710	0.0710	\$139.95		\$139.95	\$0.00	\$139.95
	MARQUES, SILVINO MIGUEL DA CRUZ; PEREIRA MARQUES, MARIA	PLAN 795 LOTS 3 AND 4	271104000229700	229700	0.1152	0.1150	\$41.47		\$41.47	\$0.00	\$41.47
	MOORE, HARRY JR; MOORE, CAROL	PLAN 36 LOT 5 LOT 6 NP795	271104000229900	229900	0.1826	0.1830	\$228.97		\$228.97	\$0.00	\$228.97
	SCHULTZ, WINKLEY JANE; SCHULTZ, DOUGLAS ALLEN	PLAN 36 LOT 7 NP795	271104000230000	230000	0.0914	0.0910	\$111.96		\$111.96	\$0.00	\$111.96
	ALEXANDER, KATHRYN RUTH	PLAN 36 LOT 8 NP795	271104000230100	230100	0.0915	0.0910	\$110.40		\$110.40	\$0.00	\$110.40
	DE OCAMPO, MARTINIANO; DE OCAMPO, AMELIA	PLAN 36 LOT 9 NP795	271104000230200	230200	0.0916	0.0920	\$109.19		\$109.19	\$0.00	\$109.19
	ZIEMIANSKI, DEREK; HOCHREITER, MELISSA MAY	PLAN 36 LOT 10 NP795	271104000230300	230300	0.0916	0.0920	\$107.63		\$107.63	\$0.00	\$107.63
	VAN ESCH, STEVEN CARMEN; VAN ESCH, KAITLIN MICHELLE	PLAN 36 LOT 11 NP795	271104000230400	230400	0.0917	0.0920	\$106.06		\$106.06	\$0.00	\$106.06
	GAME, RYAN DOUGLAS; GAME, RENEE MARIE	PLAN 36 LOT 12 NP795	271104000230500	230500	0.0918	0.0920	\$104.50		\$104.50	\$0.00	\$104.50
	MCCOMBE, LAURIE; DEROSE, LEONARDO	PLAN 36 LOT 13 NP795	271104000230600	230600	0.0918	0.0920	\$102.93		\$102.93	\$0.00	\$102.93
	DEROSE, LEONARDO; MCCOMBE, LAURIE	PLAN 36 LOT 14 PT LOT 15 NP795	271104000230700	230700	0.1077	0.1080	\$100.00		\$100.00	\$0.00	\$100.00
	HALL, JILLIAN; HALL, BRIAN	PLAN 36 PT LOT 15 PT LOT 16 NP795	271104000230800	230800	0.0409	0.0410	\$14.78		\$14.78	\$0.00	\$14.78
	NORMAN, ERNEST J; NORMAN, LOIS A	PLAN 36 PT LOT 16 PT LOT 17 NP795	271104000230900	230900	0.0490	0.0490	\$17.67		\$17.67	\$0.00	\$17.67
	MAHONEY, BRIAN	PLAN 36 PT LOT 17 PT LOT 18 NP795	271104000231000	231000	0.0327	0.0330	\$11.90		\$11.90	\$0.00	\$11.90
	WILSON, ROBERT FRED JOHN; CANAVAN, WENDY ELIZABETH; WILSON, KIM GREGORY	PLAN 36 PT LOT 18 PT LOT 19 NP795	271104000231100	231100	0.0394	0.0390	\$14.06		\$14.06	\$0.00	\$14.06
	PJDB PROPERTIES INC	PLAN 36 PT LOT 19 NP795	271104000231200	231200	0.0387	0.0390	\$14.06		\$14.06	\$0.00	\$14.06
	LANDON, HANKLIN LIVINGSTONE	PLAN 36 PT LOT 20 NP795	271104000231300	231300	0.0277	0.0280	\$10.10		\$10.10	\$0.00	\$10.10
	SWARTZ, DEBORAH ANN LOUISE; SWARTZ, DOUGLAS	PLAN 36 PT LOT 20 NP795	271104000231400	231400	0.0263	0.0260	\$9.37		\$9.37	\$0.00	\$9.37
	SOUDER, CATHERINE R	PLAN 795 SAND BEACH	271104000231501	231501	0.5595	0.0230	\$3.32		\$3.32	\$0.00	\$3.32
	MEYER, PETER; SAHS-MEYER, EVA-LYN	PLAN 36 LOT 32 NP795	271104000232700	232700	0.0835	0.0260	\$3.75		\$3.75	\$0.00	\$3.75
	DEMERY, RUTA; DEMERY, GEORGE	PLAN 36 LOT 33 NP795	271104000232800	232800	0.0874	0.0540	\$7.79		\$7.79	\$0.00	\$7.79
	PARR, MARTIN JOHN; PARR, LINDSEY MARIE	PLAN 36 LOT 34 NP795	271104000232900	232900	0.0912	0.0870	\$12.55		\$12.55	\$0.00	\$12.55
	NARDONE, WILMA; NARDONE, JESSICA	PLAN 36 PT LOT 35 NP795	271104000233000	233000	0.0254	0.0250	\$3.61		\$3.61	\$0.00	\$3.61

Assess Summary

Farm	Owner	Legal_Txt	Roll No	ARN ABBREV	Area	Area in Drain	Sect. 23	Sect. 24	Total	Allowances	Net
	PRUYN, FRANCIS MATHEUS ROBERT; PRUYN, HENRIETTE	PLAN 36 PT LOT 35 NP795	271104000233100	233100	0.0578	0.0580	\$8.37		\$8.37	\$0.00	\$8.37
	PETRUS, MICHAEL LESLIE; PETRUS, BRADLY MICHAEL	CON 1 PT LOT 13	271104000233200	233200	0.3085	0.3080	\$774.87		\$774.87	\$0.00	\$774.87
	MARTINEAU, WILFRED ROMEO; MARTINEAU, ROXANNE STEPHANIE	CON 1 PT LOT 13	271104000233300	233300	1.3341	1.3340	\$2,316.97	\$850.00	\$3,166.97	\$0.00	\$3,166.97
	CHAMISH, ETHAN	PLAN 59 LOT 1 NP818	271104000233400	233400	0.0809	0.0810	\$203.28		\$203.28	\$0.00	\$203.28
	MAYO, JAYSEN; GOLFI, KRISTINE	PLAN 59 LOT 2 NP818	271104000233500	233500	0.0809	0.0810	\$203.27		\$203.27	\$0.00	\$203.27
	EBERHARDT, PAULINE	PLAN 59 LOT 3 NP818	271104000233600	233600	0.0809	0.0810	\$130.74		\$130.74	\$0.00	\$130.74
	DIPLOCK, MICHAEL CRAIG	PLAN 59 LOT 4 NP818	271104000233700	233700	0.0809	0.0810	\$130.74		\$130.74	\$0.00	\$130.74
	GELKA, BRADLEY GEORGE	PLAN 59 LOT 5 LOT 6 NP818	271104000233800	233800	0.1618	0.1620	\$261.47		\$261.47	\$0.00	\$261.47
	MCCARTHY, MICHAEL EARL	PLAN 59 LOT 7 NP818	271104000233900	233900	0.0809	0.0810	\$130.74		\$130.74	\$0.00	\$130.74
	WARNER, ROSE MARIE; WARNER, TERRY RAY	PLAN 59 LOT 8 LOT 9 NP818	271104000234000	234000	0.1594	0.1590	\$257.31		\$257.31	\$0.00	\$257.31
	SCHNEIDER, WENDY LORRAINE; STOUT, CHRISTOPHER JOHN	PLAN 59 LOT 10 NP818	271104000234100	234100	0.0725	0.0730	\$117.33		\$117.33	\$0.00	\$117.33
	788833 ONTARIO LIMITED; O'CONNOR, ELIZABETH	PLAN 59 LOT 11 LOT 12 NP818	271104000234200	234200	0.1509	0.1510	\$243.74		\$243.74	\$0.00	\$243.74
	AKINS, ANNETTE MARIE MARGARET; AKINS, DAVID LLOYD	PLAN 59 LOT 13 NP818	271104000234300	234300	0.0809	0.0810	\$130.73		\$130.73	\$0.00	\$130.73
	DE MELO, SUSETE MARIA; DE MELO, KRISTEN TAYLOR; DE MELO, KYLE DANIEL	PLAN 59 LOT 14 NP818	271104000234400	234400	0.0809	0.0810	\$130.73		\$130.73	\$0.00	\$130.73
	DANIS, GUY GERALD; DANIS, SUSAN ELAINE	PLAN 59 LOT 16 LOT 17 NP818	271104000234500	234500	0.1618	0.1620	\$261.47		\$261.47	\$0.00	\$261.47
	DE MELO, KRISTEN TAYLOR; DE MELO, KYLE DANIEL; DE MELO, SUSETE MARIA	PLAN 59 LOT 15 NP 818	271104000234501	234501	0.0809	0.0810	\$130.74		\$130.74	\$0.00	\$130.74
	DANILEWICZ, LESZEK; DANILEWICZ, GRAZYNA	PLAN 59 LOT 18 NP818	271104000234600	234600	0.0809	0.0810	\$130.74		\$130.74	\$0.00	\$130.74
	MCCLEMONT, DIANE MARLENE; MCCLEMONT, KENNETH GRANT	PLAN 59 LOT 19 NP818	271104000234700	234700	0.0809	0.0810	\$203.27		\$203.27	\$0.00	\$203.27
	REZZA, VITO; REZZA, MARGARET	PLAN 59 LOT 20 NP818	271104000234800	234800	0.0809	0.0810	\$202.74		\$202.74	\$0.00	\$202.74
	NAGY, ANITA LOUISE	PLAN 59 LOT 21 NP818	271104000234900	234900	0.0809	0.0810	\$130.74		\$130.74	\$0.00	\$130.74
	NAGY, ANITA LOUISE	PLAN 59 LOT 22 NP818	271104000235000	235000	0.0809	0.0810	\$130.74		\$130.74	\$0.00	\$130.74
	CARMICHAEL, BAYLEY; GUTTIN, CORDELL	PLAN 59 LOTS 23, 24 NP818	271104000235100	235100	0.1618	0.1620	\$261.47		\$261.47	\$0.00	\$261.47
	DANIS, SUSAN ELAINE; DANIS, GUY GERALD	PLAN 59 LOT 25 LOT 26 NP818	271104000235300	235300	0.1618	0.1620	\$261.47		\$261.47	\$0.00	\$261.47
	WYBROW, ROBERT WILLIAM	PLAN 59 LOT 27 NP818	271104000235400	235400	0.0809	0.0810	\$130.74		\$130.74	\$0.00	\$130.74
	WYBROW, ROBERT WILLIAM	PLAN 59 LOT 28 NP818	271104000235500	235500	0.0809	0.0810	\$130.74		\$130.74	\$0.00	\$130.74
	ALEK, CHRISTOPHER PAUL; ALEK, WENDY LEE	PLAN 59 LOT 29 LOT 30 NP818	271104000235600	235600	0.1508	0.1510	\$243.63		\$243.63	\$0.00	\$243.63
	KNIGHT-WOODWARD, BARBARA	CON 1 PT LOT 13	271104000235700	235700	0.0689	0.0690	\$111.30		\$111.30	\$0.00	\$111.30
	SCOTT, TARA EILEEN	CON 1 PT LOT 13	271104000235800	235800	0.0812	0.0810	\$131.11		\$131.11	\$0.00	\$131.11
	RUSTON, CHRISTINE ANN	CON 1 PT LOT 13	271104000235900	235900	0.0812	0.0810	\$131.07		\$131.07	\$0.00	\$131.07
	ZIMMERMAN, CARRIE ANN; ZIMMERMAN, JODY ANTHONY	CON 1 PT LOT 13	271104000236000	236000	0.0811	0.0810	\$131.02		\$131.02	\$0.00	\$131.02
	SLITER, JOSHUA RAYMOND	CON 1 PT LOT 13	271104000236100	236100	0.1622	0.1620	\$388.04		\$388.04	\$0.00	\$388.04
	MCNAY, KIMBERLY MARIE	CON 1 PT LOT 13	271104000236200	236200	0.0810	0.0810	\$130.88		\$130.88	\$0.00	\$130.88
	ASHBRIDGE, ALAN; ASHBRIDGE, MARC PETER	CON 1 PT LOT 13	271104000236300	236300	0.0810	0.0810	\$130.85		\$130.85	\$0.00	\$130.85
	WEST, DARREN; WEST, ONNA	HUMBERSTONE CON 1 PT LOT 13	271104000236400	236400	0.1628	0.1630	\$263.04		\$263.04	\$0.00	\$263.04
	EZEARD, KIMBERLEY	CON 1 PT LOT 13 LALLOUET SKETCH LOT 41	271104000236600	236600	0.0807	0.0810	\$130.50		\$130.50	\$0.00	\$130.50
	EZEARD, KIMBERLEY	CON 1 PT LOT 13 LALLOUET SKETCH LOT 42	271104000236800	236800	0.0813	0.0810	\$131.25		\$131.25	\$0.00	\$131.25
	GRACE, KATHRYN; GRACE, JOHN	HUMBERSTONE CON 1 PT LOT 13	271104000236900	236900	0.0813	0.0810	\$131.27		\$131.27	\$0.00	\$131.27
	SHERSTYUK, ANDRIY	HUMBERSTONE CON 1 PT LOT 13	271104000237000	237000	0.2421	0.2420	\$391.05		\$391.05	\$0.00	\$391.05
	KELLY, ROBERT JAMES; KELLY, MARY ANN	CON 1 PT LOT 13 LALLOUET SKETCH LOT 49 LOT 50	271104000237300	237300	0.3094	0.3090	\$499.63		\$499.63	\$0.00	\$499.63
	PORT COLBORNE CITY	CON 1 PT LOT 13 LALLOUET SKETCH LOT 51 LOT 52	271104000237400	237400	0.1428	0.1430	\$230.70		\$230.70	\$0.00	\$230.70
	COX, REGINAL RICKY	CON 1 PT LOT 13 LALLOUET SKETCH LOT 68	271104000237500	237500	0.0809	0.0810	\$130.74		\$130.74	\$0.00	\$130.74
	COX, REGINAL RICKY	CON 1 PT LOT 13 PLAN 59R6615 PART 1	271104000237600	237600	0.4047	0.4050	\$653.90		\$653.90	\$0.00	\$653.90
	BEAM, JONATHAN IRVIN	CON 1 PT LOT 13	271104000237610	237610	4.6164	4.6160	\$4,417.24		\$4,417.24	\$0.00	\$4,417.24
	BACSO, MIKLOS; BACSO, NICOLE ELIZABETH	CON 1 PT LOT 13 RP 59R900 PART 3	271104000237700	237700	0.2209	0.2210	\$356.89		\$356.89	\$0.00	\$356.89
	STOUT, CHRIS	CON 1 PT LOT 13 RP 59R900 PART 1	271104000237800	237800	0.2140	0.2140	\$345.64		\$345.64	\$0.00	\$345.64
	WHITE, MARK ANTHONY	CON 1 PT LOT 13 RP 59R900 PART 2	271104000237801	237801	0.2347	0.2350	\$379.26		\$379.26	\$0.00	\$379.26
	HILBORN, KATHERINE ADA; HILBORN, BRYAN PAUL	CON 1 PT LOT 13 AND RP 59R12267 PART 1	271104000237900	237900	0.3565	0.3570	\$576.10		\$576.10	\$0.00	\$576.10
	BIDOSKI, ANNETTE MAUREEN; BIDOSKI, MURRAY ALLAN	CON 1 PT LOT 13	271104000238000	238000	0.4033	0.4030	\$651.38		\$651.38	\$0.00	\$651.38
	HIGH, DEREK ALLAN; HIGH, KERRI JOANNE	CON 1 PT LOT 13	271104000238100	238100	0.2697	0.2700	\$435.76		\$435.76	\$0.00	\$435.76
	SCHNEIDER, JOHN LOUIS; SCHNEIDER, PATRICIA AILEEN	CON 1 PT LOT 13	271104000238200	238200	0.3501	0.3500	\$565.56		\$565.56	\$0.00	\$565.56
	NADON, TROY RENE DONALD; ARMENTI-NADON, ANITA	CON 1 PT LOT 13	271104000238300	238300	0.2785	0.2780	\$642.89		\$642.89	\$0.00	\$642.89
	ANDERSON, TIMOTHY MICHAEL; ANDERSON, MELISSA MARIE	CON 1 PT LOT 13	271104000238400	238400	0.2632	0.2630	\$607.66		\$607.66	\$0.00	\$607.66

Assess Summary

Farm	Owner	Legal_Txt	Roll No	ARN ABBREV	Area	Area in Drain	Sect. 23	Sect. 24	Total	Allowances	Net
F	JACKSON, GLEN BRUCE; JACKSON, BONNIE LEE	CON 1 PT LOT 13	271104000238500	238500	0.4041	0.4040	\$922.64		\$922.64	\$0.00	\$922.64
	VANDER VAART, LEONARDUS J; VANDER VAART, MARGARET ANN	CON 1 PT LOT 13	271104000238600	238600	11.6929	11.6930	\$8,502.91		\$8,502.91	\$0.00	\$8,502.91
	SZABO, MONICA ANN; GRAY, ROGER WAYNE	CON 1 PT LOT 13	271104000238700	238700	1.9803	1.9800	\$2,021.76		\$2,021.76	\$0.00	\$2,021.76
	BABCOCK, CHARLYN KIM; BABCOCK, TIMOTHY DAVID	RP 59M140 LOT 4 CON 1 PT LOT 13	271104000238701	238701	0.8148	0.8150	\$932.99		\$932.99	\$0.00	\$932.99
	MEDINA OIL FIELD SUPPLY INC	CON 1 PT LOT 13 RP 59R1063 PART 1	271104000238702	238702	6.0722	6.0720	\$4,860.77		\$4,860.77	\$0.00	\$4,860.77
	SAHS-MEYER, EVA-LYN; MEYER, PETER	CON 1 PT LOT 13 PLAN 59R4571 PART 1	271104000238705	238705	0.8092	0.8090	\$1,681.81		\$1,681.81	\$0.00	\$1,681.81
	MEYER, PETER; SAHS-MEYER, EVA-LYN	RP 59M140 LOT 3	271104000238706	238706	0.8091	0.8090	\$1,681.73		\$1,681.73	\$0.00	\$1,681.73
	PETRI, SUSANNE CECILE; PETRI HAROLD ESTATE	RP 59M140 LOT 2	271104000238707	238707	0.8091	0.8090	\$1,681.67		\$1,681.67	\$0.00	\$1,681.67
	ROVERSI, JUDITH ANN	P 59M140 LOT 1	271104000238708	238708	0.8090	0.8090	\$1,681.59		\$1,681.59	\$0.00	\$1,681.59
	POULIOT, LIAM ROLAND; BARTOK, ELISE AMANDA	CON 1 PT LOT 13	271104000238800	238800	0.2027	0.2030	\$256.88		\$256.88	\$0.00	\$256.88
	MARSHALL, RODERICK MARK; RUFFO, LEONA JOANNE	HUMBERSTONE CON 1 PT LOT 13 AND RP 59R5794 PART 1	271104000238900	238900	0.1850	0.1850	\$234.34		\$234.34	\$0.00	\$234.34
	DESCHAMPS, SALLY ANN; DESCHAMPS, DENZIL ADELARD	CON 1 PT LOT 13	271104000239000	239000	0.2757	0.2760	\$349.30		\$349.30	\$0.00	\$349.30
	WINGER, KAREN JOANNE	CON 1 PT LOT 13	271104000239200	239200	0.1842	0.1840	\$233.32		\$233.32	\$0.00	\$233.32
	NESBITT, DANIELLE MICHELLE; SCOTT, KEVIN JOHN	CON 1 PT LOT 13	271104000239300	239300	0.1997	0.2000	\$253.04		\$253.04	\$0.00	\$253.04
	GEADY, CINDY JO; CARRIGAN, FRANCIS JAMES	CON 1 PT LOT 13 RP59R3347 PART 1 TO PART 4	271104000239400	239400	0.3789	0.3790	\$479.97		\$479.97	\$0.00	\$479.97
	PHELAN, DAISY; PHELAN, CHRISTOPHER	CON 1 N PT LOT 13	271104000239600	239600	5.6972	5.6970	\$4,238.76		\$4,238.76	\$0.00	\$4,238.76
	DIMOND, DOUGLAS PATRICK; DIMOND, JANETTE KATHERINE	CON 1 PT LOT 13 RP 59R6412 PART 2	271104000239601	239601	0.4089	0.4090	\$518.01		\$518.01	\$0.00	\$518.01
	SEREDINE, MATHEW WILLIAM	CON 1 PT LOT 13 RP 59R6412 PART 1	271104000239602	239602	0.4525	0.4460	\$563.87		\$563.87	\$0.00	\$563.87
	O'REILLY, LAURENCE MARIE; HOBMAN, GLEN RICHARD	CON 1 PT LOT 13 RP 59R1063 PART 2	271104000239700	239700	0.2199	0.2160	\$270.37		\$270.37	\$0.00	\$270.37
	SNEEKCO LTD	CON 1 PT LOT 13 RP59R 1063 PART 3	271104000239800	239800	0.1319	0.1310	\$163.79		\$163.79	\$0.00	\$163.79
	KOCH, KIRK DOUGLAS; KOCH, NANETTE ANNE	HUMBERSTONE CON 1 PT LOT 13 AND RP 59R1063 PART 4	271104000239900	239900	0.1962	0.1960	\$245.09		\$245.09	\$0.00	\$245.09
	MORRIS, TIMOTHY HENRY; MORRIS, JAMIE LYNN	CON 1 PT LOT 13 RP 59R1063 PART 5	271104000240000	240000	0.1692	0.1690	\$212.19		\$212.19	\$0.00	\$212.19
	GILLESPIE, RITA; GILLESPIE, BLAIR A	CON 1 PT LOT 13 RP 59R3144 PART 2	271104000240100	240100	0.5020	0.5020	\$634.69		\$634.69	\$0.00	\$634.69
	KORTEN, RICHARD	CON 1 PT LOT 13 RP 59R3144 PART 1	271104000240101	240101	0.4601	0.4600	\$1,398.18		\$1,398.18	\$0.00	\$1,398.18
	GUDRUNAS, PETER ERWIN	CON 1 PT LOT 13	271104000240200	240200	5.2970	5.2970	\$3,852.69		\$3,852.69	\$0.00	\$3,852.69
	SHIBLEY, JASON HAROLD	CON 1 PT LOT 14	271104000240300	240300	0.4067	0.3950	\$500.07		\$500.07	\$0.00	\$500.07
	TAGGART, BRENDA; SCHIRMEISTER, MICHAEL BURT	CON 1 PT LOT 14	271104000240600	240600	0.4988	0.4920	\$622.82		\$622.82	\$0.00	\$622.82
	BARRETT, GORDON JAMES	CON 1 PT LOT 14 RP 59R8871 PART 1	271104000240700	240700	0.5498	0.5470	\$692.93		\$692.93	\$0.00	\$692.93
	GRANT, LINDA MARGARET	CON 1 PT LOT 14 RP 59R947 PART 1	271104000240701	240701	7.3555	7.3550	\$4,828.79		\$4,828.79	\$0.00	\$4,828.79
	THIESSEN, STEPHANIE	HUMBERSTONE CON 1 PT LOT 14 RP 59R8871 PT PART 2	271104000240705	240705	17.0560	17.0560	\$16,744.63		\$16,744.63	\$0.00	\$16,744.63
F	WILLIAMS, ROBERT LEE; WILLIAMS, MARGARET HELEN	HUMBERSTONE CON 1 PT LOT 14 RP 59R17117 PART 1	271104000240707	240707	2.3175	2.3120	\$2,277.89		\$2,277.89	\$0.00	\$2,277.89
F	KALYNUIK, CATHY ANN; KALYNUIK, JAMES VAN	CON 1 PT LOT 14 PT 3 - RAILWAY LAND	271104000240710	240710	11.0393	11.0390	\$10,116.02		\$10,116.02	\$0.00	\$10,116.02
F	BROWN, THEODORE THOMAS RICHARD	CON 1 PT LOT 14	271104000240800	240800	0.4121	0.4120	\$612.16		\$612.16	\$0.00	\$612.16
	LAUR CAROL JAYNE ESTATE; LAUR, JOHN THOMAS; LAUR, MICHAEL JOHN	CON 1 PT LOT 14	271104000240900	240900	19.5469	19.5470	\$24,892.33	\$4,516.40	\$29,408.73	\$0.00	\$29,408.73
	MAZZA, RAYMOND; JORGE, JACINTA	CON 1 PT LOT 14	271104000241000	241000	0.0813	0.0810	\$268.79		\$268.79	\$0.00	\$268.79
	ZAJAC, JOHN	CON 1 PT LOT 14	271104000241100	241100	0.1660	0.1660	\$549.10		\$549.10	\$0.00	\$549.10
	ZAJAC, JOHN	CON 1 PT LOT 14	271104000241200	241200	0.0695	0.0700	\$230.16		\$230.16	\$0.00	\$230.16
	HAAZER, DARIE	CON 1 PT LOT 14	271104000241300	241300	0.0695	0.0690	\$229.67		\$229.67	\$0.00	\$229.67
	CRANE, CORNELIA; CRANE, STEPHEN	CON 1 PT LOT 14	271104000241400	241400	0.0694	0.0690	\$229.55		\$229.55	\$0.00	\$229.55
	STICKLAND, TANYA; STICKLAND, MATTHEW	CON 1 PT LOT 14	271104000241500	241500	0.1390	0.1390	\$459.90		\$459.90	\$0.00	\$459.90
	MCINTYRE, TEIGHAN BEVERLEY; DAVIES, FREDERICK CONRAD	CON 1 PT LOT 14	271104000241600	241600	0.0693	0.0690	\$229.17		\$229.17	\$0.00	\$229.17
	PRESSE, CATHERINE ANN; PRESSE, LORIN EARL	CON 1 PT LOT 14	271104000241700	241700	0.1198	0.1200	\$396.29		\$396.29	\$0.00	\$396.29
	ICON REINSURANCE INC	CON 1 PT LOT 14	271104000241800	241800	0.0933	0.0930	\$308.52		\$308.52	\$0.00	\$308.52
	FIDDY, CHARLES JOHN; FIDDY, LILLIAN NICOLE	CON 1 PT LOT 14 RP59R 8956 PART 1	271104000241900	241900	0.1678	0.1680	\$554.98		\$554.98	\$0.00	\$554.98
	TURNER, DAVID BRETT; SINDERLY, MICHAEL JOSEPH; SINDERLY, BARBARA RUTH	CON 1 PT LOT 14 RP59R3837 PART 2 RP59R8956 PART 2	271104000242100	242100	0.2135	0.2140	\$706.45		\$706.45	\$0.00	\$706.45
	PORT COLBORNE CITY	CON 1 PT LOT 13 PT LOT 14 PLAN 36 PT BLK A	271104000242101	242101	19.0899	18.1900	\$7,593.10	\$14,452.48	\$22,045.58	\$0.00	\$22,045.58
	GRAYDON, AMANDA	HUMBERSTONE CON 1 PT LOT 14 RP 59R16071 PART 1	271104000242200	242200	0.4174	0.1460	\$26.32		\$26.32	\$0.00	\$26.32
	BASCIANO, MARKUS ALEXANDER	HUMBERSTONE CON 1 PT LOTS 13 AND 14 RP 59R16071 PART 2	271104000242202	242202	0.4502	0.1290	\$23.26		\$23.26	\$0.00	\$23.26
	EVANS, LANA; EVANS, MARK RANDALL	CON 1 PT LOT 14	271104000242300	242300	0.3339	0.1270	\$22.90		\$22.90	\$0.00	\$22.90
	KIS, GARY MICHAEL	CON 1 PT LOT 14	271104000242500	242500	0.8129	0.3220	\$58.05		\$58.05	\$0.00	\$58.05
	BARKER, VICTOR THOMAS; BARKER, GISELE BRIGITTE	PLAN 42 LOT 80 PT LOTS 70 & 79 NP 801 59R 9778 PART 1	271104000242600	242600	0.5014	0.5010	\$1,013.59		\$1,013.59	\$0.00	\$1,013.59

Assess Summary

Farm	Owner	Legal_Txt	Roll No	ARN	Area	Area in Drain	Sect. 23	Sect. 24	Total	Allowances	Net
				ABBREV							
	MACCABE, NATALIE ANN BETHANY; APOLCER, JEREMY MATHEW	CON 1 PT LOT 14 RP 59R3783 PART 1 PART 2	271104000242700	242700	0.2090	0.2090	\$691.21	\$3,818.41	\$4,509.62	\$0.00	\$4,509.62
	APOLCER, JEREMY MATTHEW; MACCABE, NATALIE ANN BETHANY	CON 1 PT LOT 14	271104000242900	242900	0.0696	0.0700	\$230.51		\$230.51	\$0.00	\$230.51
	SCEPPACERQUA, DREW ALBERT	CON 1 PT LOT 14 RP 59R3783 PART 4	271104000243100	243100	0.1393	0.1390	\$460.68		\$460.68	\$0.00	\$460.68
	FIGUEIRA, MARIO	CON 1 PT LOT 14	271104000243200	243200	0.1144	0.1140	\$378.12		\$378.12	\$0.00	\$378.12
	FIGUEIRA, MARIO	CON 1 PT LOT 14	271104000243300	243300	0.0697	0.0700	\$230.53		\$230.53	\$0.00	\$230.53
	PIZZO, THEODORE ORLANDO	CON 1 PT LOT 14	271104000243400	243400	0.1742	0.1740	\$576.27		\$576.27	\$0.00	\$576.27
	8798494 CANADA CORP	CON 1 PT LOT 14	271104000243500	243500	2.0227	2.0230	\$879.48		\$879.48	\$0.00	\$879.48
	MCADAM, RICHARD WILSON	CON 1 PT LOT 14	271104000243600	243600	0.7984	0.7980	\$483.36		\$483.36	\$0.00	\$483.36
	TOMLINSON, RICHARD MATTHEW	CON 1 PT LOT 14	271104000243700	243700	0.3482	0.3480	\$390.60		\$390.60	\$0.00	\$390.60
	HENDERSON, PERIANNE LYNNE; HENDERSON, BRIAN RICHARD	CON 1 PT LOT 14	271104000243800	243800	0.1865	0.1860	\$275.25		\$275.25	\$0.00	\$275.25
	JAEGGI, STEPHAN; JAEGGI, TAMMY	CON 1 PT LOT 14	271104000243900	243900	0.2321	0.2320	\$383.82		\$383.82	\$0.00	\$383.82
	WELLS, BARBARA ELLEN; BELL, DAVID ANDREW	PLAN 40 LOT 42 LOT 43 NP799	271104000244500	244500	0.1298	0.0170	\$28.82		\$28.82	\$0.00	\$28.82
	MCAVOY, MATTHEW JOHN; MCAVOY, CARRIE	PLAN 40 PT LOTS 39,40 & 50 LOTS 41,49 NP 799 RP59R10110 PART 1	271104000244501	244501	0.1697	0.0800	\$131.76		\$131.76	\$0.00	\$131.76
	ST JOHN'S LUTHERAN CHURCH TRUSTEES	PLAN 40 LOT 48 NP799 CON 1 PT LOT 14	271104000244601	244601	0.4725	0.1940	\$321.16		\$321.16	\$0.00	\$321.16
	SOLOMON, NATHAN ALLEN; SOLOMON, RACHEL CHRISTINE	PLAN 40 LOTS 38 51 52 PT LOTS 37 39 40 50 53 NP799 RP 59R1767 PT 2 RP 59R10110 PT 2	271104000244602	244602	0.2364	0.1590	\$262.26		\$262.26	\$0.00	\$262.26
	PRATT, GARY; PRATT, IRENE	PLAN 40 LOT 36 LOT 54 PT LOTS 35 37 53 & 55 NP799 RP 59R1767 PART 1	271104000244900	244900	0.1838	0.1240	\$205.09		\$205.09	\$0.00	\$205.09
	LECKIE, PATRICIA EVELYN; LECKIE, JAMES FERRELL	PLAN 799 PT BLK A LOTS 34 AND 56 PT LOTS 35 AND 55	271104000245000	245000	0.1229	0.0860	\$142.10		\$142.10	\$0.00	\$142.10
	BANATO, DONNA MARIE; SMITH, PETER WATT	PLAN 799 LOTS 31 TO 33 57 TO 59	271104000245100	245100	0.2362	0.1610	\$265.65		\$265.65	\$0.00	\$265.65
	8798494 CANADA CORP	PLAN 799 LOTS 23 24 30 AND 60 PT LOTS 25 29 61 PT BLK C	271104000245200	245200	0.1057	0.0970	\$160.03		\$160.03	\$0.00	\$160.03
	OLEKSIAK, JAMIESON DEAKIN; OLEKSIAK, ALISON MARIE	PLAN 799 PT LOTS 29&61 PLAN 801 L 74,75 &PT LTS 73,76 RP59R7934 PT 1	271104000245301	245301	0.2108	0.1960	\$324.26		\$324.26	\$0.00	\$324.26
	ALLEN, CHRISTINE; STINZIANI, LUIGI GINO	PLAN 801 PT BLKS A D AND E PT LOTS 65 66 72 73 76 AND 77 RP 59R15049 PARTS 1 TO 4	271104000245400	245400	0.4451	0.2350	\$388.15		\$388.15	\$0.00	\$388.15
	KELLER, ROGER L	PLAN 42 LOT 67 LOT 71 LOT 78 PT LOT 66 PT LOT 72 PT LOT 77 PT BLK D PT BLK E PLAN 40 PT BLK A	271104000245500	245500	0.5330	0.2730	\$450.87		\$450.87	\$0.00	\$450.87
	PRIMERANO, ROBIN; CLARE, IRENE; CLARE, JOHN; CLARE, RANDY	PLAN 42 LOT 68 LOT 69 PT LOT 70	271104000245600	245600	1.2159	0.8350	\$560.47		\$560.47	\$0.00	\$560.47
	ASHBY, JORDAN; ASHBY, MIRANDA	PLAN M-168 LOT 1	271104000252800	252800	0.8255	0.8260	\$1,611.93		\$1,611.93	\$0.00	\$1,611.93
	LUNDY, JANET; LUNDY, JAMES	PLAN 59M168 LOT 2	271104000252900	252900	0.8364	0.8360	\$1,723.79		\$1,723.79	\$0.00	\$1,723.79
	SAXTON, THOMAS ROBERT; SAXTON, MARIA	PLAN 59M168 LOT 3	271104000253000	253000	0.8468	0.8470	\$1,760.10		\$1,760.10	\$0.00	\$1,760.10
	JAMES, WILLIAM RUSSELL	PLAN 59M168 LOT 4	271104000253100	253100	0.8802	0.8800	\$1,829.53		\$1,829.53	\$0.00	\$1,829.53
	DANIEL, VINCENT; DANIEL, ARUNA	PLAN 59M168 LOT 5	271104000253200	253200	0.8147	0.8150	\$1,693.47		\$1,693.47	\$0.00	\$1,693.47
	PETERSON, ALLAN BERT; PETERSON, LISA MARIE	PLAN 59M168 LOT 6	271104000253300	253300	0.8156	0.8160	\$1,695.36		\$1,695.36	\$0.00	\$1,695.36
	SALIBA, CARMEL JOSEPH; SALIBA, CHRISTINA GRACE	PLAN 59M168 LOT 7	271104000253400	253400	0.7515	0.7520	\$1,562.22		\$1,562.22	\$0.00	\$1,562.22
	MORRISON, DAVID JOHN; MORRISON, BONNIE SUE	PLAN 59M175 LOT 3	271104000253500	253500	0.8188	0.8190	\$1,702.04		\$1,702.04	\$0.00	\$1,702.04
	ASHBY, JOANNE; SIMPSON, BRIAN	PLAN 59M-175 LOT 4	271104000253600	253600	0.8341	0.8340	\$1,733.61		\$1,733.61	\$0.00	\$1,733.61
	GIRARD, ANGELA JACQUELINE; GIRARD, STEED	PLAN 59M175 LOT 5	271104000253700	253700	0.8423	0.8420	\$1,750.62		\$1,750.62	\$0.00	\$1,750.62
	YOUNG, CHANTAL	PLAN 59M175 LOT 6	271104000253800	253800	0.8343	0.8340	\$1,734.11		\$1,734.11	\$0.00	\$1,734.11
	TYPER, JULIANNA MARIANNA	PLAN 59M175 LOT 7	271104000253900	253900	0.8083	0.8080	\$1,680.03		\$1,680.03	\$0.00	\$1,680.03
	COMFORT, CHRISTOPHER HERMAN; COMFORT, JOSEPHINE ANN	PLAN 59M175 LOT 1	271104000254000	254000	0.6468	0.6470	\$1,344.43		\$1,344.43	\$0.00	\$1,344.43
	FONTAINE, BARBARA	PLAN 59M175 LOT 2	271104000254100	254100	0.6235	0.6240	\$1,296.18		\$1,296.18	\$0.00	\$1,296.18
	REPEC, JENNIFER	HUMBERSTONE CON 1 PT LOT 15 PLAN 796 PT BLKS A AND B LOTS 8 TO 14 PT LOT 15 PT WATER LOT	271104000300900	300900	5.9988	3.4410	\$5,691.58		\$5,691.58	\$0.00	\$5,691.58
	VIOLIN, ELIZABETH IRENE; VIOLIN, VICTOR EMILIO	PLAN 796 PT BLK B BROKEN LOTS 15 AND 16	271104000301000	301000	2.2699	1.5320	\$2,535.51		\$2,535.51	\$0.00	\$2,535.51
	KEPPY, JANE AUDREE; COCKSHUTT, WILLIAM ANTHONY	HUMBERSTONE CON 1 PT LOT 16 PLAN 796 PT BLK B PT WATER LOT RP 59R15083 PARTS 1 AND 2	271104000301100	301100	1.3959	0.5530	\$915.29		\$915.29	\$0.00	\$915.29
	BODNER, MEGAN; FARNAN, SCOTT	PLAN 796 PT BLK B RP 59R12610 PART 1	271104000301101	301101	0.5496	0.5500	\$862.76		\$862.76	\$0.00	\$862.76
	FALLON, KERRY BERNARD	PLAN 796 PT BLK B RP 59R12610 PART 2	271104000301105	301105	0.9272	0.9270	\$1,533.40		\$1,533.40	\$0.00	\$1,533.40
	FLETT, SUSANNE MAY; FLETT, JOHN ROSS	PLAN 796 PT BLK B HUMBERSTONE CON 1 PT WATER LOT IN FRONT OF LOT 16 AND RP 59R11670 PART 1 UNREG	271104000301200	301200	2.3190	1.4780	\$1,270.27		\$1,270.27	\$0.00	\$1,270.27
	GROOM, JOSHUA NATHAN; GROOM, KRISTAL LYNN	PLAN 37 LOT 16 PT LOT 15 NP796	271104000301300	301300	0.5266	0.5270	\$871.05	\$3,448.89	\$4,319.94	\$0.00	\$4,319.94
	JASEK, COLLEEN R; JASEK, JOHN M	PLAN 37 LOT 17 NP796	271104000301400	301400	0.4571	0.4570	\$755.74	\$3,547.43	\$4,303.17	\$0.00	\$4,303.17

Farm	Owner	Legal_Txt	Roll No	ARN ABBREV	Area	Area in Drain	Sect. 23	Sect. 24	Total	Allowances	Net	
*#4	HOLODAY, SUSAN-PIETRAS; HOLODAY, RICHARD	PLAN 37 LOT 18 PT LOT 19 NP796	271104000301500	301500	0.6470	0.6340	\$1,048.30	\$3,366.77	\$4,415.07	\$0.00	\$4,415.07	
	MORRISON, HALEY MARILYN; MINOR, DUNCAN LINCOLN	PLAN 37 PT LOT 19 NP796	271104000301600	301600	0.2054	0.2040	\$336.73		\$336.73	\$0.00	\$336.73	
	KRIEGER, LESLEY EILEEN	PLAN 37 LOT 20 NP796	271104000301700	301700	0.3953	0.3850	\$636.01		\$636.01	\$0.00	\$636.01	
	BUCHANAN, CHERIE ELIZABETH; BUCHANAN, ROBERT JOSEPH	PLAN 37 PT LOT 21 NP796	271104000301800	301800	0.1490	0.1220	\$202.40		\$202.40	\$0.00	\$202.40	
	SMITH, MARJORY LEE; SMITH, BRIAN WESLEY	PLAN 37 PT LOT 22 NP796	271104000301900	301900	0.1194	0.0770	\$126.74		\$126.74	\$0.00	\$126.74	
	SIMPSON, KORY; BELSKY, IGOR	PLAN 37 PT LOT 22 NP796	271104000302000	302000	0.0510	0.0140	\$22.38		\$22.38	\$0.00	\$22.38	
	WINGER, W A	PLAN 796 PT BLK A	271104000302001	302001	0.4597	0.0660	\$110.60		\$110.60	\$0.00	\$110.60	
	BEGG, TERRY-LYNN	PLAN 37 PT LOT 21 PT LOT 22 NP796	271104000302100	302100	0.5792	0.5790	\$957.90	\$2,463.49	\$3,421.39	\$0.00	\$3,421.39	
	METCALF, IVANA KOMLIJENOVIC; METCALF, THOMAS ASA	CON 1 PT LOT 15 RP 59R7605 PART 1	271104000302610	302610	0.4045	0.4050	\$669.15	\$5,419.68	\$6,088.83	\$0.00	\$6,088.83	
	1000071167 ONTARIO INC	HUMBERSTONE CON 1 PT LOT 16 PT LOT 15	271104000302700	302700	21.1469	21.1470	\$41,667.08	\$4,434.28	\$46,101.36	\$0.00	\$46,101.36	
F	SAWDON, SONJA ODARKA; SAWDON, DEBORAH ANN	CON 1 PT LOT 15	271104000302800	302800	14.0778	14.0780	\$32,596.11		\$32,596.11	\$0.00	\$32,596.11	
F	CROWDER, MARTHA; MOORE, RICHARD WILLIAM	CON 1 PT LOT 15 PT LOT 16	271104000302900	302900	20.8284	14.9820	\$14,324.72		\$14,324.72	\$0.00	\$14,324.72	
	JONES, LARRY WAYNE	CON 1 PT LOT 15	271104000303000	303000	0.4046	0.4050	\$512.62		\$512.62	\$0.00	\$512.62	
	SHAUBEL, ALLEN WILLIAM	CON 1 PT LOT 15	271104000303100	303100	0.9148	0.9150	\$1,158.95		\$1,158.95	\$0.00	\$1,158.95	
F	NIGH, HAROLD ALFRED; NIGH, JANE CAROLYN	CON 1 PT LOT 15 PT LOT 16	271104000303200	303200	20.4940	11.3440	\$11,176.79		\$11,176.79	\$0.00	\$11,176.79	
F	FEHRMAN, AMY LEE; FEHRMAN, PAUL ALLAN	CON 1 PT LOT 15 PT LOT 16	271104000303400	303400	39.5797	10.3560	\$10,203.35		\$10,203.35	\$0.00	\$10,203.35	
	FANNON, SYLVIA ROSE; FANNON, WILLIAM THOMAS	CON 1 PT LOT 15	271104000303500	303500	0.4473	0.4470	\$566.57		\$566.57	\$0.00	\$566.57	
	PORT COLBORNE CITY	CON 1 PT LOTS 1-22	271104000499900	499900	1.6006	1.6010	\$4,184.86	\$11,208.89	\$15,393.74	\$0.00	\$15,393.74	
							253.865	\$322,785.54	\$57,526.72	\$380,312.26	\$0.00	\$380,312.26
Section 23: Roadway Assessment												
Roads												
	City of Port Colborne	Pinecrest Road			4.062	148317	\$15,536.61					
	City of Port Colborne	Richard Avenue			0.616	148341	\$2,702.59					
	City of Port Colborne	Tammy Avenue			0.549	148342	\$2,408.59					
	City of Port Colborne	Tracy Terrace			0.750	148362	\$3,290.59					
	City of Port Colborne	Vimy Ridge Road From Pinecrest Road To Centennial Park			0.790	148378	\$3,416.79					
	City of Port Colborne	Vimy Ridge Road From Centennial Park To Cedar Bay Road			0.571	148415	\$390.87					
	City of Port Colborne	Firelane 4 From Centennial Park To Cedar Bay Road			0.399	148461	\$1,767.37					
	City of Port Colborne	June Road From Centennial Park To Cedar Bay Road			0.399	148477	\$1,901.93					
	City of Port Colborne	Cedar Bay Road			3.343	148506	\$12,659.08					
					11.478		\$44,074.42					
						265.343						
Section 26: Special Assessments												
	City of Port Colborne	Relay Culvert O-CS-08 to design gradeline includes grouted joint seal and new bedding			\$8,540				\$8,540.13			
	Niagara Regional Broadband Network, (NRBN)	Utility protection and relaying during construction of the culvert.			\$3,882				\$3,881.88			
						\$12,422.00						
Oil Mill Creek Drain												
Total Assessed: \$436,808.69												
Notes: 1. The above lands marked "F" are currently classified as agricultural according to the OMAFRA and are therefore entitled to a 1/3 grant. 2. Section 21 of the Drainage Act, RSO 1990 requires that assessments be shown for each parcel of land and road affected. The affected parcels of land are identified using the roll number received from the City. For convenience only, the owners' names are shown by the last revised assessment roll. 3. The value of the assessments identified in this schedule are estimates only, and should not be considered final. 4. Property 271104000302001 is a private road, Firelane 2 and ownership is shared. W A Winger is the name on the property record.												

7 Oil Mill Creek Drain Report Conclusions

This report has identified a series of drain improvements, including maintenance, to ensure suitable channel design flows are achieved. Also, drain alignments based on identified property impacts have been developed through the plan and profile.

The following are summary descriptions of the planned improvements:

1. The existing Oil Mill Creek Outlet.
The primary improvements are related to site safety for the operation of the raising and lowering of the existing flap gate.
The inclusion of smaller flap gates to provide more passive flow opportunities is a low-cost adjustment to reduce the frequency of gate adjustment.
2. Grade line improvements to the E1 Branch
The proposed improvement to the grade line of E1 achieves a lower upper channel bottom that will improve the outlet drainage serving the Bell Acres subdivision.
3. Maintenance work and outlet re-alignment for E2 Branch
Convert the two outlet branch connections into one improved alignment flow path for E2 and E3. Clean and improve the existing channel to Merkel Rd.
4. Channel geometry conversion for E3 Branch with culvert improvement.
The channel is compromised, and the existing culvert has grade line problems. Reconstruction into a low flow and high flood channel geometry with new culvert is proposed.
5. West Branch grade line culvert improvements, including rock removal and reuse as riffles and pools on the OMC main channel.
6. The proposed Centennial Wetland will reduce runoff peak flow using flow storage and slow release. The cost of the wetland is balanced against the reduction in regular flooding that currently exists. However, the wetland does not eliminate flooding, which still occurs for larger storms. The wetland does reduce the impact of flooding events in all cases by giving room for each flood event.

These improvements reduce the flooding impacts but do not eliminate the impact of flooding especially for storms larger than the design case, 68.9mm per 24 hours.

Appendix A:
Drainage Design Drawings;
Plans, Profiles

Oil Mill Creek Municipal Drain

City of Port Colborne

FEBRUARY 20, 2025

ISSUED FOR REPORT

LEGEND

	EXISTING DITCH BOTTOM (NPCA DEM DATA)
	EXISTING DITCH BOTTOM (SURVEYED)
	HISTORICAL GRADELINE
	PROPOSED DRAIN GRADELINE-EWA, 2022
	LEFT BANK
	RIGHT BANK
	EXISTING DRAIN SECTION
	EXISTING STRUCTURE DETAILS
	ASSUMED EXISTING STRUCTURE DETAILS
	EXISTING DRAIN ELEVATION
	PROPOSED DRAIN CENTERLINE ELEVATION
	PROPOSED DRAIN ELEVATION (WHERE MATCHES EXISTING ELEVATION)
	DATA POINT FROM HISTORICAL DESIGN GRADELINE RVA, 1979
	BRIDGE STRUCTURES
	WATER LEVEL FROM SURVEY DATA, INDICATIVE

DRAWING INDEX

DWG I.D.	DWG Title
PLAN	PLAN OF CONSTRUCTION
P0	MAIN BRANCH - PROFILE STA: -0+175 to 1+936
P1	MAIN BRANCH - PROFILE STA: -0+150 to 0+300
P2	MAIN BRANCH - PROFILE STA: 0+300 to 1+943 EOD
P3	E1 BRANCH - PROFILE STA: -0+100 to 1+277
P4	E2 BRANCH - PROFILE STA: 0+000 to 0+348
	E3 BRANCH - PROFILE STA: -0+100 to 0+222
P5	WEST BRANCH - PROFILE STA: -0+100 to 1+188
P6	OUTLET - PLAN/PROFILE STA: -0+150 to 0+100
SD-1	PROPOSED CENTENNIAL WETLANDS PLAN VIEW
SD-2	PROPOSED CENTENNIAL PONDS CROSS SECTIONS EAST & WEST
SD-3	PROPOSED CENTENNIAL WETLAND WEIR DETAILS
SD-4	OUTLET IMPROVEMENTS & BREAK WALL
GD	GENERAL DETAILS
CN	CONSTRUCTION NOTES


CITY OF PORT COLBORNE
ALANA VANDER VEEN
DRAINAGE SUPERINTENDENT
ENGINEERING AND OPERATIONS CENTRE
1 KILLAY ST W, PORT COLBORNE, ON L3K 2L5
PHONE 905-228-8127
ALANA.VANDERVEEN@PORTCOLBORNE.CA

EWA ENGINEERING INC.
PAUL C. MARSH, P.ENG.
APPOINTED DRAINAGE ENGINEER
27 CHADWICK AVENUE, GUELPH, ON N1H 3E7
PHONE 647.400.2824
PCMARSH@EWAENG.COM




LOCATION PLAN

(N.T.S.)




KEY PLAN

(N.T.S.)



OIL MILL CREEK MUNICIPAL DRAIN - 2024

OIL MILL CREEK DRAIN: -0+175 to 1+943



- NOTES:**
- DIMENSIONS ARE IN METRES UNLESS OTHERWISE NOTED.
 - THE ACCURACY OF THE UTILITIES SHOWN IS APPROXIMATE BASED ON AVAILABLE DATA. THE CONSTRUCTOR IS TO HAVE LOCATES PRIOR TO THE START OF CONSTRUCTION.
 - THE CONSTRUCTOR IS TO PROTECT EXISTING UTILITIES DURING CONSTRUCTION AND TO NOTIFY THE OWNER AND DRAINAGE ENGINEER OF CONFLICTS BETWEEN EXISTING UTILITIES AND PROPOSED WORKS.
 - BRUSHING AND GRUBBING ARE TO COMPLY WITH SPECIAL PROVISIONS.
 - SHOP DRAWING SUBMISSIONS FOR APPROVED EQUIVALENT OPTIONS ARE TO BE PROVIDED A MINIMUM OF 4 WEEKS PRIOR TO CONSTRUCTION START.
 - THE CONSTRUCTOR IS RESPONSIBLE FOR SITE LAYOUT AND ACHIEVING THE PROPOSED CONSTRUCTED GRADE WITHIN THE IDENTIFIED MAXIMUM 100MM DEVIATION OR BE ASKED TO RESTORE TO DESIGN GRADE LINE.
 - THE DRAINAGE SUPERINTENDENT WILL BE NOTIFIED, AND APPROVAL WILL BE OBTAINED PRIOR TO TREE REMOVAL. TREES REMOVED WILL BE CONFIRMED FOR THE CANOPY PROTECTION PROGRAM.
 - THE CONSTRUCTOR IS RESPONSIBLE FOR ENVIRONMENTAL COMPLIANCE DURING CONSTRUCTION. THE CONSTRUCTOR IS RESPONSIBLE FOR SITE EROSION CONTROL TO MEET DFO REQUIREMENTS AND OTHER AGENCIES.

THE POSITION OF POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND, WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED.

BEFORE STARTING WORK, THE CONTRACTOR SHALL INFORM THEMSELVES OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE DONE TO THEM.


- SPATIAL DATA:**
- HORIZONTAL DATUM: UTM NAD83-CSRS ZONE 17N
 - VERTICAL DATUM: CGVD28-1978
 - ACCURACY: ABSOLUTE HORIZONTAL AND VERTICAL POSITIONAL ACCURACIES OF ±0.02m

LEGEND

	EXISTING DITCH BOTTOM (NPCA DEM DATA)
	EXISTING DITCH BOTTOM (SURVEYED)
	HISTORICAL GRADELINE
	PROPOSED DRAIN GRADELINE-EWA, 2022
	LEFT BANK
	RIGHT BANK
	EXISTING DRAIN SECTION
	EXISTING STRUCTURE DETAILS
	ASSUMED EXISTING STRUCTURE DETAILS
	EXISTING DRAIN ELEVATION
	PROPOSED DRAIN CENTERLINE ELEVATION
	PROPOSED DRAIN ELEVATION (WHERE MATCHES EXISTING ELEVATION)
	DATA POINT FROM HISTORICAL DESIGN GRADELINE 1978
	BRIDGE STRUCTURES
	WATER LEVEL FROM SURVEY DATA, INDICATIVE


5		
4		
3		
2		
1	ISSUED FOR REPORT	JUNE 20, 2024
NO.	REVISION DESCRIPTION	DATE

OIL MILL CREEK MUNICIPAL DRAIN PROFILE
STA -0+130 to 1+943



DRAWN BY : KD	APPROVED BY : PCM	PROJECT NO. : 19-9998	DRAWING NO. : OM.P0
DESIGNED BY : PCM	DATE : 20-JUN-2024	SCALE : FIT TO PAGE	

OIL MILL CREEK DRAIN: -0+150 to 0+380



- ### NOTES:
1. DIMENSIONS ARE IN METRES UNLESS OTHERWISE NOTED.
 2. THE ACCURACY OF THE UTILITIES SHOWN IS APPROXIMATE BASED ON AVAILABLE DATA. THE CONSTRUCTOR IS TO HAVE LOCATES PRIOR TO THE START OF CONSTRUCTION.
 3. THE CONSTRUCTOR IS RESPONSIBLE FOR IDENTIFYING UTILITIES DURING CONSTRUCTION AND TO NOTIFY THE OWNER AND DRAINAGE ENGINEER OF CONFLICTS BETWEEN EXISTING UTILITIES AND PROPOSED WORKS.
 4. BRUSHING AND GRUBBING ARE TO COMPLY WITH SPECIAL PROVISIONS.
 5. SHOP DRAWING SUBMISSIONS FOR APPROVED EQUIVALENT OPTIONS ARE TO BE PROVIDED A MINIMUM OF 4 WEEKS PRIOR TO CONSTRUCTION START.
 6. THE CONSTRUCTOR IS RESPONSIBLE FOR SITE LAYOUT AND ACHIEVING THE PROPOSED CONSTRUCTED GRADE WITHIN THE IDENTIFIED MAXIMUM 100MM DEVIATION OR BE ASKED TO RESTORE TO DESIGN GRADE LINE.
 7. THE DRAINAGE SUPERINTENDENT WILL BE NOTIFIED, AND APPROVAL WILL BE OBTAINED PRIOR TO REMOVAL OF TREES REMOVED WILL BE CONFIRMED FOR THE CANOPY PROTECTION PROGRAM.
 8. THE CONSTRUCTOR IS RESPONSIBLE FOR ENVIRONMENTAL COMPLIANCE DURING CONSTRUCTION. THE CONSTRUCTOR IS RESPONSIBLE FOR SITE EROSION CONTROL TO MEET DFO REQUIREMENTS AND OTHER AGENCIES.

THE POSITION OF POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND, WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED.

BEFORE STARTING WORK, THE CONTRACTOR SHALL INFORM THEMSELVES OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE DONE TO THEM.

SPATIAL DATA:

- HORIZONTAL DATUM: UTM NAD83-CSRS ZONE 17N
- VERTICAL DATUM: CGVD28-1978
- ACCURACY: ABSOLUTE HORIZONTAL AND VERTICAL POSITIONAL ACCURACIES OF $\pm 0.02\text{m}$

LEGEND

	EXISTING DITCH BOTTOM (NPCA DEM DATA)
	EXISTING DITCH BOTTOM (SURVEYED)
	HISTORICAL GRADELINE
	PROPOSED DRAIN GRADELINE-EWA, 2022
	LEFT BANK
	RIGHT BANK
	EXISTING DRAIN SECTION
	EXISTING STRUCTURE DETAILS
	ASSUMED EXISTING STRUCTURE DETAILS
	EXISTING DRAIN ELEVATION
	PROPOSED DRAIN CENTERLINE ELEVATION
	PROPOSED DRAIN ELEVATION (WHERE IT MATCHES EXISTING ELEVATION)
	DATA POINT FROM HISTORICAL DESIGN GRADELINE RVA, 1979
	BRIDGE STRUCTURES
	WATER LEVEL FROM SURVEY DATA, INDICATIVE


5		
4		
3		
2		
1	ISSUED FOR REPORT	JUNE 20, 2024
NO.	REVISION DESCRIPTION	DATE

**OIL MILL CREEK MUNICIPAL
DRAIN PROFILE**
STA -0+150 to 0+380



DRAWN BY : KD	APPROVED BY : PCM	PROJECT NO. : 19-9998	DRAWING NO. : OM.P1
DESIGNED BY : PCM	DATE : 20-JUN-2024	SCALE : H=1:2500 V=1:25	

OIL MILL CREEK: 0+380 to 1+943

[illegible]

- NOTES:**
1. DIMENSIONS ARE IN METRES UNLESS OTHERWISE NOTED.
 2. THE ACCURACY OF THE UTILITIES SHOWN IS APPROXIMATE BASED ON AVAILABLE DATA. THE CONSTRUCTOR IS TO HAVE LOCATES PRIOR TO THE START OF CONSTRUCTION.
 3. THE CONSTRUCTOR IS RESPONSIBLE FOR EXISTING UTILITIES DURING CONSTRUCTION AND TO NOTIFY THE OWNER AND DRAINAGE ENGINEER OF CONFLICTS BETWEEN EXISTING UTILITIES AND PROPOSED WORKS.
 4. BRUSHING AND GRUBBING ARE TO COMPLY WITH SPECIAL PROVISIONS.
 5. SHOP DRAWING SUBMISSIONS FOR APPROVED EQUIVALENT MATERIALS ARE TO BE PROVIDED A MINIMUM OF 4 WEEKS PRIOR TO CONSTRUCTION START.
 6. THE CONSTRUCTOR IS RESPONSIBLE FOR SITE LAYOUT AND ACHIEVING THE PROPOSED CONSTRUCTED GRADE WITHIN THE IDENTIFIED MAXIMUM TOLERANCE DEVIATION OR BE ASKED TO RESTORE TO DESIGN GRADE LINE.
 7. THE DRAINAGE SUPERINTENDENT WILL BE NOTIFIED, AND APPROVAL WILL BE OBTAINED PRIOR TO TREE REMOVAL. TREES REMOVED WILL BE CONFIRMED FOR THE CANOPY PROTECTION PROGRAM.
 8. THE CONSTRUCTOR IS RESPONSIBLE FOR ENVIRONMENTAL COMPLIANCE DURING CONSTRUCTION. THE CONSTRUCTOR IS RESPONSIBLE FOR SITE EROSION CONTROL TO MEET DFO REQUIREMENTS AND OTHER AGENCIES.








THE POSITION OF POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND, WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED.

BEFORE STARTING WORK, THE CONTRACTOR SHALL INFORM THEMSELVES OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE DONE TO THEM.

SPATIAL DATA:

- HORIZONTAL DATUM: UTM NAD83-CSRS ZONE 17N
- VERTICAL DATUM: CGVD28-1978
- ACCURACY: ABSOLUTE HORIZONTAL AND VERTICAL POSITIONAL ACCURACIES OF $\pm 0.02\text{m}$

LEGEND

	EXISTING DITCH BOTTOM (NPCA DEM DATA)
	EXISTING DITCH BOTTOM (SURVEYED)
	HISTORICAL GRADELINE
	PROPOSED DRAIN GRADELINE-EWA, 2022
	LEFT BANK
	RIGHT BANK
	EXISTING DRAIN SECTION
	EXISTING STRUCTURE DETAILS
	ASSUMED EXISTING STRUCTURE DETAILS
	EXISTING DRAIN ELEVATION
	PROPOSED DRAIN CENTERLINE ELEVATION
	PROPOSED DRAIN ELEVATION (WHERE MATCHES EXISTING ELEVATION)
	DATA POINT FROM HISTORICAL DESIGN GRADELINE RVA, 1979
	BRIDGE STRUCTURES
	WATER LEVEL FROM SURVEY DATA, INDICATIVE


5		
4		
3		
2		
1	ISSUED FOR REPORT	JUNE 20, 2024
NO.	REVISION DESCRIPTION	DATE

**OIL MILL CREEK MUNICIPAL
DRAIN PROFILE**
STA 0+300 to 1+943



DRAWN BY : KD	APPROVED BY : PCM	PROJECT NO. : 19-9998	DRAWING NO. : OM.P2
DESIGNED BY : PCM	DATE : 20-JUN-2024	SCALE : H=1:2500 V=1:25	

E1 BRANCH: 0+000 to 1+277



PROPERTY, INFO, CONSTRUCTION, DESIGN, GRADE, DATA, NOTES	DRAIN GRADE ELEVATION	PR	EX	(m)
	PR 174.90 EX 174.66 (0.24 m)			0+000
	PR 175.02 EX 174.68 (0.13 m)			0+100
	PR 175.13 EX 174.67 (0.26 m)			0+200
	PR 175.28 EX 175.20 (0.08 m)			0+300
	PR 175.40 EX 175.37 (0.03 m)			0+400
	PR 175.55 EX 175.51 (0.04 m)			0+500
	PR 175.67 EX 175.93 (-0.26 m)			0+600
	PR 175.79 EX 176.17 (-0.38 m)			0+700
	PR 176.01 EX 176.32 (-0.31 m)			0+800
	PR 176.33 EX 176.56 (-0.22 m)			0+900
	PR 176.63 EX 176.79 (-0.16 m)			1+000
	PR 176.93 EX 177.12 (-0.19 m)			1+100
	PR 177.29 EX 177.44 (-0.22 m)			1+200
				EOD=1+277

STATION	N	E	ELEV
0+000	4748790.2	648424.3	174.900
0+250	4749048.9	648419.9	175.200
0+265	4749054.2	648420.0	175.250
0+331	4749055.6	648485.3	175.300
0+515	4749238.5	648482.0	175.574
0+692	4749249.5	648657.9	175.775
0+875	4749429.2	648665.1	176.175
0+880	4749429.2	648665.1	176.275
1+277	4749440.2	649061.6	177.450

SECTION	DESCRIPTION	LENGTH (m)
SECT. 74	MAINTENANCE OF EXISTING DRAIN TO PROPOSED GRADE LINE FOR 515m.	515
SECT. 78	PROPOSED IMPROVED GRADE LINE. RECONSTRUCT TO GRADE LINE AND CHANNEL DESIGN 762m.	762

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000	ARN:242101	104.5m				
0+104						
0+404						
0+409	ARN:240900	742.4m				
0+849						
0+874						
0+874						
1+074	ARN:238600	199.6m				
1+074						
1+273	ARN:238700	199.3m				
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						
1+074						
1+273						
1+273						
1+277						

PROPERTY	INFO	CONSTRUCTION	DESIGN	GRADE	DATA	NOTES
0+000						
0+104						
0+404						
0+409						
0+849						
0+874						
0+874						
1+074						

E2 BRANCH: 0+000 to 0+350

0+000

0+100

0+200

0+300

0+350

EXISTING E2 BRANCH
OUTLET TO BE FILLED WITH
SPOIL FROM NEW ALIGNMENT.

E2 BRANCH
OUTLET
RE-ALIGNMENT

OIL MILL CREEK
DRAIN

0-BS-04

0-BS-05

E3 BRANCH

234100

234200

234300

234400

235600

235500

235400

235700

235800

235900

236000

FIRELANE 4

JUNE ROAD

237300

MERKEL ROAD

1. DIMENSIONS ARE IN METRES UNLESS OTHERWISE NOTED
2. THE ACCURACY OF THE UTILITIES SHOWN IS APPROXIMATE BASED ON AVAILABLE DATA. THE CONSTRUCTOR IS TO HAVE LOCATES PRIOR TO THE START OF CONSTRUCTION.
3. THE CONSTRUCTOR IS TO PROTECT EXISTING UTILITIES DURING CONSTRUCTION AND TO NOTIFY THE OWNER AND DRAINAGE ENGINEER OF ANY CONFLICTS BETWEEN EXISTING UTILITIES AND PROPOSED WORKS.
4. BRUSHING AND GRUBBING ARE TO COMPLY WITH SPECIAL PROVISIONS.
5. SHOP DRAWING SUBMISSIONS FOR APPROVED EQUIVALENT OPTIONS ARE TO BE PROVIDED A MINIMUM OF 4 WEEKS PRIOR TO CONSTRUCTION.
6. THE CONSTRUCTOR IS RESPONSIBLE FOR SITE LAYOUT AND ACHIEVING THE PROPOSED CONSTRUCTED GRADE WITHIN THE SPECIFIED MAXIMUM 100MM DEVIATION OR BE ASKED TO RESTORE TO DESIGN GRADE LINE.
7. THE DRAINAGE SUPERINTENDENT WILL BE NOTIFIED, AND APPROVAL WILL BE OBTAINED PRIOR TO TREE REMOVAL. TREES REMOVED WILL BE CONFIRMED FOR THE CANOPY PROTECTION PROGRAM.
8. THE CONSTRUCTOR IS RESPONSIBLE FOR ENVIRONMENTAL COMPLIANCE DURING CONSTRUCTION. THE CONSTRUCTOR IS RESPONSIBLE FOR SITE EROSION CONTROL TO MEET DFO REQUIREMENTS AND OTHER AGENCIES.

BEFORE STARTING WORK, THE CONTRACTOR SHALL INFORM THEMSELVES OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE DONE TO THEM.


- HORIZONTAL DATUM: UTM NAD83-CSRS ZONE 17N
- VERTICAL DATUM: CGVD28-1978
- ACCURACY: ABSOLUTE HORIZONTAL AND VERTICAL POSITIONAL ACCURACIES OF $\pm 0.02\text{m}$

	EXISTING DITCH BOTTOM (NPCA DEM DATA)
	EXISTING DITCH BOTTOM (SURVEYED)
	PROPOSED DRAIN GRADELINE
	PROPOSED DRAIN GRADELINE-EWA, 2022
	LEFT BANK
	RIGHT BANK
	EXISTING DRAIN SECTION
	EXISTING STRUCTURE DETAILS
	ASSUMED EXISTING STRUCTURE DETAILS
	EXISTING DRAIN ELEVATION
	PROPOSED DRAIN ELEVATION
	PROPOSED DRAIN ELEVATION (WHERE MATCHES EXISTING ELEVATION)
	DATA POINT FROM HISTORICAL DESIGN GRADELINE RVA, 1979
	BRIDGE STRUCTURES
	WATER LEVEL FROM SURVEY DATA, INDICATIVE


OIL MILL CREEK E2/E3 BRANCH
DRAIN PROFILE
STA 0+000 to 0+350

DRAIN PROFILE
STA 0+000 to 0+222


A circular professional seal for Paul C. Marsh, a Licensed Professional Engineer in the Province of Ontario. The seal features the text "LICENSED PROFESSIONAL ENGINEER" around the top and "PROVINCE OF ONTARIO" around the bottom. In the center, the name "PAUL C. MARSH" is printed below a stylized signature. A date stamp "2024-06-20" is visible over the bottom portion of the seal.



PLOT DATE: June 19, 2024



FILE PATH:




COFPC OLDMILL\DESIGN\DWG\IFR100\OMC_EWA_100_2.DWG

CL - CENTRELINE PROPOSED
TWO STAGE CHANNEL

_____ MAY NOT EXISTING BANKS.

WEST BRANCH DRAIN: 0+000 to 1+188



PROFILE VIEW
SCALE H=1:2500 V=1:2

FILE PATH

D:\PROJECTS\199998 COFPC OLDMILL\DESIGN\DWG\IFR100\OMC_EWA_100_2.DWG

FILE NAME:

OMC_EWA_100_2.DWG

PLOT DATE: June 19, 2024

- NOTES:**
1. DIMENSIONS ARE IN METRES UNLESS OTHERWISE NOTED.
 2. THE ACCURACY OF THE UTILITIES SHOWN IS APPROXIMATE BASED ON AVAILABLE DATA. THE CONSTRUCTOR IS TO HAVE LOCATES PRIOR TO THE START OF CONSTRUCTION.
 3. THE CONSTRUCTOR IS TO PROTECT EXISTING UTILITIES DURING CONSTRUCTION AND TO BE RESPONSIBLE FOR THE HIRE OF AN ENGINEER OF CONFLICTS BETWEEN EXISTING UTILITIES AND PROPOSED WORKS.
 4. BRUSHING AND GRUBBING ARE TO COMPLY WITH SPECIAL PROVISIONS.
 5. SHOP DRAWING SUBMISSIONS FOR EQUIPMENT AND MATERIALS ARE TO BE PROVIDED A MINIMUM OF 4 WEEKS PRIOR TO CONSTRUCTION START.
 6. THE CONSTRUCTOR IS RESPONSIBLE FOR SITE LAYOUT AND ADDRESSING TO PROTECT THE CONSTRUCTED GRADE 2 WITHIN THE IDENTIFIED MAXIMUM 100MM DEVIATION OR BE ASKED TO RESTORE TO DESIGN GRADE LINE.
 7. THE TREE REMOVAL SUPERINTENDENT WILL BE NOTIFIED, AND APPROVAL WILL BE OBTAINED PRIOR TO TREE REMOVAL. TREES REMOVED WILL BE CONFIRMED FOR THE CANOPY PROTECTION PROGRAM.
 8. THE CONSTRUCTOR IS RESPONSIBLE FOR ENVIRONMENTAL COMPLIANCE DURING CONSTRUCTION. THE CONSTRUCTOR IS RESPONSIBLE FOR EROSION CONTROL TO MEET DFO REQUIREMENTS AND OTHER AGENCIES.


THE POSITION OF POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND, WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED.

BEFORE STARTING WORK, THE CONTRACTOR SHALL INFORM THEMSELVES OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE DONE TO THEM.

SPATIAL DATA

- HORIZONTAL DATUM: UTM NAD83-CSRS ZONE 17N
- VERTICAL DATUM: CGVD28-1978
- ACCURACY: ABSOLUTE HORIZONTAL AND VERTICAL POSITIONAL ACCURACIES OF $\pm 0.02\text{m}$

LEGEND


	EXISTING DITCH BOTTOM (NPCA DEM DATA)
	EXISTING DITCH BOTTOM (SURVEYED)
	HISTORICAL GRADELINE
	PROPOSED DRAIN GRADELINE—EWA, 2022
	LEFT BANK
	RIGHT BANK
	EXISTING DRAIN SECTION
	EXISTING STRUCTURE DETAILS
	ASSUMED EXISTING STRUCTURE DETAILS
	EXISTING DRAIN ELEVATION
	PROPOSED DRAIN CENTERLINE ELEVATION
	PROPOSED DRAIN ELEVATION (WHERE MATCHES EXISTING ELEVATION)
	DATA POINT FROM HISTORICAL DESIGN GRADELINE RRA, 1979
	BRIDGE STRUCTURES
	WATER LEVEL FROM SURVEY DATA, INDICATIVE





5		
4		
3		
2		
1	ISSUED FOR REPORT	JUNE 20, 2024
NO.	REVISION DESCRIPTION	DATE

**OIL MILL CREEK WEST BRANCH
DRAIN PROFILE**
STA 0+000 to 1+188



DRAWN BY : KD	APPROVED BY : PCM	PROJECT NO. : 19-9998	DRAWING NO. : OM.P5
DESIGNED BY : PCM	DATE : 20-JUN-2024	SCALE : H=1:2500 V=1:25	





- NOTES:**
- DIMENSIONS ARE IN METRES UNLESS OTHERWISE NOTED.
 - THE ACCURACY OF THE UTILITIES SHOWN IS APPROXIMATE BASED ON AVAILABLE DATA. THE CONSTRUCTOR IS TO HAVE LOCATES PRIOR TO THE START OF CONSTRUCTION.
 - THE CONSTRUCTOR IS TO PROTECT EXISTING UTILITIES DURING CONSTRUCTION AND TO NOTIFY THE OWNER AND DRAINAGE ENGINEER OF CONFLICTS BETWEEN EXISTING UTILITIES AND PROPOSED WORKS.
 - BRUSHING AND GRUBBING ARE TO COMPLY WITH SPECIAL PROVISIONS.
 - SHOP DRAWING SUBMISSIONS FOR APPROVED EQUIVALENT OPTIONS ARE TO BE PROVIDED A MINIMUM OF 4 WEEKS PRIOR TO CONSTRUCTION START.
 - THE CONSTRUCTOR IS RESPONSIBLE FOR SITE LAYOUT AND ACHIEVING THE PROPOSED CONSTRUCTED GRADE WITHIN THE IDENTIFIED MAXIMUM 100MM DEVIATION OR BE ASKED TO RESTORE TO DESIGN GRADE LINE.
 - THE DRAINAGE SUPERINTENDENT WILL BE NOTIFIED, AND APPROVAL WILL BE OBTAINED PRIOR TO TREE REMOVAL. TREES REMOVED WILL BE CONFIRMED FOR THE CANOPY PROTECTION PROGRAM.
 - THE CONSTRUCTOR IS RESPONSIBLE FOR ENVIRONMENTAL COMPLIANCE DURING CONSTRUCTION. THE CONSTRUCTOR IS RESPONSIBLE FOR SITE EROSION CONTROL TO MEET DFO REQUIREMENTS AND OTHER AGENCIES.

THE POSITION OF POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND, WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED.

BEFORE STARTING WORK, THE CONTRACTOR SHALL INFORM THEMSELVES OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE DONE TO THEM.

- SPATIAL DATA:**
- HORIZONTAL DATUM: UTM NAD83-CSRS ZONE 17N
 - VERTICAL DATUM: CGVD28-1978
 - ACCURACY: ABSOLUTE HORIZONTAL AND VERTICAL POSITIONAL ACCURACIES OF ±0.02m

LEGEND

	EXISTING DITCH BOTTOM (NPCA DEM DATA)
	EXISTING DITCH BOTTOM (SURVEYED)
	HISTORICAL GRADELINE
	PROPOSED DRAIN GRADELINE-EWA, 2022
	LEFT BANK
	RIGHT BANK
	EXISTING DRAIN SECTION
	EXISTING STRUCTURE DETAILS
	ASSUMED EXISTING STRUCTURE DETAILS
	EXISTING DRAIN ELEVATION
	PROPOSED DRAIN CENTERLINE ELEVATION
	PROPOSED DRAIN ELEVATION (WHERE MATCHES EXISTING ELEVATION)
	DATA POINT FROM HISTORICAL DESIGN GRADELINE R&A, 1978
	BRIDGE STRUCTURES
	WATER LEVEL FROM SURVEY DATA, INDICATIVE













5		
4		
3		
2		
1	ISSUED FOR REPORT	JUNE 20, 2024
NO.	REVISION DESCRIPTION	DATE

**OIL MILL CREEK DRAIN
PROPOSED OUTLET IMPROVEMENT**

STA 0+000 TO 0+225



DRAWN BY : TJF	APPROVED BY : PCM	PROJECT NO. : -	DRAWING NO. : SD-4
DESIGNED BY : PCM	DATE : 20-JUNE-2024	SCALE : H=1:2500 V=1:25	



OIL MILL CREEK
MUNICIPAL DRAIN

PAUL C MARSH
2024-06-20
PROVINCE OF ONTARIO

DRAWN BY :
TJF

APPROVED BY :
PCM

PROJECT NO. :
—

DRAWING NO. :
OM.GD

DESIGNED BY :
PCM

DATE :
29-MAR-2024

SCALE :
N/A

Appendix B:
Cost Estimates &
Assessment Schedules

Oil Mill Creek Municipal Drain
City of Port Colborne
Regional Municipality of Niagara

Section 74/78 & Section 4 Works under the Municipal Drainage Act.

Oil Mill Creek Summary of Proposed Works

Eligible Administration Costs		
		\$241,446.18
Previous Construction Works Completed but not Assessed		
		\$0.00
Estimated Cost of Construction		
Construction Management Estimated Costs	\$17,500.00	
Section 78 - Proposed Improvements for Construction		
OMC Outlet Improvements	\$27,637.50	
West Branch Drain Improvements - 968m	\$69,025.00	
Oil Mill Creek Improvements - 0+360 to 0+480 Centennial Wetland	\$0.00	
Interval E1 Branch Drain Sta 0+515 to 0+880	\$11,975.00	
Interval E1 Branch Drain From Sta 0+880 to Sta 1+277 - 400m	\$6,455.00	
Section 74 - Maintenance Works for Construction		
E3 Branch Drain	\$10,145.00	
E2 Branch Drain	\$13,300.00	
Oil Mill Creek Drain - Upper Watershed	\$39,325.00	
Sub-Total Estimated Cost of Construction		\$195,362.50
Drain Allowances		
Sub-Total Drain Allowances		\$0.00
Forecasted Total Costs		\$436,808.68
		\$ -
Assessment Schedule		
Benefit Assessment (Section 22)		
		\$0.00
Total - Benefit Assessment (Section 22)		\$0.00
Outlet Liability Assessment (Section 23)		
Private Lands	\$322,785.54	
Road Right of Way Lands	\$44,074.42	
Total - Outlet Liability Assessment (Section 23)		\$366,859.96
Special Benefit Assessment (Section 24)		
Cedar of E1 Branch	\$0.00	
E1 Branch	\$4,516.40	
E2 Branch		
PORT COLBORNE CITY	\$14,452.48	
E3 Branch	\$850.00	
West Branch	\$26,498.95	
OMC Upper		
City of Port Colborne	\$11,208.89	
OMC Middle - Centennial Wetland	\$0.00	
OMC - Outlet works	\$0.00	
Total - Special Benefit Assessment (Section 24)		\$57,526.72
Special Assessments (Section 26)		
E1 Branch		
West Branch		
E2 Branch		
E3 Branch		
OMC Upper		
City of Port Colborne	\$8,540.13	
Niagara Regional Broadband Network, (NRBN)	\$3,881.88	
OMC Middle - Centennial Wetland		
OMC - Outlet works		
City of Port Colborne		
Total - Special Assessments (Section 26)		\$12,422.00
Forecasted Total Assessments		\$436,808.69
		\$0.00



Oil Mill Creek Municipal Drain
City of Port Colborne
Regional Municipality of Niagara

Administration Costs

Categories	Eligible Costs as per Act	Items	Cost	HST	Sub-totals, \$	Totals, \$
ENGINEERING						
	Report Preparation by EWA Engineering Inc.	Study, Analysis and Report Adj	\$93,652.34	\$12,174.80		
		CAD CO-25		\$0.00	\$93,652.34	
		Final CO-30				
		Remove the Wetland CO-32	\$2,820.00			
	Spriet Associates	Survey - Topographic	\$15,394.50	\$2,001.29	\$15,394.50	
	CofPC - Supply of CAD services for design	2020	\$22,087.00			
		2021	\$16,601.00			
		2022	\$28,366.00			
		2023	\$520.00		\$67,574.00	
	Appeal Process Costs including CoR and Tribunal (not estimated and assumed to be zero)				\$0.00	
	Tendering, Contract Administration and Construction Inspection Services (estimated)		\$1,500.00	\$195.00	\$1,500.00	
Total - ENGINEERING						\$178,120.84
ADMINISTRATION						
	Interim Financing Allowance					
		Engineering Fee Interest Charges				
		Financing Charge - 2022	\$7,798.00			
		Financing Charge - 2023	\$17,500.00			
		Financing Charge - 2024	\$22,000.00			
		Construction Fee Interest Charges	\$10,000.00			
					\$57,298.00	
	Legal and Permitting Fees		\$0.00			
	Expenses, where applicable	mailing fees, binding fees, etc.	\$500.00			
	Applicable Taxes	GST Municipal portion (5%)		\$5,527.34	\$6,027.34	
Total - ADMINISTRATION						\$63,325.34
Total Administration Cost						\$241,446.18



Oil Mill Creek Municipal Drain
City of Port Colborne
Regional Municipality of Niagara

Proposed Construction - Cost Estimate

Construction Management Estimated Costs

						Linear, Each or Lump Sum						
Cost ID:	Drain	From STA	To STA	Work	Description	Cost Type	Length	\$/m	Qty	/each	\$	Notes
	Oil Mill Creek Drain			Bonding							\$4,000.00	Budget @ 2.0% of total
	Oil Mill Creek Drain			Environmental Management - Compliance with legislative requirements	Preparation of Environmental Management Plan - Exclusions for SAR incidents that require on site expertise.	Lump Sum					\$2,500.00	Program budget - actual cost will vary
	Oil Mill Creek Drain			Erosion Control During construction -		Lump Sum					\$3,500.00	Program budget - actual cost will vary
	Oil Mill Creek Drain			Construction Management	Traffic Control, Layout, and all compliance items for submission on construction startup.	pro-rated lump sum					\$5,000.00	Budget @ 2.5% of total
	Oil Mill Creek Drain			Tree Replacement Program	Where private trees are removed for the drain and in lieu of compensation a 2 for 1 tree planting program is available for owners.	Each			50	\$50.00	\$2,500.00	Program budget - actual cost will vary
											SubTotal for: \$ 17,500.00	

Section 78 - Proposed Improvements for Construction

OMC Outlet Improvements						Linear, Each or Lump Sum						
Cost ID:	Drain	From STA	To STA	Work	Description	Cost Type	Length	\$/m	Qty	/each	\$	Notes
	Oil Mill Creek	0+000	0+050	Flap Gate Improvements	Cut 300mm circular holes into existing gate sheet steel	each			2	\$1,200.00	\$2,400.00	
					Install new PE flap gate to cover new holes	each			2	\$4,200.00	\$8,400.00	
				Gate Winch replacement	Replace existing wire cable with new longer cable; including new hole through concrete.		22	\$12.50			\$275.00	
				Alternate #1: Power Winch	Replace existing hand winch with electric power winch, 110/120V							
					Winch Lock Box and protective Shield				1	\$1,250.00	\$1,250.00	
					Install new winch (Sherpa ATV 4,500 Lb SATVW4512VT or approved equivalent) or Thern SERIES 4WP2D HIGH SPEED WORM GEAR PORTABLE POWER WINCH		1	\$1,500.00	1	\$600.00	\$2,100.00	
					New 110/120V electric service to winch protective box; including all associated panels and switches. Includes transformer to 12V.				1	\$11,000.00	\$11,000.00	\$14,350.00
				Alternate #2:	Thern Hand winch with brake 4WM2 or approved equivalent		1	\$1,500.00	1	\$1,452.00	\$0.00	
					Include protective lockable box.				1	\$850.00	\$0.00	\$3,802.00
					Cable cover; installed and fixed to existing concrete pipe.		17.5	\$55.00	1	\$350.00	\$1,312.50	
					Daylight existing 600mm PE CB and fix/repair existing lids as required.				2	\$450.00	\$900.00	
											\$0.00	
SubTotal for: OMC Outlet Improvements											\$ 27,637.50	



Oil Mill Creek Improvements - 0+360 to 0+480 Centennial Wetland						Linear, Each or Lump Sum						
Cost ID:	Drain	From STA	To STA	Work	Description	Cost Type	Length	\$/m	Qty	/each	\$	Notes
OMC Middle - Centennial Wetland												
		0+360	0+410	Gravel Riffle and Pools	15m downstream & 20m upstream		50	\$250.00			\$0.00	
	Wetland in Centennial Park			Tree Removal					25	\$250.00	\$0.00	
				Excavation - West Wetland					407.2	\$10.00	\$0.00	
				Excavation - East Wetland					8073	\$10.00	\$0.00	
				Excavation - Channel			60	\$55.00	0	\$0.00	\$0.00	
				Grading for the West and East Crest			420	\$14.50			\$0.00	
				Plant Materials	Cost to acquire and install Terrestrial plants				350	\$12.50	\$0.00	
				Plant Materials	Cost to acquire and install Aquatic plants				240	\$30.00	\$0.00	
SubTotal for: Oil Mill Creek Improvements - 0+360 to 0+480 Centennial Wetland											\$0.00	

West Branch Drain Improvements - 968m						Linear, Each or Lump Sum						
Cost ID:	Drain	From STA	To STA	Work	Description	Cost Type	Length	\$/m	Qty	/each	\$	Notes
				Lower to design grade line	work requires excavation through bedrock; 0+647 to 1+168		541	\$50.00			\$ 27,050.00	
				Lower to design grade line	0+150 to 0+647		497	\$15.00			\$ 7,455.00	
				WB-CS-05 - 2595 Vimy Ridge Rd	Replace with 6m@ 0.11% CSPA 889x610 with 0.050 emb		6	\$275.00	1	\$ 3,000.00	\$ 4,650.00	
				WB-CS-09 - 462 Pinecrest Rd	Replace with 10m@0.11% CSP 900 with 0.050 embedded		10	\$240.00	1	\$ 3,000.00	\$ 5,400.00	
				WB-CS-11 - 446 Pinecrest Rd	Replace with 15m@0.11% CSP 900 with 0.050 embedded		15	\$240.00	1	\$ 3,000.00	\$ 6,600.00	
				WB-CS-12 - 426 Pinecrest Rd	lower existing 3m - CSP Arch 550x900 culvert				1	\$ 3,000.00	\$ 3,000.00	
				WB-CS-14 - 2366 Firelane 2	Replace with 4m @ 0.11% PE 600		5	\$220.00	1	\$ 3,000.00	\$ 4,100.00	
				WB-CS-15 - 2334 Firelane 2	Replace with 6m @ 0.11% PE 600		6	\$220.00	1	\$ 3,000.00	\$ 4,320.00	
				WB-CS-17 - 2316 Firelane 2	Replace with 6m @ 0.11% PE 450		6	\$200.00	1	\$ 3,000.00	\$ 4,200.00	
											\$ -	
				0+000 to 0+150	Vegetation maintenance and spot channel repair only.		150	\$15.00		\$ -	\$ 2,250.00	
SubTotal for: West Branch Drain Improvements - 968m											\$ 69,025.00	

Interval E1 Branch Drain Sta 0+515 to 0+880						Linear, Each or Lump Sum						
Cost ID:	Drain	From STA	To STA	Work	Description	Cost Type	Length	\$/m	Qty	/each	\$	Notes
E1-01	E1 Branch Drain	0+000	0+515			both	0	15	5	\$ 200.00	\$1,000.00	
		0+515	0+880			both	365	15			\$5,475.00	
		0+556	0+566	Existing twin PE culverts to be relaid to grade.	All costs shared 50/50 with owner.	each pipe	10		2	\$ 2,750.00	\$5,500.00	The estimate includes all reinstatement costs.
SubTotal for: Interval E1 Branch Drain Sta 0+515 to 0+880											\$11,975.00	

Interval E1 Branch Drain From Sta 0+880 to Sta 1+277 - 400m						Linear, Each or Lump Sum						
Cost ID:	Drain	From STA	To STA	Work	Description	Cost Type	Length	\$/m	Qty	/each	\$	Notes
		0+880	1+277	Regrade to new design	remove to grade and spread soil adjacent to Drain, cover seed as per spec.		397	15			\$5,955.00	all spoil remains on site.
			1+165	existing crossing to be reinstated or removed.	Cost is conditional on the landowner's directions, to be determined during construction. Cost for removal 100% to the watershed.				1	\$ 500.00	\$500.00	
											\$0.00	
SubTotal for: Interval E1 Branch Drain From Sta 0+880 to Sta 1+277 - 400m											\$6,455.00	



Section 74 - Maintenance Works for Construction

E3 Branch Drain						Linear, Each or Lump Sum						
Cost ID:	Drain	From STA	To STA	Work	Description	Cost Type	Length	\$/m	Qty	/each	\$	Notes
E3-01	E3 Branch	0+000	0+019	Re-align	convert existing to a low-flow / flood-flow cross section	per m	10	\$70.00			\$700.00	
E3-02	E3 Branch	0+019	0+143	Reconstruct to new cross-section	convert existing to a low-flow / flood-flow cross section	per m	124	\$25.00			\$3,100.00	
E3-03	E3 Branch											
E3-04	E3 Branch	0+143	0+226	Re-grade to design		per m	83	\$15.00			\$1,245.00	
		0+079	0+085	replace culvert and improve inlet/outlet conditions	E3-CS-01: 6m-HDPE 450mm REMOVE AND REPLACE CULVERT WITH 525mm D PE CULVERT 6m WITH 100mm B GRAVEL BEDDING AND TO THE PIPE HAUNCHES	both	6	\$125.00	1	\$3,500.00	\$4,250.00	improve bedding to haunches of pipe.
				Remove existing fence and replace with like or better gate for future maintenance access.		each			1	\$850.00	\$850.00	
SubTotal for: E3 Branch Drain											\$10,145.00	

E2 Branch Drain						Linear, Each or Lump Sum						
Cost ID:	Drain	From STA	To STA	Work	Description	Cost Type	Length	\$/m	Qty	/each	\$	Notes
E2-01	E2 Branch Drain			Clean and clear			300	\$15.00			\$4,500.00	
				Re-align outlet	construct new confluence with existing spoil to fill in previous channel. Restoration includes seeding on natural materials fibermat.		90	\$70.00	1	\$ 2,500.00	\$8,800.00	
SubTotal for: E2 Branch Drain											\$ 13,300.00	

Oil Mill Creek						Linear, Each or Lump Sum						
Cost ID:	Drain	From STA	To STA	Work	Description	Cost Type	Length	\$/m	Qty	/each	\$	Notes
OMC-01	Oil Mill Creek Drain - Upper Watershed											
		0+905	1+943	Perform maintenance on existing drain		per m	1800	\$15.00			\$27,000.00	
				Relay Culvert O-CS-08 to design gradeline	includes grouted joint seal and new bedding	each			1	\$5,500.00	\$5,500.00	
				REPLACE O-CS-05 EXISTING 500mm WITH 600 PE 320 kPa	Replace TO DESIGN GRADE WITH 25mm EMBEDDED INVERTS, 12m @ 0.2% US INV = 177.235 DS INV = 177.210	both	12	225	1	\$ 4,125.00	\$6,825.00	
SubTotal for: Oil Mill Creek											\$ 39,325.00	

\$ 195,362.50

Oil Mill Creek Municipal Drain
City of Port Colborne
Regional Municipality of Niagara

Section 24 Special Benefit
The engineer may assess for special benefit any lands for which special benefits have been provided by the drainage works. R.S.O. 1990, c. D.17, s. 24.

Owner	Legal_Txt	Roll No	Municipal Address	Proposed Work	Private	Watershed	Culvert Works	Construction Sub-Total	Construction Admin Fee Allocation 9.0%	Construction Total	Portion of Eng & Admin 55.3%	TOTAL Special Benefit
-------	-----------	---------	-------------------	---------------	---------	-----------	---------------	------------------------	--	--------------------	---------------------------------	-----------------------

E1 Branch

LAUR CAROL JAYNE ESTATE; LAUR, JOHN THOMAS; LAUR, MICHAEL JOHN	CON 1 PT LOT 14	271104000240900	663 PINECREST RD	Existing twin PE culverts to be relaid to grade. All costs shared 50/50 with owner.	50%	50%	\$2,750.00	\$2,750.00	\$246.34	\$2,996.34	\$1,520.06	\$4,516.40
--	-----------------	-----------------	------------------	---	-----	-----	------------	------------	----------	------------	------------	------------

E2 Branch

PORT COLBORNE CITY	CON 1 PT LOT 13 PT LOT 14 PLAN 36 PT BLK A	271104000242101	2767 VIMY RIDGE RD	Re-align outlet construct new confluence with existing spoil to fill in previous channel. Restoration includes seeding on natural materials fibermat.	100%	0%	\$8,800.00	\$8,800.00	\$788.28	\$9,588.28	\$4,864.20	\$14,452.48
--------------------	--	-----------------	--------------------	---	------	----	------------	------------	----------	------------	------------	-------------

E3 Branch

MARTINEAU, WILFRED ROMEO; MARTINEAU, ROXANNE STEPHANIE	CON 1 PT LOT 13	271104000233300	562 CEDAR BAY RD	replace culvert and improve inlet/outlet conditions E3-CS-01: 6m-HDPE 450mm REMOVE AND REPLACE CULVERT WITH 525mm D PE CULVERT 6m WITH 100mm B GRAVEL BEDDING AND TO THE PIPE HAUNCHES	20%	80%	\$850.00	\$850.00	\$0.00	\$850.00	\$0.00	\$850.00
--	-----------------	-----------------	------------------	--	-----	-----	----------	----------	--------	----------	--------	----------

West Branch

GROOM, JOSHUA NATHAN; GROOM, KRISTAL LYNN	PLAN 37 LOT 16 PT LOT 15 NP796	271104000301300	2316 FIRELANE 2	WB-CS-17 - 2316 Firelane 2 Replace with 6m @ 0.11% PE 450	50%	50%	\$ 2,100.00	\$2,100.00	\$188.11	\$2,288.11	\$1,160.78	\$3,448.89
JASEK, COLLEEN R; JASEK, JOHN M	PLAN 37 LOT 17 NP796	271104000301400	2334 FIRELANE 2	WB-CS-15 - 2334 Firelane 2 Replace with 6m @ 0.11% PE 600	50%	50%	\$ 2,160.00	\$2,160.00	\$193.49	\$2,353.49	\$1,193.94	\$3,547.43
HOLODAY, SUSAN-PIETRAS; HOLODAY, RICHARD	PLAN 37 LOT 18 PT LOT 19 NP796	271104000301500	2366 FIRELANE 2	WB-CS-14 - 2366 Firelane 2 Replace with 4m @ 0.11% PE 600	50%	50%	\$ 2,050.00	\$2,050.00	\$183.63	\$2,233.63	\$1,133.14	\$3,366.77
BEGG, TERRY-LYNN	PLAN 37 PT LOT 21 PT LOT 22 NP796	271104000302100	426-434 PINECREST RD	WB-CS-12 - 426 Pinecrest Rd lower existing 3m - CSP Arch 550x900 culvert	50%	50%	\$ 1,500.00	\$1,500.00	\$134.37	\$1,634.37	\$829.13	\$2,463.49
METCALF, IVANA KOMLIJENOVIC; METCALF, THOMAS ASA	CON 1 PT LOT 15 RP 59R7605 PART 1	271104000302610	446 PINECREST RD	WB-CS-11 - 446 Pinecrest Rd Replace with 15m@0.11% CSP 900 with 0.050 embedded	50%	50%	\$ 3,300.00	\$3,300.00	\$295.60	\$3,595.60	\$1,824.08	\$5,419.68
1000071167 ONTARIO INC	HUMBERSTONE CON 1 PT LOT 16 PT LOT 15	271104000302700	462 PINECREST RD	WB-CS-09 - 462 Pinecrest Rd Replace with 10m@0.11% CSP 900 with 0.050 embedded	50%	50%	\$ 2,700.00	\$2,700.00	\$241.86	\$2,941.86	\$1,492.43	\$4,434.28
MACCABE, NATALIE ANN BETHANY; APOLCER, JEREMY MATHEW	CON 1 PT LOT 14 RP 59R3783 PART 1 PART 2	271104000242700	2595 VIMY RIDGE RD	WB-CS-05 - 2595 Vimy Ridge Rd Replace with 6m@ 0.11% CSPA 889x610 with 0.050 emb	50%	50%	\$ 2,325.00	\$2,325.00	\$208.27	\$2,533.27	\$1,285.14	\$3,818.41

OMC Upper

PORT COLBORNE CITY	CON 1 PT LOTS 1-22	271104000499900	1-12 DUNNVILLE SUBD	REPLACE O-CS-05 EXISTING 500mm WITH 600 PE 320 kPa Replace TO DESIGN GRADE WITH 25mm EMBEDDED INVERTS, 12m @ 0.2% US INV = 177.235 DS INV = 177.210	100%	0%	\$6,825.00	\$6,825.00	\$611.36	\$7,436.36	\$3,772.52	\$11,208.89
LAUR CAROL JAYNE ESTATE; LAUR, JOHN THOMAS; LAUR, MICHAEL JOHN	CON 1 PT LOT 14	271104000240900	663 PINECREST RD	Relay Culvert O-CS-08 to design gradeline includes grouted joint seal and new bedding	0%	0%	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00

OMC Middle - Centennial Wetland

There are no Special Benefits assessed.

OMC - Outlet works

There are no Special Benefits assessed for the OMC Outlet

<u><u>\$35,360.00</u></u>	<u><u>\$3,091.30</u></u>	<u><u>\$19,075.42</u></u>	<u><u>\$57,526.72</u></u>
---------------------------	--------------------------	---------------------------	---------------------------

Oil Mill Creek Municipal Drain
City of Port Colborne
Regional Municipality of Niagara

Section 24 Special Benefit

the public utility or road authority shall be assessed for and shall pay all the increase of cost of such drainage works caused by the existence of the works of the public utility or road authority. R.S.O. 1990, c. D.17, s. 26.

Agency	Items	A. Portion of General Construction Costs	B. Channel Improvement Works	C. Culvert Improvement Works	D. Erosion and Sediment Control Works	E. Other Improvement Works	Total Construction Costs	Portion of Administration Costs	TOTAL Special Assessment
Regional Municipality of Niagara									
	There are no RMON roadways within the watershed.						\$ -		\$0.00
	MINISTRY OF TRANSPORTATION ONTARIO						\$ -		\$0.00
Utilities - Enbridge									
	No conflicts assessed during design.						\$ -		\$0.00
E1 Branch									
E2 Branch									
E3 Branch									
West Branch									
OMC Upper									
City of Port Colborne									
	Relay Culvert O-CS-08 to design gradeline includes grouted joint seal and new bedding			\$5,500.00			\$5,500.00	\$3,040.13	\$8,540.13
Niagara Regional Broadband Network, (NRBN)									
	Utility protection and relaying during construction of the culvert.			\$2,500.00			\$2,500.00	\$1,381.88	\$3,881.88
OMC Middle									
OMC - Outlet works									
							\$0.00	\$0.00	\$0.00
Total Section 24 Special Benefit Assessments									\$12,422.00

Oil Mill Creek Municipal Drain
City of Port Colborne
Regional Municipality of Niagara

Maintenance Schedule

		Land Area				Watershed					Interval 1: Watershed less Wetland			Interval 2: E1 Branch		
Owner	Legal_Txt	Roll No	Area in			QRF	SWM	SWMF	QRF-SWMF	QRF Ratio	Total Adjusted Area Int#1	QRF	QRF Ratio	Total Adjusted Area Int#2	QRF	QRF Ratio
			Ha	Drain Ha	Runoff Factor 'C'											
City of Port Colborne - Lands Assessed																
AZZOPARDI, THERESA FRANCES	CON 1 PT LOT 12	271104000226100	3.8339	0.8620	45	2.53066	0	0	2.53066	0.00383	0.862	2.5306596	0.00413	0.8621526	2.53111	0.01912
BRYAN, MILDRED AGNES	CON 1 PT LOT 12 RP 59R12293 PART 2	271104000226200	3.6457	0.4970	45	1.45909	0	0	1.45909	0.00221	0.497	1.4590926	0.00238	0.4972217	1.45974	0.01103
SNEEK, GREGORY ALAN; SNEEK, ARIANE KATRINA	CON 1 PT LOT 12 RP 59R12293 PART 1	271104000226210	0.4046	0.4020	45	1.18019	0	0	1.18019	0.00179	0.402	1.1801916	0.00193	0.4016712	1.17923	0.00891
BULGER, CAROL ANN	CON 1 PT LOT 12	271104000226300	3.8977	0.8720	45	2.56002	0	0	2.56002	0.00387	0.872	2.5600176	0.00418	0.8723415	2.56102	0.01935
RIZZI GIOVANNI ESTATE; RIZZI, MENA	CON 1 PT LOT 12	271104000226301	10.0639	0.5330	35	1.21705	0	0	1.21705	0.00184	0.533	1.2170522	0.00199	0.5330089	1.21707	0.00919
SCHUIT, JOHN; DUMA, PAMELA SUSAN	HUMERSTONE CON 1 PT LOT 12	271104000226400	9.4729	3.1000	30	6.06732	0	0	6.06732	0.00918	3.1	6.06732	0.00991			
DUMA, PAMELA SUSAN; SCHUIT, JOHN	HUMERSTONE CON 1 PT LOT 12 RP 59R15490 PART 3	271104000226402	0.9997	1.0000	30	1.95720	0	0	1.95720	0.00296	1	1.9572	0.00320			
KLAUCK, WESLEY; KLAUCK, LISA	HUMERSTONE CON 1 PT LOT 12 RP 59R15490 PART 2	271104000226403	0.9997	0.8030	30	1.57163	0	0	1.57163	0.00238	0.803	1.5716316	0.00257			
TAVANO, ANTONIO FELICE	HUMERSTONE CON 1 PT LOT 12 RP 59R15490 PART 1	271104000226404	0.9997	0.3220	30	0.63022	0	0	0.63022	0.00095	0.322	0.6302184	0.00103			
BOSLEY, MARY ANN; BOSLEY, ROBERT J	HUMBERSTONE CON 1 PT LOT 12 RP 59R7346 PT PART 1	271104000226417	6.4219	3.3000	30	6.45876	0	0	6.45876	0.00977	2.45	4.79514	0.00783			
BABIRAD, RACHAEL LYNN	CON 1 PT LOT 12 PLAN 59R-6139 PART 1	271104000226418	0.4044	0.4040	50	1.31785	0	0	1.31785	0.00199	0.329	1.073198	0.00175			
BABIRAD, RACHAEL LYNN	CON 1 PT LOT 12 RP59R-6139 PART 2	271104000226419	0.4044	0.4040	50	1.31785	0	0	1.31785	0.00199	0.398	1.298276	0.00212			
FORDY, MARY ANN; FORDY, BRUCE GLEN	CON 1 PT LOT 12 RP59R-6139 PART 3	271104000226420	0.4045	0.3950	50	1.28849	0	0	1.28849	0.00195	0.395	1.28849	0.00210			
MINOR, MARK FRANKLIN; CHRISTIE MINOR, AMBER NOELLE	HUMBERSTONE CON 1 PT LOT 12 RP 59R16386 PART 1	271104000226422	1.0009	0.7390	30	1.44637	0	0	1.44637	0.00219	0.739	1.4463708	0.00236			
MINOR, ANNE CATHERINE; MINOR, MORGAN PAUL	HUMBERSTONE CON 1 PT LOT 12 RP 59R16386 PART 2	271104000226423	1.0010	0.7480	30	1.46399	0	0	1.46399	0.00221	0.748	1.4639856	0.00239			
THOMSON, WAYNE ROBERT; BROWN, NANCY ANN	PLAN 24 PT LOT 1 NP783	271104000226500	0.1635	0.0210	25	0.03425	0	0	0.03425	0.00005	0.021	0.034251	0.00006			
HRABOWSKY, YVONNA VLADISLAVA	PLAN 24 S PT LOT 1 NP783	271104000226800	0.1705	0.0210	25	0.03425	0	0	0.03425	0.00005	0.021	0.034251	0.00006			
MCWHINNIE, ELLEN	PLAN 24 LOT 27 PT LOT 26 NP 783 RP59R 8197 PART 1	271104000229000	0.1579	0.0170	25	0.02773	0	0	0.02773	0.00004	0.017	0.027727	0.00005			
MAFFEI, CHERYL; MAFFEI, TERRY	PLAN 24 LOT 28 LOT 29 NP783	271104000229100	0.2125	0.0310	25	0.05056	0	0	0.05056	0.00008	0.031	0.050561	0.00008			
KAVANAGH, RUTH	PLAN 24 LOT 30 NP783	271104000229200	0.1076	0.0060	25	0.00979	0	0	0.00979	0.00001	0	0	0.00000			
VESPER, DEBORAH SUZZANE	PLAN 36 LOT 1 NP795	271104000229500	0.0690	0.0690	50	0.22508	0	0	0.22508	0.00034	0.069	0.225078	0.00037			
VESPER, DEBORAH	PLAN 36 LOT 2 NP795	271104000229600	0.0710	0.0710	50	0.23160	0	0	0.23160	0.00035	0.071	0.231602	0.00038			
MARQUES, SILVINO MIGUEL DA CRUZ; PEREIRA MARQUES, MARIA	PLAN 795 LOTS 3 AND 4	271104000229700	0.1152	0.1150	50	0.37513	0	0	0.37513	0.00057	0.115	0.37513	0.00061			
MOORE, HARRY JR; MOORE, CAROL	PLAN 36 LOT 5 LOT 6 NP795	271104000229900	0.1826	0.1830	50	0.59695	0	0	0.59695	0.00090	0.183	0.596946	0.00097			
SCHULTZ, WINKLEY JANE; SCHULTZ, DOUGLAS ALLEN	PLAN 36 LOT 7 NP795	271104000230000	0.0914	0.0910	50	0.29684	0	0	0.29684	0.00045	0.091	0.296842	0.00048			
ALEXANDER, KATHRYN RUTH	PLAN 36 LOT 8 NP795	271104000230100	0.0915	0.0910	50	0.29684	0	0	0.29684	0.00045	0.091	0.296842	0.00048			
DE OCAMPO, MARTINIANO; DE OCAMPO, AMELIA	PLAN 36 LOT 9 NP795	271104000230200	0.0916	0.0920	50	0.30010	0	0	0.30010	0.00045	0.092	0.300104	0.00049			
ZIEMIANSKI, DEREK; HOCHREITER, MELISSA MAY	PLAN 36 LOT 10 NP795	271104000230300	0.0916	0.0920	50	0.30010	0	0	0.30010	0.00045	0.092	0.300104	0.00049			
VAN ESCH, STEVEN CARMEN; VAN ESCH, KAITLIN MICHELLE	PLAN 36 LOT 11 NP795	271104000230400	0.0917	0.0920	50	0.30010	0	0	0.30010	0.00045	0.092	0.300104	0.00049			
GAME, RYAN DOUGLAS; GAME, RENEE MARIE	PLAN 36 LOT 12 NP795	271104000230500	0.0918	0.0920	50	0.30010	0	0	0.30010	0.00045	0.092	0.300104	0.00049			
MCCOMBE, LAURIE; DEROSE, LEONARDO	PLAN 36 LOT 13 NP795	271104000230600	0.0918	0.0920	50	0.30010	0	0	0.30010	0.00045	0.092	0.300104	0.00049			
DEROSE, LEONARDO; MCCOMBE, LAURIE	PLAN 36 LOT 14 PT LOT 15 NP795	271104000230700	0.1077	0.1080	50	0.35230	0	0	0.35230	0.00053	0.108	0.352296	0.00058			
HALL, JILLIAN; HALL, BRIAN	PLAN 36 PT LOT 15 PT LOT 16 NP795	271104000230800	0.0409	0.0410	50	0.13374	0	0	0.13374	0.00020	0.041	0.133742	0.00022			
NORMAN, ERNEST J; NORMAN, LOIS A	PLAN 36 PT LOT 16 PT LOT 17 NP795	271104000230900	0.0490	0.0490	50	0.15984	0	0	0.15984	0.00024	0.049	0.159838	0.00026			
MAHONEY, BRIAN	PLAN 36 PT LOT 17 PT LOT 18 NP795	271104000231000	0.0327	0.0330	50	0.10765	0	0	0.10765	0.00016	0.033	0.107646	0.00018			
WILSON, ROBERT FRED JOHN; CANAVAN, WENDY ELIZABETH; WILSON, KIM GREGORY	PLAN 36 PT LOT 18 PT LOT 19 NP795	271104000231100	0.0394	0.0390	50	0.12722	0	0	0.12722	0.00019						
											0.039	0.127218	0.00021			
PJDB PROPERTIES INC	PLAN 36 PT LOT 19 NP795	271104000231200	0.0387	0.0390	50	0.12722	0	0	0.12722	0.00019	0.039	0.127218	0.00021			
LANDON, HANKLIN LIVINGSTONE	PLAN 36 PT LOT 20 NP795	271104000231300	0.0277	0.0280	50	0.09134	0	0	0.09134	0.00014	0.028	0.091336	0.00015			
SWARTZ, DEBORAH ANN LOUISE; SWARTZ, DOUGLAS	PLAN 36 PT LOT 20 NP795	271104000231400	0.0263	0.0260	50	0.08481	0	0	0.08481	0.00013	0.026	0.084812	0.00014			
SOUDER, CATHERINE R	PLAN 795 SAND BEACH	271104000231501	0.5595	0.0230	20	0.03001	0	0	0.03001	0.00005	0.023	0.0300104	0.00005			
MEYER, PETER; SAHS-MEYER, EVA-LYN	PLAN 36 LOT 32 NP795	271104000232700	0.0835	0.0260	20	0.03392	0	0	0.03392	0.00005	0.026	0.0339248	0.00006			
DEMERY, RUTA; DEMERY, GEORGE	PLAN 36 LOT 33 NP795	271104000232800	0.0874	0.0540	20	0.07046	0	0	0.07046	0.00011	0.054	0.0704592	0.00012			
PARR, MARTIN JOHN; PARR, LINDSEY MARIE	PLAN 36 LOT 34 NP795	271104000232900	0.0912	0.0870	20	0.11352	0	0	0.11352	0.00017	0.087	0.1135176	0.00019			
NARDONE, WILMA; NARDONE, JESSICA	PLAN 36 PT LOT 35 NP795	271104000233000	0.0254	0.0250	20	0.03262	0	0	0.03262	0.00005	0.025	0.03262	0.00005			
PRUYN, FRANCIS MATHEUS ROBERT; PRUYN, HENRIETTE	PLAN 36 PT LOT 35 NP795	271104000233100	0.0578	0.0580	20	0.07568	0	0	0.07568	0.00011	0.058	0.0756784	0.00012			
PETRUS, MICHAEL LESLIE; PETRUS, BRADLY MICHAEL	CON 1 PT LOT 13	271104000233200	0.3085	0.3080	50	1.00470	0	0	1.00470	0.00152	0.308	1.004696	0.00164			
MARTINEAU, WILFRED ROMEO; MARTINEAU, ROXANNE STEPHANIE	CON 1 PT LOT 13	271104000233300	1.3341	1.3340	35	3.04606	0	0	3.04606	0.00461	1.334	3.0460556	0.00497			
CHAMISH, ETHAN	PLAN 59 LOT 1 NP818	271104000233400	0.0809	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
MAYO, JAYSEN; GOLFI, KRISTINE	PLAN 59 LOT 2 NP818	271104000233500	0.0809	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.000			

Owner	Legal_Txt	Land Area				Watershed					Interval 1: Watershed less Wetland			Interval 2: E1 Branch		
		Roll No	Area in		Runoff Factor 'C'	QRF	SWM	SWMF	QRF-SWMF	QRF Ratio	Total Adjusted Area Int#1	QRF	QRF Ratio	Total Adjusted Area Int#2	QRF	QRF Ratio
			Ha	Drain Ha												
WARNER, ROSE MARIE; WARNER, TERRY RAY	PLAN 59 LOT 8 LOT 9 NP818	271104000234000	0.1594	0.1590	50	0.51866	0	0	0.51866	0.00078	0.159	0.518658	0.00085			
SCHNEIDER, WENDY LORRAINE; STOUT, CHRISTOPHER JOHN	PLAN 59 LOT 10 NP818	271104000234100	0.0725	0.0730	50	0.23813	0	0	0.23813	0.00036	0.073	0.238126	0.00039			
788833 ONTARIO LIMITED; O'CONNOR, ELIZABETH	PLAN 59 LOT 11 LOT 12 NP818	271104000234200	0.1509	0.1510	50	0.49256	0	0	0.49256	0.00075	0.151	0.492562	0.00080			
AKINS, ANNETTE MARIE MARGARET; AKINS, DAVID LLOYD	PLAN 59 LOT 13 NP818	271104000234300	0.0809	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
DE MELO, SUSETE MARIA; DE MELO, KRISTEN TAYLOR; DE MELO, KYLE DANIEL	PLAN 59 LOT 14 NP818	271104000234400	0.0809	0.0810	50	0.26422	0	0	0.26422	0.00040						
DANIS, GUY GERALD; DANIS, SUSAN ELAINE	PLAN 59 LOT 16 LOT 17 NP818	271104000234500	0.1618	0.1620	50	0.52844	0	0	0.52844	0.00080	0.162	0.528444	0.00086			
DE MELO, KRISTEN TAYLOR; DE MELO, KYLE DANIEL; DE MELO, SUSETE MARIA	PLAN 59 LOT 15 NP 818	271104000234501	0.0809	0.0810	50	0.26422	0	0	0.26422	0.00040						
DANILEWICZ, LESZEK; DANILEWICZ, GRAZYNA	PLAN 59 LOT 18 NP818	271104000234600	0.0809	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
MCCLEMONT, DIANE MARLENE; MCCLEMONT, KENNETH GRANT	PLAN 59 LOT 19 NP818	271104000234700	0.0809	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
REZZA, VITO; REZZA, MARGARET	PLAN 59 LOT 20 NP818	271104000234800	0.0809	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
NAGY, ANITA LOUISE	PLAN 59 LOT 21 NP818	271104000234900	0.0809	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
NAGY, ANITA LOUISE	PLAN 59 LOT 22 NP818	271104000235000	0.0809	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
CARMICHAEL, BAYLEY; GUTTIN, CORDELL	PLAN 59 LOTS 23, 24 NP818	271104000235100	0.1618	0.1620	50	0.52844	0	0	0.52844	0.00080	0.162	0.528444	0.00086			
DANIS, SUSAN ELAINE; DANIS, GUY GERALD	PLAN 59 LOT 25 LOT 26 NP818	271104000235300	0.1618	0.1620	50	0.52844	0	0	0.52844	0.00080	0.162	0.528444	0.00086			
WYBROW, ROBERT WILLIAM	PLAN 59 LOT 27 NP818	271104000235400	0.0809	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
WYBROW, ROBERT WILLIAM	PLAN 59 LOT 28 NP818	271104000235500	0.0809	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
ALEK, CHRISTOPHER PAUL; ALEK, WENDY LEE	PLAN 59 LOT 29 LOT 30 NP818	271104000235600	0.1508	0.1510	50	0.49256	0	0	0.49256	0.00075	0.151	0.492562	0.00080			
KNIGHT-WOODWARD, BARBARA	CON 1 PT LOT 13	271104000235700	0.0689	0.0690	50	0.22508	0	0	0.22508	0.00034	0.069	0.225078	0.00037			
SCOTT, TARA EILEEN	CON 1 PT LOT 13	271104000235800	0.0812	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
RUSTON, CHRISTINE ANN	CON 1 PT LOT 13	271104000235900	0.0812	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
ZIMMERMAN, CARRIE ANN; ZIMMERMAN, JODY ANTHONY	CON 1 PT LOT 13	271104000236000	0.0811	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
SLITER, JOSHUA RAYMOND	CON 1 PT LOT 13	271104000236100	0.1622	0.1620	50	0.52844	0	0	0.52844	0.00080	0.162	0.528444	0.00086	0.0758291	0.24735	0.00187
MCNAY, KIMBERLY MARIE	CON 1 PT LOT 13	271104000236200	0.0810	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
ASHBRIDGE, ALAN; ASHBRIDGE, MARC PETER	CON 1 PT LOT 13	271104000236300	0.0810	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
WEST, DARREN; WEST, ONNA	HUMBERSTONE CON 1 PT LOT 13	271104000236400	0.1628	0.1630	50	0.53171	0	0	0.53171	0.00080	0.163	0.531706	0.00087			
EZEARD, KIMBERLEY	CON 1 PT LOT 13 LALLOUET SKETCH LOT 41	271104000236600	0.0807	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
EZEARD, KIMBERLEY	CON 1 PT LOT 13 LALLOUET SKETCH LOT 42	271104000236800	0.0813	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
GRACE, KATHRYN; GRACE, JOHN	HUMBERSTONE CON 1 PT LOT 13	271104000236900	0.0813	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
SHERSTYUK, ANDRIY	HUMBERSTONE CON 1 PT LOT 13	271104000237000	0.2421	0.2420	50	0.78940	0	0	0.78940	0.00119	0.242	0.789404	0.00129			
KELLY, ROBERT JAMES; KELLY, MARY ANN	CON 1 PT LOT 13 LALLOUET SKETCH LOT 49 LOT 50	271104000237300	0.3094	0.3090	50	1.00796	0	0	1.00796	0.00152	0.309	1.007958	0.00165			
PORT COLBORNE CITY	CON 1 PT LOT 13 LALLOUET SKETCH LOT 51 LOT 52	271104000237400	0.1428	0.1430	50	0.46647	0	0	0.46647	0.00071	0.143	0.466466	0.00076			
COX, REGINAL RICKY	CON 1 PT LOT 13 LALLOUET SKETCH LOT 68	271104000237500	0.0809	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
COX, REGINAL RICKY	CON 1 PT LOT 13 PLAN 59R6615 PART 1	271104000237600	0.4047	0.4050	50	1.32111	0	0	1.32111	0.00200	0.405	1.32111	0.00216			
BEAM, JONATHAN IRVIN	CON 1 PT LOT 13	271104000237610	4.6164	4.6160	30	9.03444	0	0	9.03444	0.01367	4.616	9.0344352	0.01475			
BACSO, MIKLOS; BACSO, NICOLE ELIZABETH	CON 1 PT LOT 13 RP 59R900 PART 3	271104000237700	0.2209	0.2210	50	0.72090	0	0	0.72090	0.00109	0.221	0.720902	0.00118			
STOUT, CHRIS	CON 1 PT LOT 13 RP 59R900 PART 1	271104000237800	0.2140	0.2140	50	0.69807	0	0	0.69807	0.00106	0.214	0.698068	0.00114			
WHITE, MARK ANTHONY	CON 1 PT LOT 13 RP 59R900 PART 2	271104000237801	0.2347	0.2350	50	0.76657	0	0	0.76657	0.00116	0.235	0.76657	0.00125			
HILBORN, KATHERINE ADA; HILBORN, BRYAN PAUL	CON 1 PT LOT 13 AND RP 59R12267 PART 1	271104000237900	0.3565	0.3570	50	1.16453	0	0	1.16453	0.00176	0.357	1.164534	0.00190			
BIDOSKI, ANNETTE MAUREEN; BIDOSKI, MURRAY ALLAN	CON 1 PT LOT 13	271104000238000	0.4033	0.4030	50	1.31459	0	0	1.31459	0.00199	0.403	1.314586	0.00215			
HIGH, DEREK ALLAN; HIGH, KERRI JOANNE	CON 1 PT LOT 13	271104000238100	0.2697	0.2700	50	0.88074	0	0	0.88074	0.00133	0.27	0.88074	0.00144			
SCHNEIDER, JOHN LOUIS; SCHNEIDER, PATRICIA AILEEN	CON 1 PT LOT 13	271104000238200	0.3501	0.3500	50	1.14170	0	0	1.14170	0.00173	0.35	1.1417	0.00186			
NADON, TROY RENE DONALD; ARMENTI-NADON, ANITA	CON 1 PT LOT 13	271104000238300	0.2785	0.2780	50	0.90684	0	0	0.90684	0.00137	0.278	0.906836	0.00148	0.2784381	0.90827	0.00686
ANDERSON, TIMOTHY MICHAEL; ANDERSON, MELISSA MARIE	CON 1 PT LOT 13	271104000238400	0.2632	0.2630	50	0.85791	0	0	0.85791	0.00130	0.263	0.857906	0.00140	0.2631325	0.85834	0.00648
JACKSON, GLEN BRUCE; JACKSON, BONNIE LEE	CON 1 PT LOT 13	271104000238500	0.4041	0.4040	50	1.31785	0	0	1.31785	0.00199	0.404	1.317848	0.00215	0.3986617	1.30043	0.00982
VANDER VAART, LEONARDUS J; VANDER VAART, MARGARET ANN	CON 1 PT LOT 13	271104000238600	11.6929	11.6930	35	26.69980	0	0	26.69980	0.04039	11.678	26.6655452	0.04354	1.8298707	4.17833	0.03156
SZABO, MONICA ANN; GRAY, ROGER WAYNE	CON 1 PT LOT 13	271104000238700	1.9803	1.9800	35	4.52113	0	0	4.52113	0.00684	1.277	2.9159018	0.00476	1.1886337	2.71413	0.02050
BABCOCK, CHARLYN KIM; BABCOCK, TIMOTHY DAVID	RP 59M140 LOT 4 CON 1 PT LOT 13	271104000238701	0.8148	0.8150	45	2.39268	0	0	2.39268	0.00362	0.449	1.3181742	0.00215	0.4488425	1.31771	0.00995
MEDINA OIL FIELD SUPPLY INC	CON 1 PT LOT 13 RP 59R1063 PART 1	271104000238702	6.0722	6.0720	45	17.82618	0	0	17.82618	0.02697	3.837	11.2646646	0.01839			
SAHS-MEYER, EVA-LYN; MEYER, PETER	CON 1 PT LOT 13 PLAN 59R4571 PART 1	271104000238705	0.8092	0.8090	45	2.37506	0	0	2.37506	0.00359	0.809	2.3750622	0.00388	0.809156	2.37552	0.01794
MEYER, PETER; SAHS-MEYER, EVA-LYN	RP 59M140 LOT 3	271104000238706	0.8091	0.8090	45	2.37506	0	0	2.37506	0.00359	0.809	2.3750622	0.00388	0.8091099	2.37538	0.01794
PETRI, SUSANNE CECILE; PETRI HAROLD ESTATE	RP 59M140 LOT 2	271104000238707	0.8091	0.8090	45	2.37506	0	0	2.37506	0.00359	0.809	2.3750622	0.00388	0.8090753	2.37528	0.01794
ROVERSI, JUDITH ANN	P 59M140 LOT 1	271104000238708	0.8090	0.8090	45	2.37506	0	0	2.37506	0.00359	0.809	2.3750622	0.00388	0.8090254	2.37514	0.01794
POULIOT, LIAM ROLAND; BARTOK, ELISE AMANDA	CON 1 PT LOT 13	271104000238800	0.2027	0.2030	45	0.59597	0	0	0.59597	0.00090	0.203	0.5959674	0.00097			
MARSHALL, RODERICK MARK; RUFFO, LEONA JOANNE	HUMBERSTONE CON 1 PT LOT 13 AND RP 59R5794 PART 1	271104000238900	0.1850	0.1850	45	0.54312	0	0	0.54312	0.00082	0.185	0.543123	0.00089			
DESCHAMPS, SALLY ANN; DESCHAMPS, DENZIL ADELARD	CON 1 PT LOT 13	271104000239000	0.2757	0.2760	45	0.81028	0	0	0.81028	0.00123	0.276	0.8102808	0.00132			
WINGER, KAREN JOANNE	CON 1 PT LOT 13	271104000239200	0.1842	0.1840	45	0.54019	0	0	0.54019	0.00082	0.184	0.5401872	0.00088			
NESBITT, DANIELLE MICHELLE; SCOTT, KEVIN JOHN	CON 1 PT LOT 13	271104000239300	0.1997	0.2000	45	0.58716	0	0	0.58716	0.00089	0.2	0.58716	0.00096			
GEADY, CINDY JO; CARRIGAN, FRANCIS JAMES	CON 1 PT LOT 13 RP59R3347 PART 1 TO PART 4	271104000239400	0.3789	0.3790	45	1.11267	0	0	1.11267	0.00168	0.379	1.1126682	0.00182			
PHELAN, DAISY; PHELAN, CHRISTOPHER	CON 1 N PT LOT 13	271104000239600	5.6972	5.6970	30	11.15017	0	0	11.15017	0.01687	5.019	9.8231868	0.01604			
DIMOND, DOUGLAS PATRICK; DIMOND, JANETTE KATHERINE	CON 1 PT LOT 13 RP 59R6412 PART 2	271104000239601	0.4089	0.4090	45	1.20074	0	0	1.20074	0.00182	0.409	1.2007422	0.00196			

Watershed											Interval 1: Watershed less Wetland			Interval 2: E1 Branch		
Owner	Legal_Txt	Land Area									Total Adjusted Area Int#1	QRF	QRF Ratio	Total Adjusted Area Int#2	QRF	QRF Ratio
		Roll No	Area in Drain Ha	Runoff Factor 'C'		QRF	SWM	SWMF	QRF-SWMF	QRF Ratio						
SEREDINE, MATHEW WILLIAM	CON 1 PT LOT 13 RP 59R6412 PART 1	271104000239602	0.4525	0.4460	45	1.30937	0	0	1.30937	0.00198	0.446	1.3093668	0.00214			
O'REILLY, LAURENCE MARIE; HOBMAN, GLEN RICHARD	CON 1 PT LOT 13 RP 59R1063 PART 2	271104000239700	0.2199	0.2160	45	0.63413	0	0	0.63413	0.00096	0.216	0.6341328	0.00104			
SNEEKO LTD	CON 1 PT LOT 13 RP59R 1063 PART 3	271104000239800	0.1319	0.1310	45	0.38459	0	0	0.38459	0.00058	0.131	0.3845898	0.00063			
KOCH, KIRK DOUGLAS; KOCH, NANETTE ANNE	HUMBERSTONE CON 1 PT LOT 13 AND RP 59R1063 PART 4	271104000239900	0.1962	0.1960	45	0.57542	0	0	0.57542	0.00087	0.196	0.5754168	0.00094			
MORRIS, TIMOTHY HENRY; MORRIS, JAMIE LYNN	CON 1 PT LOT 13 RP 59R1063 PART 5	271104000240000	0.1692	0.1690	45	0.49615	0	0	0.49615	0.00075	0.169	0.4961502	0.00081			
GILLESPIE, RITA; GILLESPIE, BLAIR A	CON 1 PT LOT 13 RP 59R3144 PART 2	271104000240100	0.5020	0.5020	45	1.47377	0	0	1.47377	0.00223	0.502	1.4737716	0.00241			
KORTEN, RICHARD	CON 1 PT LOT 13 RP 59R3144 PART 1	271104000240101	0.4601	0.4600	45	1.35047	0	0	1.35047	0.00204	0.46	1.350468	0.00220			
GUDRUNAS, PETER ERWIN	CON 1 PT LOT 13	271104000240200	5.2970	5.2970	30	10.36729	0	0	10.36729	0.01568	4.562	8.9287464	0.01458			
SHIBLEY, JASON HAROLD	CON 1 PT LOT 14	271104000240300	0.4067	0.3950	45	1.15964	0	0	1.15964	0.00175	0.395	1.159641	0.00189			
TAGGART, BRENDA; SCHIRMEISTER, MICHAEL BURT	CON 1 PT LOT 14	271104000240600	0.4988	0.4920	45	1.44441	0	0	1.44441	0.00219	0.492	1.4444136	0.00236			
BARRETT, GORDON JAMES	CON 1 PT LOT 14 RP 59R8871 PART 1	271104000240700	0.5498	0.5470	45	1.60588	0	0	1.60588	0.00243	0.547	1.6058826	0.00262			
GRANT, LINDA MARGARET	CON 1 PT LOT 14 RP 59R947 PART 1	271104000240701	7.3555	7.3550	30	11.99601	0	0	11.99601	0.01815	4.885	7.967435	0.01301	3.0855083	5.03246	0.03801
THIESSEN, STEPHANIE	HUMBERSTONE CON 1 PT LOT 14 RP 59R8871 PT PART 2	271104000240705	17.0560	17.0560	35	38.94567	0	0	38.94567	0.05892	16.995	38.806383	0.06336			
WILLIAMS, ROBERT LEE; WILLIAMS, MARGARET HELEN	HUMBERSTONE CON 1 PT LOT 14 RP 59R17117 PART 1	271104000240707	2.3175	2.3120	35	5.27922	0	0	5.27922	0.00799	2.312	5.2792208	0.00862			
KALYNUIK, CATHY ANN; KALYNUIK, JAMES VAN	CON 1 PT LOT 14 PT 3 - RAILWAY LAND	271104000240710	11.0393	11.0390	30	18.00461	0	0	18.00461	0.02724	9.257	15.098167	0.02465	7.9856202	13.02455	0.09839
BROWN, THEODORE THOMAS RICHARD	CON 1 PT LOT 14	271104000240800	0.4121	0.4120	45	1.20955	0	0	1.20955	0.00183	0.412	1.2095496	0.00197	0.1110761	0.32610	0.00246
LAUR CAROL JAYNE ESTATE; LAUR, JOHN THOMAS; LAUR, MICHAEL JOHN	CON 1 PT LOT 14	271104000240900	19.5469	19.5470	35	44.63362	0	0	44.63362	0.06752						
											18.842	43.0238228	0.07024	12.2354724	27.93848	0.21104
MAZZA, RAYMOND; JORGE, JACINTA	CON 1 PT LOT 14	271104000241000	0.0813	0.0810	50	0.26422	0	0	0.26422	0.00040	0.081	0.264222	0.00043			
ZAJAC, JOHN	CON 1 PT LOT 14	271104000241100	0.1660	0.1660	50	0.54149	0	0	0.54149	0.00082	0.166	0.541492	0.00088			
ZAJAC, JOHN	CON 1 PT LOT 14	271104000241200	0.0695	0.0700	50	0.22834	0	0	0.22834	0.00035	0.07	0.22834	0.00037			
HAAZER, DARIE	CON 1 PT LOT 14	271104000241300	0.0695	0.0690	50	0.22508	0	0	0.22508	0.00034	0.069	0.225078	0.00037			
CRANE, CORNELIA; CRANE, STEPHEN	CON 1 PT LOT 14	271104000241400	0.0694	0.0690	50	0.22508	0	0	0.22508	0.00034	0.069	0.225078	0.00037			
STICKLAND, TANYA; STICKLAND, MATTHEW	CON 1 PT LOT 14	271104000241500	0.1390	0.1390	50	0.45342	0	0	0.45342	0.00069	0.139	0.453418	0.00074			
MCINTYRE, TEIGHAN BEVERLEY; DAVIES, FREDERICK CONRAD	CON 1 PT LOT 14	271104000241600	0.0693	0.0690	50	0.22508	0	0	0.22508	0.00034	0.069	0.225078	0.00037			
PRESSE, CATHERINE ANN; PRESSE, LORIN EARL	CON 1 PT LOT 14	271104000241700	0.1198	0.1200	50	0.39144	0	0	0.39144	0.00059	0.12	0.39144	0.00064			
ICON REINSURANCE INC	CON 1 PT LOT 14	271104000241800	0.0933	0.0930	50	0.30337	0	0	0.30337	0.00046	0.093	0.303366	0.00050			
FIDDY, CHARLES JOHN; FIDDY, LILLIAN NICOLE	CON 1 PT LOT 14 RP59R 8956 PART 1	271104000241900	0.1678	0.1680	50	0.54802	0	0	0.54802	0.00083	0.168	0.548016	0.00089			
TURNER, DAVID BRETT; SINDERLY, MICHAEL JOSEPH; SINDERLY, BARBARA RUTH	CON 1 PT LOT 14 RP59R3837 PART 2 RP59R8956 PART 2	271104000242100	0.2135	0.2140	50	0.69807	0	0	0.69807	0.00106						
											0.214	0.698068	0.00114			
PORT COLBORNE CITY	CON 1 PT LOT 13 PT LOT 14 PLAN 36 PT BLK A	271104000242101	19.0899	18.1900	40	47.46862	0	0	47.46862	0.07181	12.078	31.5187488	0.05146	0.3511497	0.91636	0.00692
GRAYDON, AMANDA	HUMBERSTONE CON 1 PT LOT 14 RP 59R16071 PART 1	271104000242200	0.4174	0.1460	25	0.23813	0	0	0.23813	0.00036	0.146	0.238126	0.00039			
BASCIANO, MARKUS ALEXANDER	HUMBERSTONE CON 1 PT LOTS 13 AND 14 RP 59R16071 PART 2	271104000242202	0.4502	0.1290	25	0.21040	0	0	0.21040	0.00032						
											0.129	0.210399	0.00034			
EVANS, LANA; EVANS, MARK RANDALL	CON 1 PT LOT 14	271104000242300	0.3339	0.1270	25	0.20714	0	0	0.20714	0.00031	0.127	0.207137	0.00034			
KIS, GARY MICHAEL	CON 1 PT LOT 14	271104000242500	0.8129	0.3220	25	0.52518	0	0	0.52518	0.00079	0.322	0.525182	0.00086			
BARKER, VICTOR THOMAS; BARKER, GISELE BRIGITTE	PLAN 42 LOT 80 PT LOTS 70 & 79 NP 801 59R 9778 PART 1	271104000242600	0.5014	0.5010	50	1.63426	0	0	1.63426	0.00247	0.501	1.634262	0.00267			
MACCABE, NATALIE ANN BETHANY; APOLCER, JEREMY MATHEW	CON 1 PT LOT 14 RP 59R3783 PART 1 PART 2	271104000242700	0.2090	0.2090	50	0.68176	0	0	0.68176	0.00103	0.209	0.681758	0.00111			
APOLCER, JEREMY MATTHEW; MACCABE, NATALIE ANN BETHANY	CON 1 PT LOT 14	271104000242900	0.0696	0.0700	50	0.22834	0	0	0.22834	0.00035	0.07	0.22834	0.00037			
SCEPPACERQUA, DREW ALBERT	CON 1 PT LOT 14 RP 59R3783 PART 4	271104000243100	0.1393	0.1390	50	0.45342	0	0	0.45342	0.00069	0.139	0.453418	0.00074			
FIGUEIRA, MARIO	CON 1 PT LOT 14	271104000243200	0.1144	0.1140	50	0.37187	0	0	0.37187	0.00056	0.114	0.371868	0.00061			
FIGUEIRA, MARIO	CON 1 PT LOT 14	271104000243300	0.0697	0.0700	50	0.22834	0	0	0.22834	0.00035	0.07	0.22834	0.00037			
PIZZO, THEODORE ORLANDO	CON 1 PT LOT 14	271104000243400	0.1742	0.1740	50	0.56759	0	0	0.56759	0.00086	0.174	0.567588	0.00093			
8798494 CANADA CORP	CON 1 PT LOT 14	271104000243500	2.0227	2.0230	20	2.63961	0	0	2.63961	0.00399	0.665	0.867692	0.00142			
MCADAM, RICHARD WILSON	CON 1 PT LOT 14	271104000243600	0.7984	0.7980	20	1.04123	0	0	1.04123	0.00158	0.365	0.476252	0.00078			
TOMLINSON, RICHARD MATTHEW	CON 1 PT LOT 14	271104000243700	0.3482	0.3480	25	0.56759	0	0	0.56759	0.00086	0.236	0.384916	0.00063			
HENDERSON, PERIANNE LYNNE; HENDERSON, BRIAN RICHARD	CON 1 PT LOT 14	271104000243800	0.1865	0.1860	25	0.30337	0	0	0.30337	0.00046	0.166	0.270746	0.00044			
JAEGGI, STEPHAN; JAEGGI, TAMMY	CON 1 PT LOT 14	271104000243900	0.2321	0.2320	25	0.37839	0	0	0.37839	0.00057	0.232	0.378392	0.00062			
WELLS, BARBARA ELLEN; BELL, DAVID ANDREW	PLAN 40 LOT 42 LOT 43 NP799	271104000244500	0.1298	0.0170	25	0.02773	0	0	0.02773	0.00004	0.017	0.027727	0.00005			
MCAVOY, MATTHEW JOHN; MCAVOY, CARRIE	PLAN 40 PT LOTS 39,40 & 50 LOTS 41,49 NP 799 RP59R10110 PART 1	271104000244501	0.1697	0.0800	25	0.13048	0	0	0.13048	0.00020						
											0.08	0.13048	0.00021			
ST JOHN'S LUTHERAN CHURCH TRUSTEES	PLAN 40 LOT 48 NP799 CON 1 PT LOT 14	271104000244601	0.4725	0.1940	25	0.31641	0	0	0.31641	0.00048	0.194	0.316414	0.00052			
SOLOMON, NATHAN ALLEN; SOLOMON, RACHEL CHRISTINE	PLAN 40 LOTS 38 51 52 PT LOTS 37 39 40 50 53 NP799 RP 59R1767 PT 2 RP 59R10110 PT 2	271104000244602	0.2364	0.1590	25	0.25933	0	0	0.25933	0.00039						
											0.159	0.259329	0.00042			
PRATT, GARY; PRATT, IRENE	PLAN 40 LOT 36 LOT 54 PT LOTS 35 37 53 & 55 NP799 RP 59R1767 PART 1	271104000244900	0.1838	0.1240	25	0.20224	0	0	0.20224	0.00031						
											0.124	0.202244	0.00033			
LECKIE, PATRICIA EVELYN; LECKIE, JAMES FERRELL	PLAN 799 PT BLK A LOTS 34 AND 56 PT LOTS 35 AND 55	271104000245000	0.1229	0.0860	25	0.14027	0	0	0.14027	0.00021	0.086	0.140266	0.00023			
BANATO, DONNA MARIE; SMITH, PETER WATT	PLAN 799 LOTS 31 TO 33 57 TO 59	271104000245100	0.2362	0.1610	25	0.26259	0	0	0.26259	0.00040	0.161	0.262591	0.00043			
8798494 CANADA CORP	PLAN 799 LOTS 23 24 30 AND 60 PT LOTS 25 29 61 PT BLK C	271104000245200	0.1057	0.0970	25	0.15821	0	0	0.15821	0.00024	0.097	0.158207	0.00026			
OLEKSIK, JAMIESON DEAKIN; OLEKSIK, ALISON MARIE	PLAN 799 PT LOTS 29&61 PLAN 801 L 74,75 &PT LTS 73,76 RP59R7934 PT 1	271104000245301	0.2108	0.1960	25	0.31968	0	0	0.31968	0.00048						
											0.196	0.319676	0.00052			

Watershed											Interval 1: Watershed less Wetland			Interval 2: E1 Branch		
Owner	Legal_Txt	Land Area														
		Roll No	Area in Drain Ha	Runoff Factor 'C'		QRF	SWM	SWMF	QRF-SWMF	QRF Ratio	Total Adjusted Area Int#1	QRF	QRF Ratio	Total Adjusted Area Int#2	QRF	QRF Ratio
ALLEN, CHRISTINE; STINZIANI, LUIGI GINO	PLAN 801 PT BLKS A D AND E PT LOTS 65 66 72 73 76 AND 77 RP 59R15049 PARTS 1 TO 4	271104000245400	0.4451	0.2350	25	0.38329	0	0	0.38329	0.00058	0.235	0.383285	0.00063			
KELLER, ROGER L	PLAN 42 LOT 67 LOT 71 LOT 78 PT LOT 66 PT LOT 72 PT LOT 77 PT BLK D PT BLK E PLAN 40 PT BLK A	271104000245500	0.5330	0.2730	25	0.44526	0	0	0.44526	0.00067	0.273	0.445263	0.00073			
PRIMERANO, ROBIN; CLARE, IRENE; CLARE, JOHN; CLARE, RANDY	PLAN 42 LOT 68 LOT 69 PT LOT 70	271104000245600	1.2159	0.8350	25	1.36189	0	0	1.36189	0.00206	0.835	1.361885	0.00222			
ASHBY, JORDAN; ASHBY, MIRANDA	PLAN M-168 LOT 1	271104000252800	0.8255	0.8260	45	2.42497	0	0	2.42497	0.00367	0.647	1.8994626	0.00310	0.8255224	2.42357	0.01831
LUNDY, JANET; LUNDY, JAMES	PLAN 59M168 LOT 2	271104000252900	0.8364	0.8360	45	2.45433	0	0	2.45433	0.00371	0.811	2.3809338	0.00389	0.8363787	2.45544	0.01855
SAXTON, THOMAS ROBERT; SAXTON, MARIA	PLAN 59M168 LOT 3	271104000253000	0.8468	0.8470	45	2.48662	0	0	2.48662	0.00376	0.847	2.4866226	0.00406	0.8467562	2.48591	0.01878
JAMES, WILLIAM RUSSELL	PLAN 59M168 LOT 4	271104000253100	0.8802	0.8800	45	2.58350	0	0	2.58350	0.00391	0.88	2.583504	0.00422	0.8802355	2.58420	0.01952
DANIEL, VINCENT; DANIEL, ARUNA	PLAN 59M168 LOT 5	271104000253200	0.8147	0.8150	45	2.39268	0	0	2.39268	0.00362	0.815	2.392677	0.00391	0.8146933	2.39178	0.01807
PETERSON, ALLAN BERT; PETERSON, LISA MARIE	PLAN 59M168 LOT 6	271104000253300	0.8156	0.8160	45	2.39561	0	0	2.39561	0.00362	0.816	2.3956128	0.00391	0.8155834	2.39439	0.01809
SALIBA, CARMEL JOSEPH; SALIBA, CHRISTINA GRACE	PLAN 59M168 LOT 7	271104000253400	0.7515	0.7520	45	2.20772	0	0	2.20772	0.00334	0.752	2.2077216	0.00360	0.7515163	2.20630	0.01667
MORRISON, DAVID JOHN; MORRISON, BONNIE SUE	PLAN 59M175 LOT 3	271104000253500	0.8188	0.8190	45	2.40442	0	0	2.40442	0.00364	0.819	2.4044202	0.00393	0.8188377	2.40394	0.01816
ASHBY, JOANNE; SIMPSON, BRIAN	PLAN 59M-175 LOT 4	271104000253600	0.8341	0.8340	45	2.44846	0	0	2.44846	0.00370	0.834	2.4484572	0.00400	0.8340592	2.44863	0.01850
GIRARD, ANGELA JACQUELINE; GIRARD, STEED	PLAN 59M175 LOT 5	271104000253700	0.8423	0.8420	45	2.47194	0	0	2.47194	0.00374	0.842	2.4719436	0.00404	0.8422757	2.47275	0.01868
YOUNG, CHANTAL	PLAN 59M175 LOT 6	271104000253800	0.8343	0.8340	45	2.44846	0	0	2.44846	0.00370	0.834	2.4484572	0.00400	0.834343	2.44946	0.01850
TYPER, JULIANNA MARIANNA	PLAN 59M175 LOT 7	271104000253900	0.8083	0.8080	45	2.37213	0	0	2.37213	0.00359	0.808	2.3721264	0.00387	0.8083253	2.37308	0.01793
COMFORT, CHRISTOPHER HERMAN; COMFORT, JOSEPHINE ANN	PLAN 59M175 LOT 1	271104000254000	0.6468	0.6470	45	1.89946	0	0	1.89946	0.00287	0.647	1.8994626	0.00310	0.6467801	1.89882	0.01434
FONTAINE, BARBARA	PLAN 59M175 LOT 2	271104000254100	0.6235	0.6240	45	1.83194	0	0	1.83194	0.00277	0.624	1.8319392	0.00299	0.6235251	1.83054	0.01383
REPEC, JENNIFER	HUMBERSTONE CON 1 PT LOT 15 PLAN 796 PT BLKS A AND B LOTS 8 TO 14 PT LOT 15 PT WATER LOT	271104000300900	5.9988	3.4410	25	5.61227	0	0	5.61227	0.00849	3.441	5.612271	0.00916			
VIOLIN, ELIZABETH IRENE; VIOLIN, VICTOR EMILIO	PLAN 796 PT BLK B BROKEN LOTS 15 AND 16	271104000301000	2.2699	1.5320	25	2.49869	0	0	2.49869	0.00378	1.532	2.498692	0.00408			
KEPPY, JANE AUDREE; COCKSHUTT, WILLIAM ANTHONY	HUMBERSTONE CON 1 PT LOT 16 PLAN 796 PT BLK B PT WATER LOT RP 59R15083 PARTS 1 AND 2	271104000301100	1.3959	0.5530	25	0.90194	0	0	0.90194	0.00136	0.553	0.901943	0.00147			
BODNER, MEGAN; FARNAN, SCOTT	PLAN 796 PT BLK B RP 59R12610 PART 1	271104000301101	0.5496	0.5500	25	0.89705	0	0	0.89705	0.00136	0.522	0.851382	0.00139			
FALLON, KERRY BERNARD	PLAN 796 PT BLK B RP 59R12610 PART 2	271104000301105	0.9272	0.9270	25	1.51194	0	0	1.51194	0.00229	0.927	1.511937	0.00247			
FLETT, SUSANNE MAY; FLETT, JOHN ROSS	PLAN 796 PT BLK B HUMBERSTONE CON 1 PT WATER LOT IN FRONT OF LOT 16 AND RP 59R11670 PART 1 UNREG	271104000301200	2.3190	1.4780	25	2.41062	0	0	2.41062	0.00365	0.768	1.252608	0.00205			
GROOM, JOSHUA NATHAN; GROOM, KRISTAL LYNN	PLAN 37 LOT 16 PT LOT 15 NP796	271104000301300	0.5266	0.5270	25	0.85954	0	0	0.85954	0.00130	0.527	0.859537	0.00140			
JASEK, COLLEEN R; JASEK, JOHN M	PLAN 37 LOT 17 NP796	271104000301400	0.4571	0.4570	25	0.74537	0	0	0.74537	0.00113	0.457	0.745367	0.00122			
HOLODAY, SUSAN-PIETRAS; HOLODAY, RICHARD	PLAN 37 LOT 18 PT LOT 19 NP796	271104000301500	0.6470	0.6340	25	1.03405	0	0	1.03405	0.00156	0.634	1.034054	0.00169			
MORRISON, HALEY MARILYN; MINOR, DUNCAN LINCOLN	PLAN 37 PT LOT 19 NP796	271104000301600	0.2054	0.2040	25	0.33272	0	0	0.33272	0.00050	0.204	0.332724	0.00054			
KRIEGER, LESLEY EILEEN	PLAN 37 LOT 20 NP796	271104000301700	0.3953	0.3850	25	0.62794	0	0	0.62794	0.00095	0.385	0.627935	0.00103			
BUCHANAN, CHERIE ELIZABETH; BUCHANAN, ROBERT JOSEPH	PLAN 37 PT LOT 21 NP796	271104000301800	0.1490	0.1220	25	0.19898	0	0	0.19898	0.00030	0.122	0.198982	0.00032			
SMITH, MARJORY LEE; SMITH, BRIAN WESLEY	PLAN 37 PT LOT 22 NP796	271104000301900	0.1194	0.0770	25	0.12559	0	0	0.12559	0.00019	0.077	0.125587	0.00021			
SIMPSON, KORY; BELSKY, IGOR	PLAN 37 PT LOT 22 NP796	271104000302000	0.0510	0.0140	25	0.02283	0	0	0.02283	0.00003	0.014	0.022834	0.00004			
WINGER, W A	PLAN 796 PT BLK A	271104000302001	0.4597	0.0660	25	0.10765	0	0	0.10765	0.00016	0.066	0.107646	0.00018			
BEGG, TERRY-LYNN	PLAN 37 PT LOT 21 PT LOT 22 NP796	271104000302100	0.5792	0.5790	25	0.94435	0	0	0.94435	0.00143	0.579	0.944349	0.00154			
METCALF, IVANA KOMLIJENOVIC; METCALF, THOMAS ASA	CON 1 PT LOT 15 RP 59R7605 PART 1	271104000302610	0.4045	0.4050	25	0.66056	0	0	0.66056	0.00100	0.405	0.660555	0.00108			
1000071167 ONTARIO INC	HUMBERSTONE CON 1 PT LOT 16 PT LOT 15	271104000302700	21.1469	21.1470	35	48.28706	0	0	48.28706	0.07305	19.1586138	43.7467788	0.07142			
SAWDON, SONJA ODARKA; SAWDON, DEBORAH ANN	CON 1 PT LOT 15	271104000302800	14.0778	14.0780	35	32.14571	0	0	32.14571	0.04863	14.078	32.1457052	0.05248			
CROWDER, MARTHA; MOORE, RICHARD WILLIAM	CON 1 PT LOT 15 PT LOT 16	271104000302900	20.8284	14.9820	35	34.20990	0	0	34.20990	0.05175	14.543	33.2074862	0.05422			
JONES, LARRY WAYNE	CON 1 PT LOT 15	271104000303000	0.4046	0.4050	45	1.18900	0	0	1.18900	0.00180	0.405	1.188999	0.00194			
SHAUBEL, ALLEN WILLIAM	CON 1 PT LOT 15	271104000303100	0.9148	0.9150	45	2.68626	0	0	2.68626	0.00406	0.915	2.686257	0.00439			
NIGH, HAROLD ALFRED; NIGH, JANE CAROLYN	CON 1 PT LOT 15 PT LOT 16	271104000303200	20.4940	11.3440	35	25.90289	0	0	25.90289	0.03919	11.344	25.9028896	0.04229			
FEHRMAN, AMY LEE; FEHRMAN, PAUL ALLAN	CON 1 PT LOT 15 PT LOT 16	271104000303400	39.5797	10.3560	35	23.64689	0	0	23.64689	0.03577	10.356	23.6468904	0.03861			
FANNON, SYLVIA ROSE; FANNON, WILLIAM THOMAS	CON 1 PT LOT 15	271104000303500	0.4473	0.4470	45	1.31230	0	0	1.31230	0.00199	0.447	1.3123026	0.00214			
PORT COLBORNE CITY	CON 1 PT LOTS 1-22	271104000499900	1.6006	1.6010	80	8.35594	0	0	8.35594	0.01264	1.601	8.3559392	0.01364	0.400825	2.09199	0.01580
				253.8650					589.8652		541.3551			46.2347	112.1228	
Roads																
	ROW_name		Area_Ha													
City of Port Colborne	Pinecrest Road		4.0616	95	25.17270	0	0	25.17270	0.03808				0.04110			
City of Port Colborne	Richard Avenue		0.6159	95	3.81748											

Watershed											Interval 1: Watershed less Wetland		Interval 2: E1 Branch			
Owner	Legal_Txt	Land Area														
		Roll No	Area in Drain		Runoff Factor 'C'	QRF	SWM	SWMF	QRF-SWMF	QRF Ratio	Total Adjusted Area Int#1	QRF Ratio	Total Adjusted Area Int#2	QRF Ratio		
			Ha	Ha												
												612.4915	1.0000	49.5036	132.3828	1.0000

Oil Mill Creek Municipal Drain
City of Port Colborne
Regional Municipality of Niagara

Maintenance Schedule

			Interval 3: West Branch			Interval 4: E2 Branch			Interval 5: E3 Branch			Interval 6: Upper OMC Watershed		
Owner	Legal_Txt	Roll No	Total Adjusted Area Int#3	QRF Ratio	QRF	Total Adjusted Area Int#4	QRF Ratio	QRF	Total Adjusted Area Int#5	QRF Ratio	QRF	Total Adjusted Area Int#6	Outlet Improvements & Maintenance	QRF Ratio
City of Port Colborne - Lands Assessed														
AZZOPARDI, THERESA FRANCES	CON 1 PT LOT 12	271104000226100												
BRYAN, MILDRED AGNES	CON 1 PT LOT 12 RP 59R12293 PART 2	271104000226200												
SNEEK, GREGORY ALAN; SNEEK, ARIANE KATRINA	CON 1 PT LOT 12 RP 59R12293 PART 1	271104000226210												
BULGER, CAROL ANN	CON 1 PT LOT 12	271104000226300												
RIZZI GIOVANNI ESTATE; RIZZI, MENA	CON 1 PT LOT 12	271104000226301												
SCHUIT, JOHN; DUMA, PAMELA SUSAN	HUMERSTONE CON 1 PT LOT 12	271104000226400							3.08254	6.03315	0.16137			
DUMA, PAMELA SUSAN; SCHUIT, JOHN	HUMERSTONE CON 1 PT LOT 12 RP 59R15490 PART 3	271104000226402							0.98034	1.91873	0.05132			
KLAUCK, WESLEY; KLAUCK, LISA	HUMERSTONE CON 1 PT LOT 12 RP 59R15490 PART 2	271104000226403							0.76382	1.49495	0.03999			
TAVANO, ANTONIO FELICE	HUMERSTONE CON 1 PT LOT 12 RP 59R15490 PART 1	271104000226404							0.28759	0.56286	0.01506			
BOSLEY, MARY ANN; BOSLEY, ROBERT J	HUMBERSTONE CON 1 PT LOT 12 RP 59R7346 PT PART 1	271104000226417							2.45024	4.79560	0.12827			
BABIRAD, RACHAEL LYNN	CON 1 PT LOT 12 PLAN 59R-6139 PART 1	271104000226418							0.32943	1.07461	0.02874			
BABIRAD, RACHAEL LYNN	CON 1 PT LOT 12 RP59R-6139 PART 2	271104000226419							0.39844	1.29970	0.03476			
FORDY, MARY ANN; FORDY, BRUCE GLEN	CON 1 PT LOT 12 RP59R-6139 PART 3	271104000226420							0.39483	1.28793	0.03445			
MINOR, MARK FRANKLIN; CHRISTIE MINOR, AMBER NOELLE	HUMBERSTONE CON 1 PT LOT 12 RP 59R16386 PART 1	271104000226422							0.73946	1.44727	0.03871			
MINOR, ANNE CATHERINE; MINOR, MORGAN PAUL	HUMBERSTONE CON 1 PT LOT 12 RP 59R16386 PART 2	271104000226423							0.74776	1.46352	0.03915			
THOMSON, WAYNE ROBERT; BROWN, NANCY ANN	PLAN 24 PT LOT 1 NP783	271104000226500							0.02086	0.03402	0.00091			
HRABOWSKY, YVONNA VLADISLAVA	PLAN 24 S PT LOT 1 NP783	271104000226800							0.02092	0.03412	0.00091			
MCWHINNIE, ELLEN	PLAN 24 LOT 27 PT LOT 26 NP 783 RP59R 8197 PART 1	271104000229000							0.01683	0.02744	0.00073			
MAFFEI, CHERYL; MAFFEI, TERRY	PLAN 24 LOT 28 LOT 29 NP783	271104000229100							0.03084	0.05030	0.00135			
KAVANAGH, RUTH	PLAN 24 LOT 30 NP783	271104000229200												
VESPER, DEBORAH SUZZANE	PLAN 36 LOT 1 NP795	271104000229500							0.06901	0.22511	0.00602			
VESPER, DEBORAH	PLAN 36 LOT 2 NP795	271104000229600							0.05313	0.17333	0.00464			
MARQUES, SILVINO MIGUEL DA CRUZ; PEREIRA MARQUES, MARIA	PLAN 795 LOTS 3 AND 4	271104000229700												
MOORE, HARRY JR; MOORE, CAROL	PLAN 36 LOT 5 LOT 6 NP795	271104000229900							0.07574	0.24706	0.00661			
SCHULTZ, WINKLEY JANE; SCHULTZ, DOUGLAS ALLEN	PLAN 36 LOT 7 NP795	271104000230000							0.03678	0.11997	0.00321			
ALEXANDER, KATHRYN RUTH	PLAN 36 LOT 8 NP795	271104000230100							0.03605	0.11760	0.00315			
DE OCAMPO, MARTINIANO; DE OCAMPO, AMELIA	PLAN 36 LOT 9 NP795	271104000230200							0.03532	0.11522	0.00308			
ZIEMIANSKI, DEREK; HOCHREITER, MELISSA MAY	PLAN 36 LOT 10 NP795	271104000230300							0.03460	0.11286	0.00302			
VAN ESCH, STEVEN CARMEN; VAN ESCH, KAITLIN MICHELLE	PLAN 36 LOT 11 NP795	271104000230400							0.03387	0.11049	0.00296			
GAME, RYAN DOUGLAS; GAME, RENEE MARIE	PLAN 36 LOT 12 NP795	271104000230500							0.03314	0.10811	0.00289			
MCCOMBE, LAURIE; DEROSE, LEONARDO	PLAN 36 LOT 13 NP795	271104000230600							0.03241	0.10574	0.00283			
DEROSE, LEONARDO; MCCOMBE, LAURIE	PLAN 36 LOT 14 PT LOT 15 NP795	271104000230700							0.02837	0.09256	0.00248			
HALL, JILLIAN; HALL, BRIAN	PLAN 36 PT LOT 15 PT LOT 16 NP795	271104000230800												
NORMAN, ERNEST J; NORMAN, LOIS A	PLAN 36 PT LOT 16 PT LOT 17 NP795	271104000230900												
MAHONEY, BRIAN	PLAN 36 PT LOT 17 PT LOT 18 NP795	271104000231000												
WILSON, ROBERT FRED JOHN; CANAVAN, WENDY ELIZABETH; WILSON, KIM GREGORY	PLAN 36 PT LOT 18 PT LOT 19 NP795	271104000231100												
PJDB PROPERTIES INC	PLAN 36 PT LOT 19 NP795	271104000231200												
LANDON, HANKLIN LIVINGSTONE	PLAN 36 PT LOT 20 NP795	271104000231300												
SWARTZ, DEBORAH ANN LOUISE; SWARTZ, DOUGLAS	PLAN 36 PT LOT 20 NP795	271104000231400												
SOUDER, CATHERINE R	PLAN 795 SAND BEACH	271104000231501												
MEYER, PETER; SAHS-MEYER, EVA-LYN	PLAN 36 LOT 32 NP795	271104000232700												
DEMERY, RUTA; DEMERY, GEORGE	PLAN 36 LOT 33 NP795	271104000232800												
PARR, MARTIN JOHN; PARR, LINDSEY MARIE	PLAN 36 LOT 34 NP795	271104000232900												
NARDONE, WILMA; NARDONE, JESSICA	PLAN 36 PT LOT 35 NP795	271104000233000												
PRUYN, FRANCIS MATHEUS ROBERT; PRUYN, HENRIETTE	PLAN 36 PT LOT 35 NP795	271104000233100												
PETRUS, MICHAEL LESLIE; PETRUS, BRADLY MICHAEL	CON 1 PT LOT 13	271104000233200							0.30846	1.00620	0.02691			
MARTINEAU, WILFRED ROMEO; MARTINEAU, ROXANNE STEPHANIE	CON 1 PT LOT 13	271104000233300							1.31456	3.00166	0.08029			
CHAMISH, ETHAN	PLAN 59 LOT 1 NP818	271104000233400							0.08089	0.26386	0.00706			
MAYO, JAYSEN; GOLFI, KRISTINE	PLAN 59 LOT 2 NP818	271104000233500							0.08089	0.26385	0.00706			
EBERHARDT, PAULINE	PLAN 59 LOT 3 NP818	271104000233600				0.08091	0.26393	0.00680						
DIPLOCK, MICHAEL CRAIG	PLAN 59 LOT 4 NP818	271104000233700				0.08091	0.26393	0.00680						
GELKA, BRADLEY GEORGE	PLAN 59 LOT 5 LOT 6 NP818	271104000233800				0.16182	0.52785	0.01361						
MCCARTHY, MICHAEL EARL	PLAN 59 LOT 7 NP818	271104000233900				0.08091	0.26393	0.00680						

Owner	Legal_Txt	Roll No	Interval 3: West Branch			Interval 4: E2 Branch			Interval 5: E3 Branch			Interval 6: Upper OMC Watershed		
			Total Adjusted Area Int#3	QRF Ratio	QRF	Total Adjusted Area Int#4	QRF Ratio	QRF	Total Adjusted Area Int#5	QRF Ratio	QRF	Total Adjusted Area Int#6	Outlet Improvements & Maintenance QRF	QRF Ratio
WARNER, ROSE MARIE; WARNER, TERRY RAY	PLAN 59 LOT 8 LOT 9 NP818	271104000234000				0.15937	0.51985	0.01340						
SCHNEIDER, WENDY LORRAINE; STOUT, CHRISTOPHER JOHN	PLAN 59 LOT 10 NP818	271104000234100				0.07253	0.23658	0.00610						
788833 ONTARIO LIMITED; O'CONNOR, ELIZABETH	PLAN 59 LOT 11 LOT 12 NP818	271104000234200				0.15085	0.49208	0.01269						
AKINS, ANNETTE MARIE MARGARET; AKINS, DAVID LLOYD	PLAN 59 LOT 13 NP818	271104000234300				0.08091	0.26392	0.00680						
DE MELO, SUSETE MARIA; DE MELO, KRISTEN TAYLOR; DE MELO, KYLE DANIEL	PLAN 59 LOT 14 NP818	271104000234400				0.08091	0.26392	0.00680						
DANIS, GUY GERALD; DANIS, SUSAN ELAINE	PLAN 59 LOT 16 LOT 17 NP818	271104000234500				0.16182	0.52786	0.01361						
DE MELO, KRISTEN TAYLOR; DE MELO, KYLE DANIEL; DE MELO, SUSETE MARIA	PLAN 59 LOT 15 NP 818	271104000234501				0.08091	0.26393	0.00680						
DANILEWICZ, LESZEK; DANILEWICZ, GRAZYNA	PLAN 59 LOT 18 NP818	271104000234600				0.08091	0.26394	0.00680						
MCCLEMONT, DIANE MARLENE; MCCLEMONT, KENNETH GRANT	PLAN 59 LOT 19 NP818	271104000234700							0.08089	0.26385	0.00706			
REZZA, VITO; REZZA, MARGARET	PLAN 59 LOT 20 NP818	271104000234800							0.08064	0.26305	0.00704			
NAGY, ANITA LOUISE	PLAN 59 LOT 21 NP818	271104000234900				0.08091	0.26393	0.00680						
NAGY, ANITA LOUISE	PLAN 59 LOT 22 NP818	271104000235000				0.08091	0.26393	0.00680						
CARMICHAEL, BAYLEY; GUTTIN, CORDELL	PLAN 59 LOTS 23, 24 NP818	271104000235100				0.16182	0.52786	0.01361						
DANIS, SUSAN ELAINE; DANIS, GUY GERALD	PLAN 59 LOT 25 LOT 26 NP818	271104000235300				0.16182	0.52787	0.01361						
WYBROW, ROBERT WILLIAM	PLAN 59 LOT 27 NP818	271104000235400				0.08091	0.26393	0.00680						
WYBROW, ROBERT WILLIAM	PLAN 59 LOT 28 NP818	271104000235500				0.08091	0.26393	0.00680						
ALEK, CHRISTOPHER PAUL; ALEK, WENDY LEE	PLAN 59 LOT 29 LOT 30 NP818	271104000235600				0.15076	0.49178	0.01268						
KNIGHT-WOODWARD, BARBARA	CON 1 PT LOT 13	271104000235700				0.06887	0.22466	0.00579						
SCOTT, TARA EILEEN	CON 1 PT LOT 13	271104000235800				0.08121	0.26490	0.00683						
RUSTON, CHRISTINE ANN	CON 1 PT LOT 13	271104000235900				0.08118	0.26479	0.00683						
ZIMMERMAN, CARRIE ANN; ZIMMERMAN, JODY ANTHONY	CON 1 PT LOT 13	271104000236000				0.08114	0.26467	0.00682						
SLITER, JOSHUA RAYMOND	CON 1 PT LOT 13	271104000236100				0.16217	0.52901	0.01364						
MCNAY, KIMBERLY MARIE	CON 1 PT LOT 13	271104000236200				0.08103	0.26431	0.00681						
ASHBRIDGE, ALAN; ASHBRIDGE, MARC PETER	CON 1 PT LOT 13	271104000236300				0.08100	0.26422	0.00681						
WEST, DARREN; WEST, ONNA	HUMBERSTONE CON 1 PT LOT 13	271104000236400				0.16278	0.53099	0.01369						
EZEARD, KIMBERLEY	CON 1 PT LOT 13 LALLOUET SKETCH LOT 41	271104000236600				0.08072	0.26331	0.00679						
EZEARD, KIMBERLEY	CON 1 PT LOT 13 LALLOUET SKETCH LOT 42	271104000236800				0.08132	0.26527	0.00684						
GRACE, KATHRYN; GRACE, JOHN	HUMBERSTONE CON 1 PT LOT 13	271104000236900				0.08134	0.26532	0.00684						
SHERSTYUK, ANDRIY	HUMBERSTONE CON 1 PT LOT 13	271104000237000				0.24210	0.78972	0.02036						
KELLY, ROBERT JAMES; KELLY, MARY ANN	CON 1 PT LOT 13 LALLOUET SKETCH LOT 49 LOT 50	271104000237300				0.30937	1.00916	0.02602						
PORT COLBORNE CITY	CON 1 PT LOT 13 LALLOUET SKETCH LOT 51 LOT 52	271104000237400				0.14276	0.46569	0.01201						
COX, REGINAL RICKY	CON 1 PT LOT 13 LALLOUET SKETCH LOT 68	271104000237500				0.08091	0.26393	0.00680						
COX, REGINAL RICKY	CON 1 PT LOT 13 PLAN 59R6615 PART 1	271104000237600				0.40473	1.32022	0.03404						
BEAM, JONATHAN IRVIN	CON 1 PT LOT 13	271104000237610				4.54055	8.88676	0.22912						
BACSO, MIKLOS; BACSO, NICOLE ELIZABETH	CON 1 PT LOT 13 RP 59R900 PART 3	271104000237700				0.22091	0.72059	0.01858						
STOUT, CHRIS	CON 1 PT LOT 13 RP 59R900 PART 1	271104000237800				0.21396	0.69792	0.01799						
WHITE, MARK ANTHONY	CON 1 PT LOT 13 RP 59R900 PART 2	271104000237801				0.23471	0.76562	0.01974						
HILBORN, KATHERINE ADA; HILBORN, BRYAN PAUL	CON 1 PT LOT 13 AND RP 59R12267 PART 1	271104000237900				0.35652	1.16296	0.02998						
BIDOSKI, ANNETTE MAUREEN; BIDOSKI, MURRAY ALLAN	CON 1 PT LOT 13	271104000238000				0.40330	1.31555	0.03392						
HIGH, DEREK ALLAN; HIGH, KERRI JOANNE	CON 1 PT LOT 13	271104000238100				0.26968	0.87968	0.02268						
SCHNEIDER, JOHN LOUIS; SCHNEIDER, PATRICIA AILEEN	CON 1 PT LOT 13	271104000238200				0.35013	1.14213	0.02945						
NADON, TROY RENE DONALD; ARMENTI-NADON, ANITA	CON 1 PT LOT 13	271104000238300												
ANDERSON, TIMOTHY MICHAEL; ANDERSON, MELISSA MARIE	CON 1 PT LOT 13	271104000238400												
JACKSON, GLEN BRUCE; JACKSON, BONNIE LEE	CON 1 PT LOT 13	271104000238500												
VANDER VAART, LEONARDUS J; VANDER VAART, MARGARET ANN	CON 1 PT LOT 13	271104000238600				1.60650	3.66827	0.09458						
SZABO, MONICA ANN; GRAY, ROGER WAYNE	CON 1 PT LOT 13	271104000238700				0.08863	0.20239	0.00522						
BABCOCK, CHARLYN KIM; BABCOCK, TIMOTHY DAVID	RP 59M140 LOT 4 CON 1 PT LOT 13	271104000238701												
MEDINA OIL FIELD SUPPLY INC	CON 1 PT LOT 13 RP 59R1063 PART 1	271104000238702										3.8371653	11.2651499	0.05031
SAHS-MEYER, EVA-LYN; MEYER, PETER	CON 1 PT LOT 13 PLAN 59R4571 PART 1	271104000238705												
MEYER, PETER; SAHS-MEYER, EVA-LYN	RP 59M140 LOT 3	271104000238706												
PETRI, SUSANNE CECILE; PETRI HAROLD ESTATE	RP 59M140 LOT 2	271104000238707												
ROVERSI, JUDITH ANN	P 59M140 LOT 1	271104000238708												
POULIOT, LIAM ROLAND; BARTOK, ELISE AMANDA	CON 1 PT LOT 13	271104000238800										0.2027042	0.59509899	0.00266
MARSHALL, RODERICK MARK; RUFFO, LEONA JOANNE	HUMBERSTONE CON 1 PT LOT 13 AND RP 59R5794 PART 1	271104000238900										0.1849868	0.54308425	0.00243
DESCHAMPS, SALLY ANN; DESCHAMPS, DENZIL ADELARD	CON 1 PT LOT 13	271104000239000										0.27565	0.80925327	0.00361
WINGER, KAREN JOANNE	CON 1 PT LOT 13	271104000239200										0.1842429	0.54090031	0.00242
NESBITT, DANIELLE MICHELLE; SCOTT, KEVIN JOHN	CON 1 PT LOT 13	271104000239300										0.1996693	0.58618913	0.00262
GEADY, CINDY JO; CARRIGAN, FRANCIS JAMES	CON 1 PT LOT 13 RP59R3347 PART 1 TO PART 4	271104000239400										0.3788554	1.11224368	0.00497
PHELAN, DAISY; PHELAN, CHRISTOPHER	CON 1 N PT LOT 13	271104000239600										5.0192079	9.8235937	0.04387
DIMOND, DOUGLAS PATRICK; DIMOND, JANETTE KATHERINE	CON 1 PT LOT 13 RP 59R6412 PART 2	271104000239601										0.4088907	1.20042132	0.00536

Maintenance Schedule

Owner	Legal_Txt	Roll No	Interval 3: West Branch			Interval 4: E2 Branch			Interval 5: E3 Branch			Interval 6: Upper OMC Watershed		
			Total Adjusted Area Int#3	QRF Ratio		Total Adjusted Area Int#4	QRF Ratio		Total Adjusted Area Int#5	QRF Ratio		Total Adjusted Area Int#6	Outlet Improvements & Maintenance QRF Ratio	
SEREDINE, MATHEW WILLIAM	CON 1 PT LOT 13 RP 59R6412 PART 1	271104000239602										0.4441978	1.3040759	0.00582
O'REILLY, LAURENCE MARIE; HOBMAN, GLEN RICHARD	CON 1 PT LOT 13 RP 59R1063 PART 2	271104000239700										0.2114302	0.62071678	0.00277
SNEEKCO LTD	CON 1 PT LOT 13 RP59R 1063 PART 3	271104000239800										0.1277802	0.37513711	0.00168
KOCH, KIRK DOUGLAS; KOCH, NANETTE ANNE	HUMBERSTONE CON 1 PT LOT 13 AND RP 59R1063 PART 4	271104000239900										0.1912764	0.56154926	0.00251
MORRIS, TIMOTHY HENRY; MORRIS, JAMIE LYNN	CON 1 PT LOT 13 RP 59R1063 PART 5	271104000240000										0.1661666	0.4878319	0.00218
GILLESPIE, RITA; GILLESPIE, BLAIR A	CON 1 PT LOT 13 RP 59R3144 PART 2	271104000240100										0.500185	1.46844312	0.00656
KORTEN, RICHARD	CON 1 PT LOT 13 RP 59R3144 PART 1	271104000240101				0.72232	2.12058	0.05467				0.4595265	1.3490779	0.00602
GUDRUNAS, PETER ERWIN	CON 1 PT LOT 13	271104000240200										4.562013	8.92877184	0.03987
SHIBLEY, JASON HAROLD	CON 1 PT LOT 14	271104000240300										0.3946807	1.1587036	0.00517
TAGGART, BRENDA; SCHIRMEISTER, MICHAEL BURT	CON 1 PT LOT 14	271104000240600										0.4915426	1.44307077	0.00644
BARRETT, GORDON JAMES	CON 1 PT LOT 14 RP 59R8871 PART 1	271104000240700										0.5470063	1.6059011	0.00717
GRANT, LINDA MARGARET	CON 1 PT LOT 14 RP 59R947 PART 1	271104000240701										1.7977293	2.93209649	0.01309
THIESSEN, STEPHANIE	HUMBERSTONE CON 1 PT LOT 14 RP 59R8871 PT PART 2	271104000240705										16.994992	38.8063647	0.17330
WILLIAMS, ROBERT LEE; WILLIAMS, MARGARET HELEN	HUMBERSTONE CON 1 PT LOT 14 RP 59R17117 PART 1	271104000240707										2.3119375	5.27907809	0.02357
KALYNUIK, CATHY ANN; KALYNUIK, JAMES VAN	CON 1 PT LOT 14 PT 3 - RAILWAY LAND	271104000240710										1.2710411	2.07306803	0.00926
BROWN, THEODORE THOMAS RICHARD	CON 1 PT LOT 14	271104000240800										0.3010093	0.8837031	0.00395
LAUR CAROL JAYNE ESTATE; LAUR, JOHN THOMAS; LAUR, MICHAEL JOHN	CON 1 PT LOT 14	271104000240900										3.9846677	9.09859023	0.04063
MAZZA, RAYMOND; JORGE, JACINTA	CON 1 PT LOT 14	271104000241000	0.08129	0.26517	0.00230									
ZAJAC, JOHN	CON 1 PT LOT 14	271104000241100	0.16600	0.54150	0.00469									
ZAJAC, JOHN	CON 1 PT LOT 14	271104000241200	0.06953	0.22680	0.00196									
HAAZER, DARIE	CON 1 PT LOT 14	271104000241300	0.06949	0.22667	0.00196									
CRANE, CORNELIA; CRANE, STEPHEN	CON 1 PT LOT 14	271104000241400	0.06945	0.22653	0.00196									
STICKLAND, TANYA; STICKLAND, MATTHEW	CON 1 PT LOT 14	271104000241500	0.13904	0.45356	0.00393									
MCINTYRE, TEIGHAN BEVERLEY; DAVIES, FREDERICK CONRAD	CON 1 PT LOT 14	271104000241600	0.06932	0.22611	0.00196									
PRESSE, CATHERINE ANN; PRESSE, LORIN EARL	CON 1 PT LOT 14	271104000241700	0.11978	0.39073	0.00338									
ICON REINSURANCE INC	CON 1 PT LOT 14	271104000241800	0.09330	0.30436	0.00264									
FIDDY, CHARLES JOHN; FIDDY, LILLIAN NICOLE	CON 1 PT LOT 14 RP59R 8956 PART 1	271104000241900	0.16775	0.54721	0.00474									
TURNER, DAVID BRETT; SINDERLY, MICHAEL JOSEPH; SINDERLY, BARBARA RUTH	CON 1 PT LOT 14 RP59R3837 PART 2 RP59R8956 PART 2	271104000242100												
PORT COLBORNE CITY	CON 1 PT LOT 13 PT LOT 14 PLAN 36 PT BLK A	271104000242101	0.21352	0.69650	0.00603									
GRAYDON, AMANDA	HUMBERSTONE CON 1 PT LOT 14 RP 59R16071 PART 1	271104000242200	0.58814	1.53481	0.01329									
BASCIANO, MARKUS ALEXANDER	HUMBERSTONE CON 1 PT LOTS 13 AND 14 RP 59R16071 PART 2	271104000242202												
EVANS, LANA; EVANS, MARK RANDALL	CON 1 PT LOT 14	271104000242300												
KIS, GARY MICHAEL	CON 1 PT LOT 14	271104000242500												
BARKER, VICTOR THOMAS; BARKER, GISELE BRIGITTE	PLAN 42 LOT 80 PT LOTS 70 & 79 NP 801 59R 9778 PART 1	271104000242600	0.28262	0.92192	0.00798									
MACCABE, NATALIE ANN BETHANY; APOLCER, JEREMY MATHEW	CON 1 PT LOT 14 RP 59R3783 PART 1 PART 2	271104000242700	0.20896	0.68163	0.00590									
APOLCER, JEREMY MATTHEW; MACCABE, NATALIE ANN BETHANY	CON 1 PT LOT 14	271104000242900	0.06965	0.22720	0.00197									
SCEPPACERQUA, DREW ALBERT	CON 1 PT LOT 14 RP 59R3783 PART 4	271104000243100	0.13931	0.45442	0.00393									
FIGUEIRA, MARIO	CON 1 PT LOT 14	271104000243200	0.11435	0.37301	0.00323									
FIGUEIRA, MARIO	CON 1 PT LOT 14	271104000243300	0.06966	0.22722	0.00197									
PIZZO, THEODORE ORLANDO	CON 1 PT LOT 14	271104000243400	0.17424	0.56838	0.00492									
8798494 CANADA CORP	CON 1 PT LOT 14	271104000243500	0.66468	0.86727	0.00751									
MCADAM, RICHARD WILSON	CON 1 PT LOT 14	271104000243600	0.36536	0.47672	0.00413									
TOMLINSON, RICHARD MATTHEW	CON 1 PT LOT 14	271104000243700	0.23619	0.38523	0.00334									
HENDERSON, PERIANNE LYNNE; HENDERSON, BRIAN RICHARD	CON 1 PT LOT 14	271104000243800	0.16648	0.27153	0.00235									
JAEGGI, STEPHAN; JAEGGI, TAMMY	CON 1 PT LOT 14	271104000243900	0.23208	0.37852	0.00328									
WELLS, BARBARA ELLEN; BELL, DAVID ANDREW	PLAN 40 LOT 42 LOT 43 NP799	271104000244500	0.01748	0.02850	0.00025									
MCAVOY, MATTHEW JOHN; MCAVOY, CARRIE	PLAN 40 PT LOTS 39,40 & 50 LOTS 41,49 NP 799 RP59R10110 PART 1	271104000244501												
ST JOHN'S LUTHERAN CHURCH TRUSTEES	PLAN 40 LOT 48 NP799 CON 1 PT LOT 14	271104000244601	0.07962	0.12987	0.00112									
SOLOMON, NATHAN ALLEN; SOLOMON, RACHEL CHRISTINE	PLAN 40 LOTS 38 51 52 PT LOTS 37 39 40 50 53 NP799 RP 59R1767 PT 2 RP 59R10110 PT 2	271104000244602	0.19421	0.31675	0.00274									
PRATT, GARY; PRATT, IRENE	PLAN 40 LOT 36 LOT 54 PT LOTS 35 37 53 & 55 NP799 RP 59R1767 PART 1	271104000244900	0.15852	0.25855	0.00224									
LECKIE, PATRICIA EVELYN; LECKIE, JAMES FERRELL	PLAN 799 PT BLK A LOTS 34 AND 56 PT LOTS 35 AND 55	271104000245000	0.12401	0.20226	0.00175									
BANATO, DONNA MARIE; SMITH, PETER WATT	PLAN 799 LOTS 31 TO 33 57 TO 59	271104000245100	0.08591	0.14011	0.00121									
8798494 CANADA CORP	PLAN 799 LOTS 23 24 30 AND 60 PT LOTS 25 29 61 PT BLK C	271104000245200	0.16056	0.26187	0.00227									
OLEKSIAK, JAMIESON DEAKIN; OLEKSIAK, ALISON MARIE	PLAN 799 LOTS 23 24 30 AND 60 PT LOTS 25 29 61 PT BLK C	271104000245200	0.09672	0.15775	0.00137									
	PLAN 799 PT LOTS 29&61 PLAN 801 L 74,75 &PT LTS 73,76 RP59R7934 PT 1	271104000245301												
			0.19605	0.31976	0.00277									

			Interval 3: West Branch			Interval 4: E2 Branch			Interval 5: E3 Branch			Interval 6: Upper OMC Watershed											
Owner	Legal_Txt	Roll No	Total Adjusted Area Int#3	QRF	QRF Ratio	Total Adjusted Area Int#4	QRF	QRF Ratio	Total Adjusted Area Int#5	QRF	QRF Ratio	Total Adjusted Area Int#6	Outlet Improvements & Maintenance QRF	QRF Ratio									
ALLEN, CHRISTINE; STINZIANI, LUIGI GINO	PLAN 801 PT BLKS A D AND E PT LOTS 65 66 72 73 76 AND 77 RP 59R15049 PARTS 1 TO 4	271104000245400	0.23464	0.38271	0.00331																		
KELLER, ROGER L	PLAN 42 LOT 67 LOT 71 LOT 78 PT LOT 66 PT LOT 72 PT LOT 77 PT BLK D PT BLK E PLAN 40 PT BLK A	271104000245500	0.27257	0.44456	0.00385																		
PRIMERANO, ROBIN; CLARE, IRENE; CLARE, JOHN; CLARE, RANDY	PLAN 42 LOT 68 LOT 69 PT LOT 70	271104000245600	0.27818	0.45372	0.00393																		
ASHBY, JORDAN; ASHBY, MIRANDA	PLAN M-168 LOT 1	271104000252800																					
LUNDY, JANET; LUNDY, JAMES	PLAN 59M168 LOT 2	271104000252900																					
SAXTON, THOMAS ROBERT; SAXTON, MARIA	PLAN 59M168 LOT 3	271104000253000																					
JAMES, WILLIAM RUSSELL	PLAN 59M168 LOT 4	271104000253100																					
DANIEL, VINCENT; DANIEL, ARUNA	PLAN 59M168 LOT 5	271104000253200																					
PETERSON, ALLAN BERT; PETERSON, LISA MARIE	PLAN 59M168 LOT 6	271104000253300																					
SALIBA, CARMEL JOSEPH; SALIBA, CHRISTINA GRACE	PLAN 59M168 LOT 7	271104000253400																					
MORRISON, DAVID JOHN; MORRISON, BONNIE SUE	PLAN 59M175 LOT 3	271104000253500																					
ASHBY, JOANNE; SIMPSON, BRIAN	PLAN 59M-175 LOT 4	271104000253600																					
GIRARD, ANGELA JACQUELINE; GIRARD, STEED	PLAN 59M175 LOT 5	271104000253700																					
YOUNG, CHANTAL	PLAN 59M175 LOT 6	271104000253800																					
TYPER, JULIANNA MARIANNA	PLAN 59M175 LOT 7	271104000253900																					
COMFORT, CHRISTOPHER HERMAN; COMFORT, JOSEPHINE ANN	PLAN 59M175 LOT 1	271104000254000																					
FONTAINE, BARBARA	PLAN 59M175 LOT 2	271104000254100																					
REPEC, JENNIFER	HUMBERSTONE CON 1 PT LOT 15 PLAN 796 PT BLKS A AND B LOTS 8 TO 14 PT LOT 15 PT WATER LOT	271104000300900	3.44139	5.61291	0.04860																		
VIOLIN, ELIZABETH IRENE; VIOLIN, VICTOR EMILIO	PLAN 796 PT BLK B BROKEN LOTS 15 AND 16	271104000301000	1.53335	2.50089	0.02165																		
KEPPY, JANE AUDREE; COCKSHUTT, WILLIAM ANTHONY	HUMBERSTONE CON 1 PT LOT 16 PLAN 796 PT BLK B PT WATER LOT RP 59R15083 PARTS 1 AND 2	271104000301100	0.55347	0.90271	0.00782																		
BODNER, MEGAN; FARNAN, SCOTT	PLAN 796 PT BLK B RP 59R12610 PART 1	271104000301101	0.52162	0.85076	0.00737																		
FALLON, KERRY BERNARD	PLAN 796 PT BLK B RP 59R12610 PART 2	271104000301105	0.92717	1.51222	0.01309																		
FLETT, SUSANNE MAY; FLETT, JOHN ROSS	PLAN 796 PT BLK B HUMBERSTONE CON 1 PT WATER LOT IN FRONT OF LOT 16 AND RP 59R11670 PART 1 UNREG	271104000301200	0.76804	1.25268	0.01085																		
GROOM, JOSHUA NATHAN; GROOM, KRISTAL LYNN	PLAN 37 LOT 16 PT LOT 15 NP796	271104000301300	0.52663	0.85893	0.00744																		
JASEK, COLLEEN R; JASEK, JOHN M	PLAN 37 LOT 17 NP796	271104000301400	0.45695	0.74528	0.00645																		
HOLODAY, SUSAN-PIETRAS; HOLODAY, RICHARD	PLAN 37 LOT 18 PT LOT 19 NP796	271104000301500	0.63383	1.03377	0.00895																		
MORRISON, HALEY MARILYN; MINOR, DUNCAN LINCOLN	PLAN 37 PT LOT 19 NP796	271104000301600	0.20355	0.33199	0.00287																		
KRIEGER, LESLEY EILEEN	PLAN 37 LOT 20 NP796	271104000301700	0.38450	0.62713	0.00543																		
BUCHANAN, CHERIE ELIZABETH; BUCHANAN, ROBERT JOSEPH	PLAN 37 PT LOT 21 NP796	271104000301800	0.12242	0.19967	0.00173																		
SMITH, MARJORY LEE; SMITH, BRIAN WESLEY	PLAN 37 PT LOT 22 NP796	271104000301900	0.07659	0.12492	0.00108																		
SIMPSON, KORY; BELSKY, IGOR	PLAN 37 PT LOT 22 NP796	271104000302000	0.01345	0.02193	0.00019																		
WINGER, W A	PLAN 796 PT BLK A	271104000302001	0.06709	0.10943	0.00095																		
BEGG, TERRY-LYNN	PLAN 37 PT LOT 21 PT LOT 22 NP796	271104000302100	0.57920	0.94468	0.00818																		
METCALF, IVANA KOMLIJENOVIC; METCALF, THOMAS ASA	CON 1 PT LOT 15 RP 59R7605 PART 1	271104000302610	0.40454	0.65981	0.00571																		
1000071167 ONTARIO INC	HUMBERSTONE CON 1 PT LOT 16 PT LOT 15	271104000302700	17.13391	39.12356	0.33876							2.0244013	4.62251793	0.02064									
SAWDON, SONJA ODARKA; SAWDON, DEBORAH ANN	CON 1 PT LOT 15	271104000302800	14.07773	32.14509	0.27834																		
CROWDER, MARTHA; MOORE, RICHARD WILLIAM	CON 1 PT LOT 15 PT LOT 16	271104000302900										14.535354	33.1900273	0.14822									
JONES, LARRY WAYNE	CON 1 PT LOT 15	271104000303000										0.404551	1.18768083	0.00530									
SHAUBEL, ALLEN WILLIAM	CON 1 PT LOT 15	271104000303100										0.9148382	2.68578199	0.01199									
NIGH, HAROLD ALFRED; NIGH, JANE CAROLYN	CON 1 PT LOT 15 PT LOT 16	271104000303200										11.3437759	25.9023779	0.11567									
FEHRMAN, AMY LEE; FEHRMAN, PAUL ALLAN	CON 1 PT LOT 15 PT LOT 16	271104000303400										10.3558832	23.6466237	0.10560									
FANNON, SYLVIA ROSE; FANNON, WILLIAM THOMAS	CON 1 PT LOT 15	271104000303500										0.4473389	1.31329754	0.00586									
PORT COLBORNE CITY	CON 1 PT LOTS 1-22	271104000499900										1.2010565	6.26855408	0.02799									
			48.89409	104.12775		13.30061	35.56762		12.67864	28.11471		86.6758	203.6690										
Roads																							
	ROW_name																						
City of Port Colborne	Pinecrest Road		1.32990	8.24245	0.07137	0.08090	0.50140	0.01293	0.31820	1.97214	0.05275	0.6159	3.81722502	0.01705									
City of Port Colborne	Richard Avenue																						
City of Port Colborne	Tammy Avenue																						
City of Port Colborne	Tracy Terrace																						
City of Port Colborne	Vimy Ridge Road		0.50320	3.11873	0.02700							0.5489	3.40197242	0.01519									
City of Port Colborne	Vimy Ridge Road																						
City of Port Colborne	Firelane 4				0.7499							4.64773022	0.02076										
City of Port Colborne	June Road																						
City of Port Colborne	Cedar Bay Road																						
			1.8331	11.3612		0.5194	3.2191		1.4960	9.2719		3.2689	20.2600										

Maintenance Schedule

			Interval 3: West Branch			Interval 4: E2 Branch			Interval 5: E3 Branch			Interval 6: Upper OMC Watershed		
Owner	Legal_Txt	Roll No	Total Adjusted Area Int#3			Total Adjusted Area Int#4			Total Adjusted Area Int#5			Total Adjusted Area Int#6		
			QRF			QRF			QRF			QRF		
			QRF Ratio			QRF Ratio			QRF Ratio			QRF Ratio		
			50.7272	115.4889	1.0000	13.8200	38.7868	1.0000	14.1746	37.3866	1.0000	89.9447	223.9290	1.0000

Appendix C:

Supplementary Information & Documents



PORT COLBORNE

Public Works Services

Memorandum

Date: March 12, 2024
To: Amy Parks, Theresa Bukovics
From: Tommy Flannigan, Municipal Drain Technologist
CC'd: Alana Vander Veen, Drainage Superintendent
Paul Marsh, EWA Engineering Appointed Engineer
Re: Recap of May 9th 2022 Oil Mill Creek Drain site visit

Wetland creation

- met at Centennial Park located in Port Colborne, where the Oil Mill Creek Drain crosses through the park
- took a look at the proposed wetland ponds on the North side of the park
- there wasn't any concern expressed from NPCA with what was proposed for the proposed wetland creations

Re-aligning the oxbow west of tennis court

- area of the drain, to create a more direct and easier flow path at the junction of where E2 and E3 Branches connect to the main drain
- discovered a lot more material to be removed then first anticipated for this work to happen
- the suggestion was made that the E2 branch outlet be re-aligned and connect to the main drain at a better angle to increase a better flow

663 Pinecrest Road, Property Roll #240900, E1 Branch location


- looked at the proposed abandonment (but to remain in place) piece the runs East to West stationed 0+516 to 0+645 ish
- the proposed re-alignment that would run from station 0+516 to the North edge of property 663 Pinecrest Rd
- walked the proposed E1 Branch re-alignment
- noticed there is currently a ditch already in place overgrown with weeds and brush
- NPCA agreed this re-alignment doesn't cause any concern as it is already ditch

If we do not hear from you by May 31, 2022, we will assume the notes recorded above to be correct.

Short Duration Rainfall Intensity–Duration–Frequency Data

2022/10/31

Données sur l'intensité, la durée et la fréquence des chutes de pluie de courte durée



Environnement
Canada

Hours/Heures

Duration/Durée

Minutes

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

40

41

42

43

44

45

46

47

48

49

50

51

52

53

54

55

56

57

58

59

60

61

62

63

64

65

66

67

68

69

70

71

72

73

74

75

76

77

78

79

80

81

82

83

84

85

86

87

88

89

90

91

92

93

94

95

96

97

98

99

100

101

102

103

104

105

106

107

108

109

110

111

112

113

114

115

116

117

118

119

120

121

122

123

124

125

126

127

128

129

130

131

132

133

134

135

136

137

138

139

140

141

142

143

144

145

146

147

148

149

150

151

152

153

154

155

156

157

158

159

160

161

162

163

164

165

166

167

168

169

170

171

172

173

174

175

176

177

178

179

180

181

182

183

184

185

186

187

188

189

190

191

192

193

194

195

196

197

198

199

200

201

202

203

204

205

206

207

208

209

210

211

212

213

214

215

216

217

218

219

220

221

222

223

224

225

226

227

228

229

230

231

232

233

234

235

236

237

238

239

240

241

242

243

244

245

246

247

248

249

250

251

252

253

254

255

256

257

258

259

260

261

262

263

264

265

266

267


268

269

270

271

</



Appendix D: Specifications

OIL MILL CREEK MUNICIPAL DRAIN PROJECT SPECIFICATIONS

A1. ROLES	1
A2 ENVIRONMENTAL CONDITIONS AND COMPLIANCE	1
A3 CONSTRUCTION LAYOUT	1
A) STAKES	1
B) PROJECT SIGNAGE	2
A4 INSTALL AND MAINTAIN SEDIMENT CONTROL DEVICES	2
A) SILT FENCE	2
B) SEDIMENT BASINS.....	2
A5 ACCESS & NOTICE	2
A6 AS-CONSTRUCTED DOCUMENTATION	3
B1 EARTH EXCAVATION	4
B2 CONSTRUCTION	4
A) VEGETATION REMOVAL	4
B) EXCAVATION	4
C) PROFILE	4
D) LINE.....	4
E) EXCAVATED MATERIAL.....	4
G) EXCAVATION AT BRIDGE AND CULVERT SITES.....	6
H) OBSTRUCTIONS.....	6
I) FENCES AND PRIVATE FURNITURE OR EQUIPMENT	6
J) TILE OUTLETS.....	6
B3 INSTALLATION OF NEW CULVERT.....	6
B4 HAND LAND RIP RAP WITH FILTER CLOTH	7
B5 TREE PLANTING.....	8
B6 BANK RESTORATION	9
B6.1 'IN WATER WORK'	9
B6.2 LIVE STAKES AND NATIVE PLANT MATERIALS	10
B6.3 EROSION CONTROL BLANKET	10
B.11 OMC DRAIN MECHANICAL ADDITIONS.....	12
B11.1 WINCH REPLACEMENT	12
<i>Hand Operated Winch.....</i>	<i>12</i>
<i>Electrical Operated Power Winch</i>	<i>12</i>
B11.2 WINCH COVER BOX	12
B11.3 ELECTRICAL SUPPLY.....	12
B11.4 RECTANGULAR FLEX FLAP GATE.....	12
C1 COMPLETION	13
C2 AS-CONSTRUCTED DOCUMENTATION.....	13

A1. ROLES

The Contractor is responsible for the construction site including all approvals required for compliance with applicable legislation not already completed by the City of Port Colborne.

The City of Port Colborne, who is further recognized as The Owner, shall be responsible party for allocation of resources in support of construction where required, such as road occupancy permits during construction.

The Drainage Engineer or the Drainage Superintendent shall supervise construction and the Drainage Engineer, Drainage Superintendent or their representative shall respond to any requests by the Contractor and identify any deficiencies between the Contractor's work and the Design documents.

The Drainage Engineer is the responsible designer and will provide technical direction to the Contractor on an as needed and as requested basis from the Drainage Superintendent or their representative.

A2 ENVIRONMENTAL CONDITIONS AND COMPLIANCE

The Contractor is wholly responsible for the site environmental conditions, compliance with applicable approvals and existing legislation. The Owner will facilitate environmental approvals, but the Contractor shall control the site and be the responsible party for all construction activities.

General requirements to be fulfilled by Contractor:

- a) Department of Fisheries and Oceans, DFO.
Requirements to protect Fish and Fish habitat.
- b) Endangered Species Act, 2007 ONTARIO REGULATION 230/08
<https://www.ontario.ca/page/species-risk>
- c) Ontario Water Resources Act, R.S.O. 1990, c. O.40
- d) On-Site and Excess Soil Management, 2019 ONTARIO REGULATION 406/19 Environmental Protection Act
- e) O. Reg. 675/98: Classification and Exemption of Spills and Reporting of Discharges, Environmental Protection Act, R.S.O. 1990

Any other legislation applicable to the jurisdiction of the works.

A3 CONSTRUCTION LAYOUT

Conditions stipulated in the Niagara Peninsula Standard Contract Document also apply. Failure to comply with these conditions will result in a reduction in payment to this item.

a) Stakes

Contractor is responsible for setting any layout, alignment or grade control stakes required for construction. A Stake shall be placed to mark every cross-section grade and a second stake shall be placed to mark the limits of the Working Zone. Work Zone Stake shall be 4' wooden stake painted red at the top of the stake. Grade stake shall be placed at the Work Zone Top of Bank. X-Section stakes shall be placed at a maximum spacing of 25m. A recommended spacing shall coincide with the Profile drawings.

Prior to the start of Construction, the Contractor will stake and identify the difference between the existing grade and the design grade. The Drainage Engineer shall review the stakes and the measurement of the soil to be removed. Post Construction, the Contractor shall remove all stakes.

b) Project Signage

The Contractor is responsible for the installation and removal of all construction signage and is responsible for daily maintenance of all signage throughout the contract.

A4 INSTALL AND MAINTAIN SEDIMENT CONTROL DEVICES

In addition to the conditions stipulated in the Niagara Peninsula Standard Contract Document and OPSS 577, the following shall also apply:

a) SILT FENCE

Silt fence is to be placed prior to disturbing soil adjacent to the drain that could be carried by runoff into the drain. This excludes the area of the drain where The Contractor is working to re-establish Drain grade and cross-section. It includes areas adjacent to the drain impacted by clearing and grubbing for work access.

Silt fence shall be installed in accordance with OPSD 219.190, except that the minimum height above the invert of the drain shall be 500 mm. Silt fence materials shall be in accordance with OPSS 577.05.02.02 for geotextile and OPSS 577.05.03 for stakes. Stakes shall be 1.5 m minimum height.

The silt fence shall remain in place for the duration of the section that the Contractor is working and the Contractor shall make every effort to maintain it throughout the project. The Contractor shall request Approval from the Engineer or the Drainage Superintendent for the removal of the silt fence once each section of the drain is complete. Prior to the removal of the silt fence, the accumulated silt shall be removed and levelled adjacent to the drain in accordance with the disposal of excavated material section.

b) SEDIMENT BASINS

Sediment basins have been provided along the length of the drain in an effort to minimize the transport of sediment. The Contractor shall construct the sediment basins in accordance with the construction drawings in the locations indicated. Relocation of sediment basins can only be undertaken upon approval of the Engineer.

The Sediment basin is to be constructed prior to the upstream work and shall be monitored during construction for sediment accumulation and sediment removed if the basin has more than 50% of the 0.5m depth occupied with sediment. Once the upstream work is complete, the Sediment basin shall be converted from Construction to Final as per the Design Detail Drawings. Sediment accumulated during construction shall be removed and disposed of in the manner directed by the Contract.

A5 ACCESS & NOTICE

The City of Port Colborne's Drainage Superintendent or designate shall provide affected landowners with notice of the commencement of construction.

It will be the Contractor's responsibility to inform the various businesses and residences of daily construction impacts in order to reduce/eliminate any problems with parked vehicles that may

interfere with their operations. Ingress & egress to the abutting businesses and residences must be maintained at all times.

The Contractor shall advise the Police Department, Fire Department and Niagara Emergency Medical Service on a daily basis, with current status of the construction as it pertains to the passage of traffic within the contract limits.

The Contractor will co-ordinate with local transit to ensure minimum interruption to bus schedules. Transit, school buses and garbage and recycling service vehicles will be given priority to maintain their schedule.

The Contractor shall also maintain/provide existing pedestrian access at all times to the businesses and residents during all phases of construction in an acceptable manner.

A6 AS-CONSTRUCTED DOCUMENTATION

For the 'as-constructed' works, the Contractor must provide the City of Port Colborne with an electronic version of the final drainage works as surveyed post construction, to be imported into AutoCAD or GIS. This copy must confirm that the design grade and cross-section details for all drainage work and the invert elevations and lengths for all culverts complies with the Engineer's Report. Survey spacing shall be to a minimum of 25m.

All work must be in an acceptable electronic format that the City of Port Colborne can use and all work must be completed using the verified geodetic benchmarks. The submission of the As-Constructed works will be in a common delimited format having the form as follows:

- Numeric key, Northing, Easting, Elevation, Coded identifier & optional description

For the coded identifiers, the City of Port Colborne will provide a table for reference. The City will certify the as-constructed files with respect to their completeness.

Failure to provide a certified as-built file will result in the delay of substantial completion and/or contract completion. In the event that the contractor asks the City to perform the AS CONSTRUCTED SURVEY, then payment for the lump sum item is negated.

B1 EARTH EXCAVATION

Work under this item shall include the supply of all labour, equipment and materials required for ditch excavation or any other type of excavation or earth work as outlined on the Contract Drawings. Ditch work involves clearing, excavation, leveling, and seeding as required.

Specifications and information on the Contract Drawings shall take precedence over the standard specifications outlined below. The specifications below shall take precedence over the Niagara Peninsula Standard Contract Document Special Provisions B2.

B2 CONSTRUCTION

a) Vegetation Removal

All trees, brush, fallen timber and debris shall be moved from the ditch cross-section and to such a distance on each side to eliminate any interference with the spreading of the spoil. The roots shall be left in the banks if no bank excavation is required as part of the new channel excavation. In wooded or heavily overgrown areas all cleared material may be pushed into piles or rows along the edge of the cleared path and away from leveled spoil. All dead trees along either side of the drain that may impede the performance of the drain if allowed to remain and fall into the ditch, shall be removed prior to excavation and put in piles, unless directed otherwise by the Engineer.

Any tree removed will be offered as wood to the property owner in the form of logs from the trunk where they lay and to be moved from the site by the owner at their expense. Tree tops shall be cut and limbs stacked as piles adjacent to the drain and within the work zone.

b) Excavation

The bottom width and the side slopes of the ditch shall be as shown on the profile(s) and/or cross-sections on the Contract Drawings. Side slopes are normally one and one-half metre horizontal to one metre vertical (1.5:1) unless otherwise noted on the Contract Drawings. If a bottom width is not specified then any excavation required shall be from the bottom of the ditch without disturbing the bank slopes subject to the clearing of brush required as described in a).

c) Profile

The profile(s) on the Contract Drawings show the depth and grade for the drain improvements. The description and elevation of benchmarks that were established during the survey are shown on the profile(s) in the location for each benchmark.

d) Line

The drain shall follow the course of the existing channel and/or shall be constructed in a straight line as outlined on the Contract Drawings. A uniform grade shall be maintained in accordance with the profile(s). A variation of one hundred millimeters (100mm) above the required grade will require the Contractor to remedy the grade to that given on the profile. The Contractor may be required to backfill any portion of the ditch that is excavated more than two hundred millimeters (200mm) below the required grade. All curves shall be made with a minimum radius of fifteen metres (15m).

e) Excavated Material

Excavated material (spoil) shall be deposited on either or both sides of the drain as directed on the Contract Drawings. Spoil upon excavation shall be placed a minimum one (1) metre back from the top of the bank, either existing or new. No excavated material shall be placed in tributary drains, depressions, or low areas, which direct or channel water into the ditch so that

no water will be trapped behind the spoil bank. The excavated material shall be placed and leveled to a maximum depth of three hundred millimeters (300mm); unless otherwise instructed. The edge of the spoil bank away from the ditch shall be feathered down to existing ground. The edge of the spoil bank nearest the ditch shall have a maximum slope of 2:1. The material shall be leveled such that it may be cultivated with ordinary equipment without causing undue hardship on farm machinery and farm personnel. Wherever clearing is necessary prior to leveling, the Contractor shall remove all stumps unless the Contract Drawings specify that stumps can be covered with the leveled spoil. No excavated material shall cover any logs, brush or rubbish of any kind. Large stones or boulders in the leveled spoil that are heavier than fifteen kilograms (15kg or approximately 300mm in size roughly referred to as man stone or the size of a stone that a single person can carry.) shall be moved to the edge of the leveled spoil nearest to the ditch but in general no closer than one metre (1) to the top of bank.

Where it is necessary to straighten any unnecessary bends or irregularities in the alignment of the ditch or to relocate any portion of an existing ditch, the excavation from the new cut shall be used for backfilling the original ditch. Regardless of the distance between the new ditch and old ditch, no extra compensation will be allowed for this work.

If the Contractor obtains written permission from an affected landowner stating that the owner does not wish the spoil to be leveled and such is approved by the Engineer, the Engineer may release the Contractor from the obligation to level the spoil. If spoil is not leveled that was to be leveled as part of the Contract, the Engineer shall determine the credit to be applied to the Contractor's payment. No additional compensation is provided to the owner if the spoil is not leveled.

If the affected landowner requests that the spoil be removed from the site instead of being spread adjacent to the drain within the work zone or that the grading requirement is to a higher standard than suitable for agricultural cultivation, then the Contractor shall provide trucking of the spoil including disposal at a suitable site or additional grading and shall provide the Drainage Superintendent with the specific costs for each landowner who requests such work. The Engineer shall assess the cost of the trucking of spoil to the landowner making such request.

The Engineer may require the Contractor to obtain written statements from any or all of the landowners affected by the leveling of the spoil. A written statement from the owners indicating their complete satisfaction with the leveling of the spoil is sufficient to comply with this specification. The final decision, with respect to leveling of the spoil, shall be made by the Engineer.

f) Excavation Through Woodlots

The Contractor shall minimize disturbance through woodlots by reducing the limit of excavation to the bottom width of the drain and a minimum side slopes. The drain shall be routed around existing trees at the direction of the Drainage Superintendent or where requested by the Engineer.

Prior to performing work through a woodlot, the Contractor in coordination with the Drainage Superintendent shall mark all trees for preservation or removal within the Drain or Workzone. This mark will consist of a physical identification that will be easily understood by the landowner and consist of either colour ribbons or specific paint markings (green to keep, red mark of an 'X' for removal).

g) Excavation at Bridge and Culvert Sites

The Contractor shall excavate or clean through all bridges and culverts to match the grade line and the downstream channel cross-section. Bridges that span from bank to bank may be carefully removed to permit excavation below the bridge and then replaced to original condition. Permanent bridges must be left intact. All necessary care and precautions shall be taken to protect the structure. The Contractor shall notify the Engineer before completing excavation in the area of a bridge or culvert if the excavation will expose the footings or otherwise cause bridge instability.

Where the invert of any pipe culvert is above the grade line, the Contractor will be required to remove the culvert, clean and relay it, so that the invert of the culvert is one hundred and fifty millimetres (150mm) below the grade for the ditch bottom at this location.

h) Obstructions

In all cases, the Contractor shall ensure that the finished drain is clear of obstructions to flow. The contractor will ensure that trunks are cut flush and that any debris or snags are removed as part of the bid price.

i) Fences and private furniture or equipment

The contractor will use the identified work zone for access and shall restore any fences to an equivalent or better condition than before construction. Where possible the Contractor shall preserve existing fences, private equipment and furniture in place but where it must be moved, the Contractor shall in all cases restore to a like or better condition than existed before construction.

j) Tile Outlets

The location of all existing tile outlets may not be shown on the profile for the drain. The Contractor shall contact each owner and ensure that all tile outlets are marked prior to commencing excavation on the owner's property. If a marked tile outlet is damaged during, or altered due to construction, the Contractor shall repair or replace the damaged or altered outlet as part of the Contract. If an existing outlet pipe does require replacement the Contractor shall confirm the replacement outlet pipe with the Engineer. All tile outlets identified are considered part of the bid work.

Additional payment will be allowed for the repair or replacement of any unmarked tile outlets encountered during excavation. Where stone or concrete riprap protection exists at any existing tile outlet such protection shall be removed and replaced as necessary to protect the outlet after reconstruction of the channel.

If any outlet becomes plugged as a result of construction, the Contractor shall be obligated to free such outlet of any impediments. Where any damage results to tile leading to and upstream of the outlet, as a consequence of such construction, the Engineer may direct the Contractor to repair such tile and shall determine a fair compensation to be paid to the Contractor for performing the work.

B3 INSTALLATION OF NEW CULVERT

Work under this item shall include the supply of all labour, equipment and materials required for supply and installation of culverts as outlined on the Contract Drawings. The Niagara Peninsula Standard Contract Document Special Provision B7 shall apply but the specifications and information on the Contract Drawings shall take precedence over Special Provision B7.

The size and material for any new ditch crossings shall be as specified on the Contract Drawings. Any crossings assembled on-site shall be assembled in accordance with the manufacturer's specifications for on-site assembly.

Where a new crossing replaces an existing crossing the following shall apply:

If directed on the drawings that the existing crossing is to be salvaged for the owner the Contractor shall carefully remove the existing crossing and leave along the ditch or haul to a location as specified on the Drawings.

If the existing crossing is not to be saved then the Contractor shall remove and dispose of the existing crossing. Disposal by burying on-site is not permitted.

All new pipe crossings shall be installed a minimum of 100mm below design grade (not as-constructed grade) or at the invert elevations as specified on the Drawings. If the ditch is over excavated greater than 200mm the Contractor shall confirm with the Engineer the elevations for installation of the new pipe crossing.

When an existing crossing is being replaced the contractor shall save all granular and riprap. New crossings can be backfilled with compacted on-site native material that is free of large rocks or stones. Contractor responsible for any damage to a culvert pipe as a result of rocks or stones in the backfill.

All new crossings shall have a minimum 6m laneway width and end slopes shall be at 1:1 slope or flatter. Finished crossing elevation shall provide a minimum of 300mm cover. Finished crossing surface shall be a minimum 150mm depth of Granular A for the minimum 6m width and extending from top of bank to top of bank using salvaged granular or imported granular as required.

Installation of private crossings during construction must be approved by the Engineer before the culvert is installed.

Where riprap protection is called for at either or both ends of a new culvert, such riprap shall be in accordance with Special Provision B4.

Payment will be based on plan quantity.

Riprap to be adequately keyed in along the bottom of the slope. Riprap to extend to top of pipe or as directed on the Drawings. No riprap is required in the ditch bottom on the upstream side of a crossing. If riprap is required in the ditch bottom on the downstream side of a crossing it shall be specified on the Drawings. Any new end face slope not protected by riprap shall be seeded as per specifications for ditch bank seeding.

B4 HAND LAND RIP RAP WITH FILTER CLOTH

Rip rap complete with filter fabric underlay (geotextile) shall be placed by the Contractor at the locations shown on the drawing or as requested by the Drainage Superintendent. Rip rap shall consist of 200 – 250 mm dia. stones (min.) and shall be placed at 300 mm minimum thickness. Along upstream edges, where surface water will enter the drain, the underlay shall extend a minimum of 300 mm upstream from the rip rap and be keyed into the soil a minimum of 300 mm. The finished elevation of the rip rap shall be at design elevation or flush with the ground.

Work under this item shall include the supply of all labour, equipment and materials required for placing riprap as outlined on the Contract Drawings. The Niagara Peninsula Standard Contract Document Special Provision B20 shall apply but the specifications and information on the Contract Drawings shall take precedence over Special Provision B20.

B5 TREE PLANTING

All trees supplied are to be Carolinian Forest or understory native species consistent with Niagara Region.

<https://www.ontario.ca/page/tree-atlas/ontario-southwest>

There will be a 1 year warranty on tree survivability.

B6 BANK RESTORATION

Bank restoration extent is to the identified location indicated on plans and by the Drain Superintendent. Offset stakes are required prior to the commencement of construction. Inspection of the offset stakes is required prior to any work commencing along with the submittal of required environmental approvals.

B6.1 'IN WATER WORK'

All in-water and near water works will be conducted in the dry with appropriate erosion and sediment controls.

The erosion and sediment control strategies outlined on the plans are not static and may need to be upgraded/amended as site conditions change to minimize sediment laden runoff from leaving the work areas. If the prescribed measures on the plans are not effective in preventing the release of deleterious substance, including sediment, then alternative measures must be implemented immediately to minimize potential ecological impacts. NPCA enforcement officer should be immediately contacted, additional ESC measures such as a tarp to be kept on site and used as necessary.

An environmental monitor will attend the site to inspect all new controls, as well as on a regular basis, or following rain/snowmelt event, to monitor site conditions.

All activities, including maintenance procedures, will be controlled to prevent the entry of petroleum products, debris, rubble, concrete, or other deleterious substances into the water. Vehicular refueling and maintenance will be conducted a minimum of 30 metres from the water.

All grades within the Regulatory Flood Plain will be maintained, matched or as specified.

The Proponent/Contractor shall monitor the weather several days in advance of the onset of the project to ensure that the works will be conducted during favourable weather conditions. Should an unexpected storm arise, The Contractor will remove all unfixed items from the 100 year storm flood plain that would have the potential to cause a spill or an obstruction to flow; e.g. fuel tanks, porta-potties, machinery, equipment, construction materials, etc.

All dewatering/unwatering shall be treated and released to the environment at least 30 metres from a watercourse or wetland and allowed to drain through a well vegetated area. No dewatering effluent shall be sent directly to any watercourse, wetland or forest or allowed to drain onto disturbed soils within the work area. These control measures shall be monitored for effectiveness and maintained or revised to meet the objectives of preventing the release of sediment laden water.

All access to the work site shall be from either side of the watercourse. No equipment or vehicles are permitted to cross through the watercourse unless approved by the NPCA.

Fish and wildlife stranded within the work area shall be captured and released in a live suitable habitat upstream of the work area under the supervision of a qualified aquatic biologist. A permit from the Ministry of Environment (MOECP) may be required. The contractor is responsible for organizing any wildlife removal, if required.

Please notify NPCA enforcement officer and an NPCA project Manager 48 hours prior to commencing construction.

An environmental monitor will be on site, and provide advice, to ensure that activities that could have a negative impact to the natural environment are effectively mitigated as construction proceeds. The

environmental monitor shall notify the NPCA enforcement officer and the project manager if an issue arises.

Additional ESC measures or devices may be deemed necessary as site conditions change and shall be installed as directed by the Site Engineer, Contract Administrator or NPCA.

B6.2 LIVE STAKES AND NATIVE PLANT MATERIALS

Contractor to make good any and all damages outside of the work area that may occur as a result of construction at no extra cost.

Tree removals are to occur outside of the active period for bats (April 1st to August 31st) to avoid impacts to species at risk, including bats, birds, and Fowlers Toad. Contractor shall ensure the site complies with The Endangered Species Act.

Construction to occur during the warm water construction timing window of July 15 – March 15. No in water works to occur between March 15 and July 15. Construction timing windows are subject to DFO conditions for approval.

Quantity to be determined based on area of disturbance to be restored.

Live stakes should be from a minimum 2-year-old stock. Live stakes are to be installed at a density of 3 stakes per metre. Live stakes should be pre-soaked (submerged in water) for at least 24 hours after harvesting and immediately before installation.

Live stakes should not be stored for a period longer than 2 days, unless they are being soaked. The contractor shall protect plant materials from drying from the time of harvest until installed.

Live stakes are to be a minimum of 25mm in diameter and cut to a length of 1000mm. Cut angle at the bottom of the stake and flat on top. Trim all side branches while taking care not to damage the bark.

Install live stakes with the buds pointing upwards and thicker stem in the ground.

Live stakes should be installed using a large rubber mallet. 80% of the stake is to be below the surface. Tamp the live stake into the ground at right angle to the surface.

In compact soil a pilot hole should be used to limit damage to the stakes. If using a pilot hole, repack the soil around the live stake. Live stakes should stand firm in the soil following installation.

All stakes not planted to the specifications above will be replaced at the contractor's expense.

B6.3 EROSION CONTROL BLANKET

A Biodegradable erosion control blanket (ECB) shall be installed on all disturbed natural surface following the placement of topsoil and application of the native seed mix.

The ECB must be constructed of 100% woven coconut fibre (eg coir) or straw mat within a geo jute netting (top and bottom) with biodegradable thread. Non - biodegradable material including polypropylene or plastic with a biodegradable rating are not acceptable. The minimum weight of the ECB must be 400g/m² (12 oz/yd²).

To install, the ECB must be unrolled downslope or in the direction of the water flow. Adjacent ECBs should overlap a minimum of 150mm along the edges. at the end of each roll, fold back 100mm to 200mm of the ECB. Overlap this 100mm to 200mm over the start of the next roll. Secure the two layers to the ground securely.

Biodegradable or tapered wooden stakes shall be used to secure the blanket. Stakes shall be installed at the spacing recommended by the ECB manufacturer to prevent surface runoff from eroding the underlying soil.

B.11 OMC DRAIN MECHANICAL ADDITIONS

The following are items of equipment to be added to the OMC Outlet Structure.

In all cases the Contractor is required to confirm all dimensions and fit for all equipment prior to commencing work or ordering parts and equipment to be supplied on the project.

B11.1 WINCH REPLACEMENT

The mounting requirements are dependent on the specific winch selected. The contractor is required to make a shop drawing submission based on using the existing concrete pad (formerly used for stairs) as the mounting platform.

Hand Operated Winch

THERN SERIES MODEL 4WM2 MANUAL WORM GEAR WINCH.

Electrical Operated Power Winch

SHERPA ATV 4,500 LB SATVW4512VT OR APPROVED EQUIVALENT.

ALTERNATE POWER WINCH: THERN SERIES 4WP2D HIGH SPEED WORM GEAR PORTABLE POWER WINCH

B11.2 WINCH COVER BOX

The requirements for the cover box are based on the winch selected. A hand operated winch only requires that the box be capable of resisting shove ice and operating in winter conditions.

Supply a Lockable Steel Equipment Box Rated NEMA 6P (IP68) to existing Concrete pad with Stainless Steel Concrete anchor bolts. Size of the box is determined by the selected winch.

Electrical connections through the box to be water tight sealed connections.

B11.3 ELECTRICAL SUPPLY

The existing gate is to be extended to match the height of gates 1 and 2 using the same materials as the existing gate. Contractor to weld extension to ensure that no gaps permit water to flow through the extension. Existing threaded rod connection to remain as is.

Contractor shall supply a welding diagram prior to commencement of the work.


B11.4 RECTANGULAR FLEX FLAP GATE

GENERAL SPECIFICATION Steel cutout: Circular: ID 300mm nominal, contractor to confirm.

Flex Flap gate: Rectangular size to fit within existing rib structure of steel flap gate. Carbon Black content of the raw material used must be not less than 2% in weight. The requirement of the carbon black is to give UV protection from sunlight. Vulcanized Rubber Wall Mounted Flap Gate (Rectangular Type) is to be flexible such that it opens and closes easily.

Installation

Bolt Flex Flap gate to the existing steel frame flap gate. Ensure that the stainless-steel ribs of the PE flap gate extend past the edges of the circular hole cut into the steel.



C1 COMPLETION

At the time of final inspection, all work in the contract shall have the full dimensions and cross-sections specified.

Payment is for all work complete on the basis of a measured linear distance inclusion of all items identified above. Where a culvert is removed and reinstalled, compensation shall be in the form of a per each payment. Where a tile is discovered and constructed as an outlet, compensation will be in the form of a per each payment for tile outlets repaired.

C2 AS-CONSTRUCTED DOCUMENTATION

For the 'as-constructed' works, the Contractor must provide the City of Port Colborne with an electronic version of the final drainage works as surveyed post construction, to be imported into AutoCAD or GIS. This copy must confirm that the design grade and cross-section details for all drainage work and the invert elevations and lengths for all culverts complies with the Engineer's Report. Survey spacing shall be to a minimum of 25m.

All work must be in an acceptable electronic format that the City of Port Colborne can use and all work must be completed using the verified geodetic benchmarks. The submission of the As-Constructed works will be in a common delimited format having the form as follows:

Numeric key, Northing, Easting, Elevation, Coded identifier & optional description

For the coded identifiers, the City of Port Colborne will provide a table for reference along with an example file from a past project for comparison. The City will certify the as-constructed files with respect to their completeness.


Failure to provide a certified as-built file will result in the delay of substantial completion and/or contract completion. In the event that the contractor asks the City to perform the AS CONSTRUCTED SURVEY, then payment for the lump sum item is negated.

A4 PAYMENT; Payment in full at the lump sum bid price for this item shall be made only upon completion and approval by the Contract Administrator.

Appendix E:

Assessment Map Atlas

Oil Mill Creek Drain



OMC Drain Assessment
Map Atlas

- MAP LEGEND
- OldMill_catchment
 - OMC_D_90 copy
 - Oil Mill Creek Drain
 - OMC Centennial Wetland
 - OMC E1 Branch
 - OMC E2 Branch
 - OMC E3 Branch
 - OMC West Branch
 - OMC Assessment Tables
 - OMC-parcel202307
 - ROW
 - OMC Assessment Schedules
 - E1 Branch
 - E2 Branch
 - E3 Branch
 - West Branch
 - Centennial Wetland Branch
 - SWM_70
 - Crest
 - BuildingFootprints
 - NPCA Environment
 - Regulated_Shoreline_Extent
 - GR_RegulatedWetlands_NPCA
 - Contours
 - Road_Segments
 - MUN
 - PRIV
 - Lake_& Canal




40 0 40 80 m
Scale 1:2,500



A1

A2

Oil Mill Creek Drain



OMC Drain Assessment
Map Atlas

- MAP LEGEND
- OldMill_catchment
 - OMC Assessment Tables
 - OMC-parcel202307
 - ROW
 - BuildingFootprints
 - NPCA Environment
 - GR_RegulatedWetlands_NPCA
 - Contours
 - Road_Segments
 - MUN
 - ON



40 0 40 80 m
Scale 1:2,500



A3